

# User's Guide


# **GS1350** Series

GbE Layer 2 PoE Switch

### **Default Login Details**

Management IP Address	http://DHCP-assigned IP or http://192.168.1.1
User Name	admin
Password	1234

Version 4.70 Edition 1, 06/2020



Copyright © 2020 Zyxel Communications Corporation

### IMPORIANT!

### READ CAREFULLY BEFORE USE

### KEEP THIS GUIDE FOR FUTURE REFERENCE.

This is a User's Guide for a series of products. Not all products support all firmware features. Screenshots and graphics in this book may differ slightly from your product due to differences in your product firmware or your computer operating system. Every effort has been made to ensure that the information in this manual is accurate.

### Related Documentation

• CLI Reference Guide

The CLI Reference Guide explains how to use the Command-Line Interface (CLI) to configure the Switch.

Note: It is recommended you use the Web Configurator to configure the Switch.

• Quick Start Guide

The Quick Start Guide shows how to connect the Switch.

• Online Help

Click the help link for a description of the fields in the Switch menus.

• More Information

Go to https://businessforum.zyxel.com for product discussions.

Go to **support.zyxel.com** to find other information on the Switch.



### Document Conventions

### Warnings and Notes

These are how warnings and notes are shown in this guide.

### Wamings tell you about things that could harm you or your device.

Note: Notes tell you other important information (for example, other things you may need to configure or helpful tips) or recommendations.

### Syntax Conventions

- All models may be referred to as the "Switch" in this guide.
- Product labels, screen names, field labels and field choices are all in **bold** font.
- A right angle bracket (>) within a screen name denotes a mouse click. For example, **Basic Setting** > **IP Setup** > **IP Configuration** > **Network Proxy Configuration** means you first click **Basic Setting** in the navigation panel, then the **IP Setup** sub menu, then **IP Configuration** and finally **Network Proxy Configuration** to get to that screen.

### Icons Used in Figures

Figures in this user guide may use the following generic icons. The Switch icon is not an exact representation of your device.

Switch	Generic Router	Wireless Router / Access Point
Generic Switch	Smart TV	Desktop
	IP Camera	Printer
Server		

### Contents Overview

User's Guide	
Getting to Know Your Switch	
Hardware Installation and Connection	
Hardware Panels	
Te c hnic a l Re fe re nc e	42
Web Configurator	
Initial Setup Example	
Tutorials	
Status	
Basic Setting	
VLAN	
Static MAC Forwarding	
Static Multicast Forwarding	
Filtering	
Spanning Tree Protocol	
Bandwidth Control	
Broadcast Storm Control	
Mirroring	
Link Aggregation	
Port Security	
Time Range	
Queuing Method	
Multicast	
AAA	
DHCP Snooping	
Loop Guard	
Error Disable	
Green Ethernet	
Link Layer Discovery Protocol (LLDP)	
Auto PD Recovery	
ONVIF	
Differentiated Services	
DHCP	
ARP Setup	
Maintenance	
Access Control	
Diagnostic	

System Log	5
Syslog Setup	6
Cluster Management	9
MAC Table	5
ARP Table	8
Path MTU Table	С
Configure Clone	1
IPv6 Neighbor Table	3
Port Status	5
Surveillance Mode	2
Quick Setup	7
System	8
Port	3
Switching	3
Networking	С
Security	4
Maintenance	6
oubleshooting and Appendices	L
Troubleshooting	2

### Table of Contents

Contents Overview	
Table of Contents	6
Part I: Use r's Guide	
Chapter 1 Getting to Know Your Switch	20
1.1 Introduction	
1.1.1 ZON Utility	
1.1.2 Web Configurator Surveillance Mode	
1.1.3 PoE	
1.2 Example Applications	
1.2.1 PoE Example Application	
1.2.2 Backbone Example Application	
1.2.3 Bridging / Fiber Uplink Example Application	
1.2.4 High Performance Switching Example	
1.2.5 IEEE 802.1Q VLAN Application Examples	
1.3 Ways to Manage the Switch	
1.4 Good Habits for Managing the Switch	
Chapter 2 Hardware Installation and Connection	26
2.1 Installation Scenarios	
2.1.1 Safety Precautions	
2.2 Desktop Installation Procedure	
2.3 Wall Mounting	
2.3.1 Installation Requirements	
2.4 Rack Mounting	
2.4.1 Installation Requirements	
2.4.2 Precautions	
2.4.3 Attaching the Mounting Brackets to the Switch	
2.4.4 Mounting the Switch on a Rack	
Chapter 3 Hardware Panels	

3.1 Front Panel	
3.1.1 Gigabit Ethernet Ports	
3.1.2 PoE	
3.1.3 SFP Slots	
3.2 Reset the Switch	
3.2.1 Restore Button	
3.2.2 Restore Custom Default	
3.2.3 Reboot the Switch	
3.3 Rear Panel	
3.3.1 Grounding	
3.3.2 Power Connection	
3.3.3 4-Pin Console Port	
3.4 LEDs	

Part II: Te chnic al Reference	
--------------------------------	--

### Chapter 4

Web Configurator43
4.1 Overview
4.2 System Login
4.3 Zyxel One Network (ZON) Utility
4.3.1 Requirements
4.3.2 Run the ZON Utility
4.4 Wizard
4.4.1 Basic
4.4.2 Protection
4.4.3 VLAN
4.4.4 QoS
4.5 Web Configurator Layout
4.5.1 Change Your Password
4.6 Save Your Configuration
4.7 Switch Lockout
4.8 Reset the Switch
4.8.1 Restore Button
4.8.2 Restore Custom Default
4.8.3 Reboot the Switch
4.9 Log Out of the Web Configurator
4.10 Help
Chapter 5 Initial Setup Example

5.1 Overview	
5.1.1 Create a VLAN	
5.1.2 Set Port VID	
5.1.3 Configure Switch Management IP Address	
Chapter 6	
Tuto ria ls	
6.1 Overview	
6.2 How to Use DHCPv4 Snooping on the Switch	
6.3 How to Use DHCPv4 Relay on the Switch	
6.3.1 DHCP Relay Tutorial Introduction	
6.3.2 Create a VLAN	
6.3.3 Configure DHCPv4 Relay	
6.3.4 Troubleshooting	
Chapter 7	
Sta tus	
7.1 Overview	
7.1.1 What You Can Do	
7.2 Status	
7.2.1 Neighbor Screen	
7.2.2 Neighbor Detail	
Chapter 8	
Basic Setting	
8.1 Overview	
8.1.1 What You Can Do	
8.2 System Information	
8.3 General Setup	
8.4 Introduction to VLANs	
8.5 Switch Setup	
8.6 IP Setup	
8.6.1 IP Interfaces	
8.6.2 IP Status	
8.6.3 IP Status Details	
8.6.4 IP Configuration	
8.6.5 Network Proxy Configuration	
8.7 Port Setup	
8.8 PoE Status	
8.8.1 PoE Time Range Setup	
8.8.2 PoE Setup	
8.9 Interface Setup	
8.10 IPv6	

113
115

C hapter	9
<b>VIAN</b>	

41	N	
	9.1 Overview	
	9.1.1 What You Can Do	121
	9.1.2 What You Need to Know	121
	9.2 VLAN Status	123
	9.2.1 VLAN Details	
	9.3 VLAN Configuration	125
	9.4 Configure a Static VLAN	126
	9.5 Configure VLAN Port Settings	
	9.6 Voice VLAN	128
	9.7 MAC Based VLAN	
	9.8 Vendor ID Based VLAN	
	9.9 Port-Based VLAN Setup	133
	9.9.1 Configure a Port-Based VLAN	133

### Chapter 10

Static MAC Forwarding	
10.1 Overview	
10.1.1 What You Can Do	
10.2 Configure Static MAC Forwarding	
Chapter 11 Static Multicast Forwarding	138
11.1 Overview	
11.1.1 What You Can Do	
11.1.2 What You Need To Know	

Chapter 12	
Filte ring	
12.1 Filtering Overview	
12.1.1 What You Can Do	
12.2 Configure a Filtering Rule	
Chapter 13	
Spanning Tree Protocol	
13.1 Spanning Tree Protocol Overview	
13.1.1 What You Can Do	
13.1.2 What You Need to Know	
13.2 Rapid Spanning Tree Protocol Status	
13.3 Configure Rapid Spanning Tree Protocol	
Chapter 14	
Bandwidth Control	
14.1 Bandwidth Control Overview	
14.1.1 What You Can Do	
14.2 Bandwidth Control Setup	
Chapter 15	
Broadcast Storm Control	
15.1 Broadcast Storm Control Overview	
15.1.1 What You Can Do	
15.2 Broadcast Storm Control Setup	152
Chapter 16	
Mirro ring	
16.1 Mirroring Overview	
16.1.1 What You Can Do	
16.2 Port Mirroring Setup	
Chapter 17	
Link Aggregation	
17.1 Link Aggregation Overview	
17.1.1 What You Can Do	
17.1.2 What You Need to Know	
17.2 Link Aggregation Status	
17.3 Link Aggregation Setting	
17.3.1 Link Aggregation Control Protocol	
17.4 Technical Reference	
17.4.1 Static Trunking Example	

C hapter 18 Port Security	
18.1 About Port Security	
18.2 Port Security Setup	
Chapter 19	
Time Range	
19.1 Time Range Overview	
19.1.1 What You Can Do	
19.2 Configuring Time Range	
Chapter 20	
Queuing Method	
20.1 Queuing Method Overview	
20.1.1 What You Can Do	
20.1.2 What You Need to Know	
20.2 Configuring Queuing	
C ha p te r 21 Multic a st	170
21.1 Multicast Overview	
21.1.1 What You Can Do	
21.1.2 What You Need to Know	
21.2 Multicast Setup	
21.3 IPv4 Multicast Status	
21.3.1 IGMP Snooping 21.3.2 IGMP Snooping VLAN	
Chapter 22	
AAA	
22.1 AAA Overview	
22.1.1 What You Can Do	
22.1.2 What You Need to Know	
22.2 AAA Screens	
22.3 RADIUS Server Setup	
22.4 AAA Setup	
22.5 Technical Reference	
22.5.1 Vendor Specific Attribute	
22.5.2 Supported RADIUS Attributes	
22.5.3 Attributes Used for Authentication	
Chapter 23	
DHCP Snooping	

23.1 Overview	
23.1.1 What You Can Do	
23.2 DHCP Snooping	
23.3 DHCP Snooping Configure	
23.3.1 DHCP Snooping Port Configure	
23.3.2 DHCP Snooping VLAN Configure	191
23.3.3 DHCP Snooping VLAN Port Configure	
23.4 Technical Reference	
23.4.1 DHCP Snooping Overview	
Chapter 24	
Loop Guard	
24.1 Loop Guard Overview	
24.1.1 What You Can Do	
24.1.2 What You Need to Know	
24.2 Loop Guard Setup	
Chapter 25	
Error Disa ble	
25.1 Error Disable Overview	100
25.1.1 CPU Protection Overview	
25.1.2 Error-Disable Recovery Overview	
25.1.3 What You Can Do	
25.2 Error Disable Settings	
25.3 Error-Disable Status	
25.4 CPU Protection Configuration	
25.5 Error-Disable Detect Configuration	
25.6 Error-Disable Recovery Configuration	
Chapter 26 Green Ethemet	
	00/
26.1 Green Ethernet Overview 26.2 Configuring Green Ethernet	
26.2 Conliguing Green Einemer	
Chapter 27	
Link Layer Discovery Protocol (LLDP)	
27.1 LLDP Overview	
27.2 LLDP-MED Overview	
27.3 LLDP Settings	
27.4 LLDP Local Status	
27.4.1 LLDP Local Port Status Detail	
27.5 LLDP Remote Status	
27.5.1 LLDP Remote Port Status Detail	

27.6 LLDP Configuration	
27.6.1 LLDP Configuration Basic TLV Setting	
27.6.2 LLDP Configuration Org-specific TLV Setting	
27.7 LLDP-MED Configuration	
27.8 LLDP-MED Network Policy	
27.9 LLDP-MED Location	
Chapter 28	
Auto PD Recovery	230
28.1 Overview	
28.1.1 What You Can Do	
28.2 Auto PD Recovery	
28.2.1 Activate the Automatic PD Recovery	
Chapter 29	
ONVIF	235
29.1 Overview	
29.1.1 What You Can Do	
29.2 ONVIF Screen	
Chapter 30	
Diffe re ntia te d Se rvic e s	237
30.1 DiffServ Overview	
30.1.1 What You Can Do	
30.1.2 What You Need to Know	
30.2 Activating DiffServ	
30.3 DSCP Settings	
30.3.1 Configuring DSCP Settings	
Chapter 31	
DHC P	241
31.1 DHCP Overview	
31.1.1 What You Can Do	
31.1.2 What You Need to Know	
31.2 DHCP Configuration	
31.3 DHCPv4 Status	
31.4 DHCPv4 Relay	
31.4.1 DHCPv4 Relay Agent Information	
31.4.2 DHCPv4 Option 82 Profile	
31.4.3 Configuring DHCPv4 Global Relay	
31.4.4 Configure DHCPv4 Global Relay Port	
31.4.5 Global DHCP Relay Configuration Example	
31.4.6 DHCPv4 VLAN Setting	

31.4.7 Configure DHCPv4 VLAN Port	
31.4.8 Example: DHCP Relay for Two VLANs	
31.5 DHCPv6 Relay	
C hapter 32 ARP Se tup	253
- 32.1 ARP Overview	052
32.1.1 What You Can Do	
32.1.2 What You Need to Know	
32.2 ARP Setup	
32.2 ARF Selop	
Chapter 33 Mainte nance	957
33.1 Overview	257
33.1.1 What You Can Do	257
33.2 Maintenance Settings	257
33.2.1 Erase Running-Configuration	258
33.2.2 Save Configuration	259
33.2.3 Reboot System	259
33.3 Firmware Upgrade	
33.4 Restore Configuration	
33.5 Backup Configuration	
33.6 Tech-Support	
33.7 Certificates	
33.7.1 HTTPS Certificates	
33.8 Technical Reference	
33.8.1 FTP Command Line	
33.8.2 Filename Conventions	
33.8.3 FTP Command Line Procedure	
33.8.4 GUI-based FTP Clients	
33.8.5 FTP Restrictions	
Chapter 34	
Access Control	
34.1 Access Control Overview	
34.1.1 What You Can Do	
34.2 Access Control Main Settings	
34.3 Configure SNMP	
34.3.1 Configure SNMP Trap Group	
34.3.2 Enable or Disable Sending of SNMP Traps on a Port	
34.3.3 Configure SNMP User	
34.4 Set Up Login Accounts	

34.5 Service Access Control	
34.6 Remote Management	
34.7 Technical Reference	
34.7.1 About SNMP	
34.7.2 SSH Overview	
34.7.3 Introduction to HTTPS	
34.7.4 Google Chrome Warning Messages	
C ha p te r 35 Dia g no stic	292
35.1 Overview	
35.1 Overview	
55.2 Diagnostic	
Chapter 36	205
System Log	
36.1 Overview	
36.2 System Log	
Chapter 37	
Syslog Setup	
37.1 Syslog Overview	
37.1.1 What You Can Do	
37.2 Syslog Setup	
Chapter 38	
Cluster Management.	
38.1 Cluster Management Overview	
38.1.1 What You Can Do	
38.2 Cluster Management Status	
38.3 Clustering Management Configuration	
38.4 Technical Reference	
38.4.1 Cluster Member Switch Management	
Chapter 39	
MAC Table	
39.1 MAC Table Overview	
39.1.1 What You Can Do	
39.1.2 What You Need to Know	
39.2 Viewing the MAC Table	
Chapter 40	
ARP Ta b le	
40.1 Overview	
	000

40.1.1 What You Can Do	
40.1.2 What You Need to Know	
40.2 Viewing the ARP Table	
Chapter 41	
Pa th MTU Ta b le	
41.1 Path MTU Overview	
41.2 Viewing the Path MTU Table	
Chapter 42	
Configure Clone	
42.1 Overview	311
42.2 Configure Clone	
Ŭ	
Chapter 43 IPv6 Neighbor Table	
43.1 IPv6 Neighbor Table Overview 43.2 Viewing the IPv6 Neighbor Table	
43.2 VIEWING THE IFV6 NEIGNDOF TODIE	
Chapter 44	
Port Sta tus	
44.1 Overview	
44.2 Port Status	
44.2.1 Port Details	
44.2.2 DDMI	
44.2.3 DDMI Details	
44.2.4 Port Utilization	
Chapter 45	
Surveillance Mode	
45.1 Overview	
45.1.1 What You Can Do	
45.2 Summary	
45.2.1 Neighbor Detail Screen	
Chapter 46	
Quick Setup	
46.1 Quick Setup Screen	
C hapter 47 System	
47.1 What You Can Do	
47.2 System Information	

47.3 General Setup	
47.4 Cloud Management	
Chapter 48 Port	
	222
48.1 What You Can Do	
48.2 Auto PD Recovery 48.3 PoE Status	
48.4 PoE Setup 48.5 Port Setup	
46.5 FOIT SETUP	
Chapter 49	
Switching	
49.1 Broadcast Storm Control	
49.2 Link Aggregation	
49.2.1 What You Can Do	
49.3 Link Aggregation Status	
49.4 Link Aggregation Setting	
49.5 Link Aggregation Control Protocol	
49.6 Loop Guard	
49.6.1 What You Need to Know	
49.7 VLAN	
49.7.1 What You Can Do	
49.7.2 What You Need to Know	
49.8 VLAN Status	
49.8.1 VLAN Detail	
49.9 Static VLAN	
49.10 VLAN Port Setting	
Chapter 50	
Ne two rking	
50.1 IP Interfaces	
50.1.1 What You Can Do	
50.2 IP Setup	
50.3 ONVIF	
Chapter 51	
Se c unity	
51.1 Access Control	364
51.1.1 What You Can Do	
51.2 Set Up Login Accounts	
51.3 Remote Management	
51.4 Configure SNMP	

51.5 Configure SNMP Trap Group	
51.6 Enable or Disable Sending of SNMP Traps on a Port	371
51.7 Configure SNMP User	372
51.8 Service Access Control Screen	
Chapter 52	
Maintenance	376
52.1 What You Can Do	
52.2 Backup Configuration	376
52.3 Firmware Upgrade	377
52.4 Reboot System	378
52.5 Restore Configuration	379
52.6 Save Configuration	
52.7 Tech-Support	

Part III: Trou	bleshooting an	d Appendices	
----------------	----------------	--------------	--

C hapter 53 Trouble shooting	
53.1 Power, Hardware Connections, and LEDs	
53.2 Switch Access and Login	
53.3 Switch Configuration	
Appendix A Customer Support	
Appendix B Common Services	392
Appendix C IPv6	395
Appendix D Legal Information	403
Inde x	407

# PART I User's Guide

## C HAPTER 1 Getting to Know Your Switch

### 1.1 Introduction

The GS1350 Series consists of the following models:

- GS1350-6HP
- GS1350-12HP
- G\$1350-18HP
- G\$1350-26HP

All models are referred to as the "Switch" in this guide. The Switch can be configured and managed by the Web Configurator. It can also be managed via Telnet or third-party SNMP management.

The following table describes the hardware features of the Switch by model.

FEA TURES	GS1350-6HP	GS1350-12HP	GS1350-18HP	GS1350-26HP
Number of 10/100/1000 Mbps Ethernet ports	5	10	16	24
Number of 10/100/1000 Mbps PoE ports	5	8	16	24
Number of GbE combo ports (dual personality interfaces)	-	-	2	2
Number of 1 Gbps SFP interfaces	1	2	-	-
4-pin console port (for troubleshooting only)	Yes	Yes	Yes	Yes
Auto-Fan	Fanless	Yes	Yes	Yes
Wall-mount	Yes	Yes	No	No
Rack-mount	No	Yes	Yes	Yes

Table 1 G\$1350 Series Comparison Table

### 1.1.1 ZON Utility

With its built-in Web Configurator, including the Neighbor Management feature (Section 7.2.1 on page 84), viewing, managing and configuring the Switch and its neighboring devices is easy.

In addition, Zyxel offers a proprietary software program called Zyxel One Network (ZON) Utility, it is a utility tool that assists you to set up and maintain network devices in a more simple and efficient way. You can download the ZON Utility at www.zyxel.com and install it on a PC (Windows operation system). For more information on ZON Utility see Section 4.3 on page 47.



### 1.1.2 Web Configurator Surveillance Mode

Aside from the Web Configurator in Standard mode, you can switch to Surveillance mode that is specifically designed for configuring and managing PoE devices like IP cameras (Chapter 45 on page 322).

### 1.1.3 PoE

The Switch is a Power Sourcing Equipment (PSE) because it provides a source of power via its Ethernet ports. Each device that receives power through an Ethernet port is a Powered Device (PD).

The Switch can adjust the power supplied to each PD according to the PoE standard the PD supports. PoE standards are:

- IEEE 802.3af Power over Ethernet (PoE)
- IEEE 802.3at Power over Ethernet (PoE) Plus
- IEEE 802.3bt 4PPoE Type 3

The following table describes the PoE features of the Switch by model.

Table 2Models and PoE Features

PO E FEA TURES	GS1350-6HP	GS1350-12HP	GS1350-18HP	GS1350-26HP
IEEE 802.3af PoE	Yes	Yes	Yes	Yes
IEEE 802.3at PoE Plus	Yes	Yes	Yes	Yes
IEEE 802.3bt 4PPoE Type 3	Yes (port1 and port2 only)	No	No	No
Power Management Mode	Consumption Classification	Consumption Classification	Consumption Classification	Consumption Classification
PoE Power Budget	60 W	130 W	250 W	375 W


### 1.2 Example Applications

This section shows a few examples of using the Switch in various network environments. Note that the Switch in the figure is just an example Switch and not your actual Switch.

### 1.2.1 PoEExample Application

The following example figure shows a Switch supplying PoE (Power over Ethernet) to Powered Devices (PDs) such as an IP camera, a wireless router, an IP telephone and a general outdoor router that are not within reach of a power outlet.





### 1.2.2 Backbone Example Application

The Switch is an ideal solution for small networks where rapid growth can be expected in the near future. The Switch can be used standalone for a group of heavy traffic users. You can connect computers and servers directly to the Switch's port or connect other switches to the Switch.

In this example, all computers can share high-speed applications on the server. To expand the network, simply add more networking devices such as switches, routers, computers, print servers, and so on.




Figure 2 Backbone Application

### 1.2.3 Bridging / Fiber Uplink Example Application

In this example, the Switch connects different company departments (**RD** and **Sales**) to the corporate backbone. It can alleviate bandwidth contention and eliminate server and network bottlenecks. All users that need high bandwidth can connect to high-speed department servers via the Switch. You can provide a super-fast uplink connection by using a Gigabit Ethernet/SFP port on the Switch.




Figure 3 Bridging / Fiber Uplink Example Application

### 1.2.4 High Performance Switching Example

The Switch is ideal for connecting two networks that need high bandwidth. In the following example, use trunking to connect these two networks.

Switching to higher-speed LANs such as ATM (Asynchronous Transmission Mode) is not feasible for most people due to the expense of replacing all existing Ethernet cables and adapter cards, restructuring your network and complex maintenance. The Switch can provide the same bandwidth as ATM at much lower cost while still being able to use existing adapters and switches. Moreover, the current LAN structure can be retained as all ports can freely communicate with each other.




Figure 4 High Performance Switched Workgroup Application

### 1.2.5 IEEE 802.1Q VIAN Application Examples

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Stations on a logical network belong to one group. A station can belong to more than one group. With VLAN, a station cannot directly talk to or hear from stations that are not in the same groups unless such traffic first goes through a router.

For more information on VLANs, refer to Chapter 9 on page 121.

### 1.2.5.1 Tag-based VIAN Example

Ports in the same VLAN group share the same frame broadcast domain thus increase network performance through reduced broadcast traffic. VLAN groups can be modified at any time by adding, moving or changing ports without any re-cabling.

Shared resources such as a server can be used by all ports in the same VLAN as the server. In the following figure only ports that need access to the server need to be part of VLAN 1. Ports can belong to other VLAN groups too.




Figure 5 Shared Server Using VLAN Example

### 1.3 Ways to Manage the Switch

Use any of the following methods to manage the Switch.

- Web Configurator in Standard or Surveillance mode. This is recommended for everyday management of the Switch using a (supported) web browser. See Chapter 4 on page 43.
- Command Line Interface. Line commands offer an alternative to the Web Configurator and in some cases are necessary to configure advanced features. See the CLI Reference Guide.
- FTP. Use FTP for firmware upgrades and configuration backup/restore. See Section 33.8.1 on page 266.
- SNMP. The Switch can be monitored by an SNMP manager. See Section 34.7.1 on page 279.
- Cluster Management. Cluster Management allows you to manage multiple switches through one switch, called the cluster manager. See Chapter 38 on page 299.
- ZON Utility. ZON Utility is a program designed to help you deploy and perform initial setup on a network more efficiently. See Section 4.3 on page 47.
- NCC (Zyxel Nebula Control Center). With the NCC, you can remotely manage and monitor the Switch through a cloud-based network management system. See Section 8.11 on page 119 or the NCC User's Guide for detailed information about how to access the NCC and manage your Switch via the NCC. See the NCC User's Guide for how to configure Nebula managed devices.

### 1.4 Good Habits for Managing the Switch

Do the following things regularly to make the Switch more secure and to manage the Switch more effectively.

- Change the password. Use a password that is not easy to guess and that consists of different types of characters, such as numbers and letters.
- Write down the password and put it in a safe place.
- Back up the configuration (and make sure you know how to restore it). Restoring an earlier working configuration may be useful if the device becomes unstable or even crashes. If you forget your password, you will have to reset the Switch to its factory default settings. If you backed up an earlier configuration file, you would not have to totally re-configure the Switch. You could simply restore your last configuration.

# CHAPTER 2 Hardware Installation and Connection

### 2.1 Installation Scenarios

This chapter shows you how to install and connect the Switch.

The Switch can be:

- Placed on a desktop.
- Wall-mounted on a wall.
- Rack-mounted on a standard EIA rack.

See Table 1 on page 20 for the comparison table of the hardware installation methods for each model.

### 2.1.1 Before Using the Switch

Please observe the following before using the Switch:

- It is recommended to ask an authorized technician to attach the Switch on a desk or to the rack or wall. Use the proper screws to prevent damage to the Switch. See the **Installation Requirements** sections in this chapter to know the types of screws and screw drivers for each mounting method.
- Make sure there is at least 2 cm of clearance on the top and bottom of the Switch, and at least 5 cm of clearance on all four sides of the Switch. This allows air circulation for cooling.
- Do NOT block the ventilation holes nor store cables or power cords on the Switch. Allow clearance for the ventilation holes to prevent your Switch from overheating. This is especially crucial when your Switch does not have fans. Overheating could affect the performance of your Switch, or even damage it.
- The surface of the Switch could be hot when it is functioning. Do NOT put your hands on it. You may get burned. This could happen especially when you are using a fanless Switch.
- The Switches with fans are not suitable for use in locations where children are likely to be present.


To start using the Switch, simply connect the power cables and turn it on.

### 2.2 Desktop Installation Procedure

- 1 Make sure the Switch is clean and dry.
- 2 Remove the adhesive backing from the rubber feet.

3 Attach the rubber feet to each corner on the bottom of the Switch. These rubber feet help protect the Switch from shock or vibration and ensure space between devices when stacking.

#### Figure 6 Attaching Rubber Feet



4 Set the Switch on a smooth, level surface strong enough to support the weight of the Switch and the connected cables. Make sure there is a power outlet nearby.

#### Cautions:


- Avoid stacking fanless Switches to prevent overheating.
- Ensure enough clearance around the Switch to allow air circulation for cooling.
- Do NOT remove the rubber feet as it provides space for air circulation.

### 2.3 Wall Mounting

The Switch can be mounted on a wall (see Table 1 on page 20). You may need screw anchors if mounting on a concrete or brick wall.

### 2.3.1 Installation Requirements

- Distance above the floor: At least 1.8 m (5.9 feet)
- Distance between holes: 78 mm (3.071 inches)
- Two M4 screws and a #2 Philips screwdriver
- Two screw anchors (optional)



- 1 Select a position free of obstructions on a wall strong enough to hold the weight of the Switch.
- 2 Mark two holes on the wall at the appropriate distance apart for the screws.


### WARNING! Be careful to avoid damaging pipes or cables located inside the wall when drilling holes for the screws.

3 If using screw anchors, drill two holes for the screw anchors into the wall. Push the anchors into the full depth of the holes, then insert the screws into the anchors. Do NOT insert the screws all the way in – leave a small gap of about 0.5 cm.

If not using screw anchors, use a screwdriver to insert the screws into the wall. Do NOT insert the screws all the way in – leave a gap of about 0.5 cm.

- 4 Make sure the screws are fastened well enough to hold the weight of the Switch with the connection cables.
- 5 Align the holes on the back of the Switch with the screws on the wall. Hang the Switch on the screws.

Note: Make sure there is enough clearance between the wall and the Switch to allow ventilation.



WARNING! The Switch should be wall-mounted horizontally, and make sure the front panel is facing down. The Switch's side panels with ventilation slots should not be facing up or down as this position is less safe.

### 2.4 Rack Mounting

The Switch can be mounted on an EIA standard size, 19-inch rack or in a wiring closet with other equipment (see Table 1 on page 20). Follow the steps below to mount your Switch on a standard EIA rack using a rack-mounting kit.

Note: Make sure there is enough clearance between each equipment on the rack for air circulation.

### 2.4.1 Installation Requirements

• Two mounting brackets.

- Eight M3 flat head screws and a #2 Philips screwdriver.
- Four M5 flat head screws and a #2 Philips screwdriver.

### 2.4.2 Precautions

- Make sure the rack will safely support the combined weight of all the equipment it contains.
- Make sure the position of the Switch does not make the rack unstable or top-heavy. Take all necessary precautions to anchor the rack securely before installing the unit.

### 2.4.3 Attaching the Mounting Brackets to the Switch

Position a mounting bracket on one side of the Switch, lining up the four screw holes on the bracket with 1 the screw holes on the side of the Switch.





Figure 7 Attaching the Mounting Brackets

- 2 Using a #2 Philips screwdriver, install the M3 flat head screws through the mounting bracket holes into the Switch.
- Repeat steps 1 and 2 to install the second mounting bracket on the other side of the Switch. 3
- You may now mount the Switch on a rack. Proceed to the next section. 4

### 2.4.4 Mounting the Switch on a Rack

1 Position a mounting bracket (that is already attached to the Switch) on one side of the rack, lining up the two screw holes on the bracket with the screw holes on the side of the rack.



2 Using a #2 Philips screwdriver, install the M5 flat head screws through the mounting bracket holes into the rack.

Note: Make sure you tighten all the four screws to prevent the Switch from getting slanted.

**3** Repeat steps 1 and 2 to attach the second mounting bracket on the other side of the rack.

## CHAPTER 3 Hardware Panels

This chapter describes the front panel and rear panel of the Switch and shows you how to make the hardware connections.

### 3.1 Front Panel

The following figures show the front panels of the Switch.

Figure 10 Front Panel: GS1350-6HP



Figure 11 Front Panel: G\$1350-12HP



Figure 12 Front Panel: GS1350-18HP



Figure 13 Front Panel: GS1350-26HP



The following table describes the ports.

Table 3	Panel	Connections
---------	-------	-------------

CONNECTOR	DESC RIPIIO N
5/10/16/24 1000Base-T RJ-45 Ethernet Ports	These are 10/100/1000Base-T auto-negotiating and auto-crossover Ethernet ports. Connect these ports to a computer, a hub, a router, or an Ethernet switch.
5/8/16/24 1000Base- T RJ-45 PoE Ports	These are 10/100/1000Base-T auto-negotiating and auto-crossover Ethernet ports. Connect these ports to a computer, a hub, a router, or an Ethernet switch.
1/2 SFP Slots (only available for GS1350-6HP/12HP)	Use SFP transceivers in these ports for high-bandwidth backbone connections.



CONNECTOR	DESC RIPIIO N
2 GbE Combo Ports (Dual Personality Interfaces)	Each interface has one 10/100/1000Base-T copper RJ-45 port and one SFP slot, with one port active at a time.
	• 10/100/1000Base-T Ports:
(only available for G\$1350-18HP/26HP)	Connect these ports to a computer, an Ethernet switch or router.
	<ul> <li>SFP Slots: Use Small Form-Factor Pluggable (SFP) transceivers in these ports for fiber connections to an Ethernet switch or router.</li> </ul>
Reset	Press the <b>RESET</b> button to reboot the Switch without turning the power off. See Section 3.3 on page 39 for more information about the LED behavior.
Restore	Press the <b>RESTO RE</b> button for 3 to 7 seconds to have the Switch automatically reboot and restore the last-saved custom default file. See Section 3.3 on page 39 for more information about the LED behavior.
	Press the <b>RESTO RE</b> button for more than 7 seconds to have the Switch automatically reboot and restore the factory default file. See Section 3.3 on page 39 for more information about the LED behavior.
Console Port	Only connect this port to your computer (using a USB Type A console cable) if you want to configure the Switch using a computer with terminal emulation software via the console port.

 Table 3
 Panel Connections (continued)

### 3.1.1 Gigabit Ethernet Ports

The Switch has 1000Base-T auto-negotiating, auto-crossover Ethernet ports. In 10/100/1000 Mbps Gigabit, the speed can be 10 Mbps, 100 Mbps or 1000 Mbps and the duplex mode can be half duplex or full duplex.

An auto-negotiating port can detect and adjust to the optimum Ethernet speed (10/100/1000 Mbps) and duplex mode (full duplex or half duplex) of the connected device.

An auto-crossover (auto-MDI/MDI-X) port automatically works with a straight-through or crossover Ethernet cable.

Four 1000Base-T Ethernet ports are paired with an SFP slot to create a dual personality interface. The Switch uses up to one connection for each SFP and 1000Base-T Ethernet pair. The SFP slots have priority over the Gigabit ports. This means that if an SFP slot and the corresponding GbE port are connected at the same time, the GbE port will be disabled.

Note: The dual personality ports change to fiber mode directly when inserting the fiber module.

When auto-negotiation is turned on, an Ethernet port negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer Ethernet port does not support auto-negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, an Ethernet port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer Ethernet port are the same in order to connect.

### 3.1.1.1 De fault Ethe met Negotiation Settings

The factory default negotiation settings for the Gigabit ports on the Switch are:

• Speed: Auto

- Duplex: Auto
- Flow control: Off
- Link Aggregation: Disabled

### 3.1.1.2 Auto-crossover

All ports are auto-crossover, that is auto-MDIX ports (Media Dependent Interface Crossover), so you may use either a straight-through Ethernet cable or crossover Ethernet cable for all Gigabit port connections. Auto-crossover ports automatically sense whether they need to function as crossover or straight ports, so crossover cables can connect both computers and switches or hubs.

### 3.1.2 PoE

The Switch supports the IEEE 802.3af Power over Ethernet (PoE), IEEE 802.3at Power over Ethernet (PoE) plus and IEEE 802.3bt standards. The Switch is a Power Sourcing Equipment (PSE) because it provides a source of power via its Ethernet ports. Each device that receives power through an Ethernet port is a Powered Device (PD).

### 3.1.3 SFP Slots

These are slots for SFP (Small Form-Factor Pluggable) transceivers. A transceiver is a single unit that houses a transmitter and a receiver. The Switch does not come with transceivers. You must use transceivers that comply with the Small Form-factor Pluggable (SFP) Transceiver MultiSource Agreement (MSA). See the SFF committee's INF-8074i specification Rev 1.0 for details.

You can change transceivers while the Switch is operating. You can use different transceivers to connect to Ethernet switches with different types of fiber-optic or even copper cable connectors.

### WARNING! To avoid possible eye injury, do NOT look into an operating fiber optic module's connectors.

HANDLING! All transceivers are static sensitive. To prevent damage from electrostatic discharge (ESD), it is recommended you attach an ESD preventive wrist strap to your wrist and to a bare metal surface when you install or remove a transceiver.

STO RAGE All modules are dust sensitive. When not in use, always keep the dust plug on. Avoid getting dust and other contaminant into the optical bores, as the optics do not work correctly when obstructed with dust.

- Type: SFP connection interface
- Connection speed: 100M/1G bps


### 3.1.3.1 Transceiver Installation


Use the following steps to install an SFP transceiver.

- 1 Attach an ESD preventive wrist strap to your wrist and to a bare metal surface.
- 2 Align the transceiver in front of the slot opening.

- 3 Make sure the latch is in the lock position (latch styles vary), then insert the transceiver into the slot with the exposed section of PCB board facing down.
- 4 Press the transceiver firmly until it clicks into place.
- 5 The Switch automatically detects the installed transceiver. Check the LEDs to verify that it is functioning properly.
- 6 Remove the dust plugs from the transceiver and cables (dust plug styles vary).
- 7 Identify the signal transmission direction of the fiber cables and the transceiver. Insert the fiber cable into the transceiver.

Figure 14 Latch in the Lock Position









Figure 16 Connecting the Fiber Cables



### 3.1.3.2 Transceiver Removal

Use the following steps to remove an SFP transceiver.

- 1 Attach an ESD preventive wrist strap to your wrist and to a bare metal surface on the chassis.
- 2 Remove the fiber optic cables from the transceiver.
- **3** Pull out the latch and down to unlock the transceiver (latch styles vary).

Note: Make sure the transceiver's latch is pushed all the way down, so the transceiver can be pulled out successfully.

4 Pull the latch, or use your thumb and index finger to grasp the tabs on both sides of the transceiver, and carefully slide it out of the slot.

- Note: Do NOT pull the transceiver out by force. You could damage it. If the transceiver will not slide out, grasp the tabs on both sides of the transceiver with a slight up or down motion and carefully slide it out of the slot. If unsuccessful, contact Zyxel Support to prevent damage to your Switch and transceiver.
- 5 Insert the dust plug into the ports on the transceiver and the cables.

#### Figure 17 Removing the Fiber Cables




Figure 18 Opening the Transceiver's Latch Example



Figure 19 Transceiver Removal Example




### 3.1.4 Dual Personality Interfaces

A combo port is for uplink connections. It consists of a Gigabit Ethernet port for Ethernet connection, and a SFP transceiver slot for fiber connection. The fiber connection takes priority if the corresponding Gigabit port is also connected.


- 100 Mbps/1 Gbps Connect these ports to high-bandwidth backbone network Ethernet switches.
- Transceiver Slots Use SFP transceivers in these slots for connections to backbone Ethernet switches.

Figure 20 Combo Port Example: Gigabit Port and SFP Transceiver Slot



### 3.2 RearPanel

The following figures show the rear panels of the Switch.



#### 3.2.1 Grounding

Grounding is a safety measure to direct excess electric charge to the ground. It prevents damage to the Switch, and protects you from electrocution. Use the grounding screw on the rear panel and the ground wire of the AC power supply to ground the Switch.

The grounding terminal and AC power ground where you install the Switch must follow your country's regulations. Qualified service personnel must ensure the building's protective earthing terminals are valid terminals.

Installation of Ethernet cables must be separate from AC power lines. To avoid electric surge and electromagnetic interference, use a different electrical conduit or raceway (tube/trough or enclosed conduit for protecting electric wiring) that is 15 cm apart, or as specified by your country's electrical regulations.

Any device that is located outdoors and connected to this product must be properly grounded and surge protected. To the extent permissible by your country's applicable law, failure to follow these guidelines could result in damage to your Switch which may not be covered by its warranty.

Note: The specification for surge or ESD protection assumes that the Switch is properly grounded.

- 1 Remove the M4 ground screw from the Switch's rear panel.
- 2 Secure a green or yellow ground cable (16 AWG or smaller) to the Switch's rear panel using the M4 ground screw.






3 Attach the other end of the ground cable to a grounding bar located on the rack where you install the Switch or to an on-site grounding terminal.

Figure 26 Attach Ground Cable to Grounding Bar or On-site Grounding Terminal



4 The grounding terminal of the server rack or on-site grounding terminal must also be grounded and connected to the building's main grounding electrode. Make sure the grounding terminal is connected to the buildings grounding electrode and has an earth resistance of less than 10 ohms, or according to your country's electrical regulations.

Figure 27 Connecting to the Building's Main Grounding Electrode



If you are uncertain that suitable grounding is available, contact the appropriate electrical inspection authority or an electrician.

# This device must be grounded. Do this before you make other connections.

#### 3.2.2 PowerConnection

Note: Make sure you are using the correct power source as shown on the panel and that no objects obstruct the airflow of the fans (located on the side of the unit).

GS1350-6HP: Connect the supplied power adapter to the power receptacle on the rear panel. Then use the included power cord to connect the power adapter to an appropriate power source. Set the power switch to the ON position.

G\$1350-12HP/18HP/26HP: To connect power to the Switch, insert the female end of the supplied power cord to the AC power receptacle on the rear panel. Connect the other end of the power cord to an appropriate power outlet.

#### 3.2.3 4-Pin Console Port

This console port is for troubleshooting only. With instructions from customer support, connect the 4-pin connector of the USB Type A console cable to the console port of the Switch. Then connect the other end to a USB port on your computer. You can use a computer with terminal emulation software configured to the following parameters:

- VT100 terminal emulation
- 115200 bps
- No parity, 8 data bits, 1 stop bit
- No flow control

#### **3.3 IEDs**

After you connect the power to the Switch, view the LEDs to ensure proper functioning of the Switch and as an aid in troubleshooting.

IED	COLOR	STATUS	DESC RIPIIO N
PWR	Green	On	The Switch is receiving power from the power module in the power slot.
		Blinking	The Switch is returning to the last-saved custom default configuration settings.
	Amber	On	The Switch is returning to its factory default configuration settings.
		Off	The Switch is not receiving power from the power module in the power slot.
SYS	Green		The Switch is on and functioning properly.
		Blinking	The Switch is rebooting and performing self-diagnostic tests.
	Red	On	The Switch is functioning abnormally.
		Off	The power is off or the Switch is not ready/malfunctioning.

Table 4 LED Descriptions

Table 4 LED Descriptions (continued)

LED	COLOR	STATUS	DESC RIPTIO N
CLOUD	Green	On	The Switch has successfully connected to the NCC (Nebula Control Center).
		Blinking	The Switch cannot connect to the NCC because it is not registered.
	Amber	On	The Switch is registered at NCC but cannot connect to the NCC. Please check the Internet connection of the Switch.
		Blinking	The Switch is not registered at NCC and cannot connect to the NCC. Please check the Internet connection of the Switch and register the Switch at NCC.
		Off	The Switch is operating in standalone mode. Nebula Control Center Discovery is disabled in <b>Basic &gt; Cloud Management &gt; Nebula Control Center</b> <b>Discovery</b> in the Switch's Web Configurator.
LOCATOR	Blue	On	The Switch is uploading firmware. While the Switch is doing this, do NOT turn off the power.
		Blinking	Shows the actual location of the Switch between several devices in a rack. The default timer is 30 minutes when you are configuring the Switch.
		Off	The locator is not functioning or malfunctioning.
PoE Usage MAX	Green	On	Each bar represents 20 percent of PoE Power consumption.
Bar1 is the bar at	(Bar1-Bar3)		Bar1: PoE power usage is below 20 percent of the power supplied budget.
the bottom; bar 5 is the bar at the top.			<b>Bar2</b> : PoE power usage is below 40 percent of the power supplied budget, but over 20 percent of the power supplied budget.
·			<b>Bar3</b> : PoE power usage is below 60 percent of the power supplied budget, but over 40 percent of the power supplied budget.
	Yellow	On	PoE power usage is below 80 percent of the power supplied budget, but
	(Bar4)		over 60 percent of the power supplied budget.
	Red	On	PoE power usage is more than 80 percent of the power supplied budget.
	(Bar5)	Blinking	Less than 5 percent of the power supplied budget remains. 5 percent is the default value.
		Off	PoE power usage is 0 percent of the power supplied budget.
Ethernet Ports and	d PoE		
LNK/ACT	Green	Blinking	The Switch is transmitting or receiving to or from a 1000 Mbps Ethernet network.
1-5 (GS1350- 6HP)		On	The link to a 1000 Mbps Ethernet network is up.
1-8 (GS1350- 12HP)	Amber	Blinking	The Switch is transmitting or receiving to or from a 10 Mbps or a 100 Mbps Ethernet network.
,		The link to a 10 Mbps or a 100 Mbps Ethernet network is up.	
18HP)		Off	The link to an Ethernet network is down.
1-24 (GS1350- 26HP)			
PoE	Green	On	Power supplied to all PoE Ethernet ports meets the IEEE 802.3at/bt standard.
1-5 (G\$1350-	Amber	On	Power supplied to all PoE Ethernet ports meets the IEEE 802.3af standard.
6HP)		Off	There is no power supplied.
1-8 (G\$1350- 12HP)			
1-16 (GS1350- 18HP)			
1-24 (GS1350-			

Table 4	LED Descriptions	(continued)
---------	------------------	-------------

LED	COLOR	STATUS	DESC RIPTIO N	
Dual Personality	nterface			
Ethernet Ports Green 17-18 (G\$1350-		Blinking	The Switch is transmitting or receiving to or from a 1000 Mbps Ethernet network.	
18HP)		On	The link to a 1000 Mbps Ethernet network is up.	
25-26 (GS1350- 26HP)			The Switch is transmitting or receiving to or from a 10 Mbps or a 100 Mbps Ethernet network.	
		On	The link to a 10 Mbps or a 100 Mbps Ethernet network is up.	
		Off	The link to an Ethernet network is down.	
SFP Slots	Green	On	The uplink port is linking at 1000 Mbps.	
17-18 (GS1350-		Blinking	The Switch is transmitting or receiving data at 1000 Mbps.	
18HP)	Amber	On	The uplink port is linking at 100 Mbps.	
25-26 (GS1350-		Blinking	The Switch is transmitting or receiving data at 100 Mbps.	
26HP)		Off	There is no link or port, the uplink port is shut down.	
10/100/1000Base	-T Ethernet Ports			
9-10 (GS1350- 12HP)	Green	Blinking	The Switch is transmitting or receiving to or from a 1000 Mbps Ethernet network.	
		On	The link to a 1000 Mbps Ethernet network is up.	
	Amber	Blinking	The Switch is transmitting or receiving to or from a 10 Mbps or a 100 Mbps Ethernet network.	
		On	The link to a 10 Mbps or a 100 Mbps Ethernet network is up.	
		Off	The link to an Ethernet network is down.	
1G SFP Slots			·	
6 (GS1350-6HP)	Green	On	The uplink port is linking at 1000 Mbps.	
11-12 (GS1350-		Blinking	The Switch is transmitting or receiving data at 1000 Mbps.	
12HP)	Amber	On	The uplink port is linking at 100 Mbps.	
		Blinking	The Switch is transmitting or receiving data at 100 Mbps.	
		Off	There is no link or port, the uplink port is shut down.	

# PART II Te c hnic a l Re fe re nc e

# C HAPTER 4 Web Configurator

# 4.1 Overview

This section introduces the configuration and functions of the Web Configurator.

The Web Configurator is an HTML-based management interface that allows easy system setup and management via Internet browser. Use a browser that supports HTML5, such Microsoft Edge, Internet Explorer 11, Mozilla Firefox, or Google Chrome. The recommended screen resolution is 1024 by 768 pixels.

In order to use the Web Configurator you need to allow:

- Web browser pop-up windows from your device.
- JavaScript (enabled by default).
- Java permissions (enabled by default).

## 4.2 System Login

- 1 Start your web browser.
- 2 The Switch is a DHCP client by default. Type "http://DHCP-assigned IP" in the Location or Address field. Press [ENTER].

If the Switch is not connected to a DHCP server, type "http://" and the static IP address of the Switch (for example, the default management IP address is 192.168.1.1 through an in-band port) in the **Location** or **Address** field. Press [ENTER]. Your computer must be in the same subnet in order to access this website address.


Also, you can use the ZON Utility to check your Switch's IP address. See Section 4.3 on page 47 for more information on the ZON utility.

3 The following screen appears.

Figure 27 Web Configurator: Login

	1
ZYXEL	
	G\$1350-6HP
	Billin User Flam, Water-ard and in Octobary
	🚱 indrin
	60 8888
	Login
alle war	ge Your Network with the Freedom of Cloud.
10	······································
nebula	Will Records
necula	THE ROOMEN

- 4 Click **Login** to log into the Web Configurator to manage the Switch directly. The default username is **admin** and associated default password is **1234**.
- 5 The following screen appears.



- 6 Select the Web Configurator in **Standard Mode** that has a complete set of configuration for network installation. Or select the Web Configurator in **Surveillance Mode** that has a set of menus specifically designed for users who are mostly using the Switch for configuring and managing PoE devices like IP cameras (Chapter 45 on page 322).
- 7 The Setup Wizard screen will appear after selecting the mode. You can use the Setup Wizard screen to configure the Switch's IP, login password, SNMP community, link aggregation, and so on. See Section 4.4 on page 51 for more information on the Setup Wizard screen. When you finish configuring the settings, you can click the Apply & Save button to make the settings take effect, and save your configuration into the Switch's non-volatile memory at once. Check the screens to see if the settings are applied.
  - Note: Once you click the Apply & Save button, the settings configured in the Setup Wizard screen will overwrite the existing settings.

Otherwise, click the Exit button. You can select the Ignore this wizard next time check box and click Apply & Save if you do not want the Setup Wizard screen to appear the next time you log in. If you want to open the Setup Wizard screen later, click the Wizard icon in the upper right hand corner of the Web Configurator.



Figure 29 Web Configurator: Wizard

8 If you did not change the default administrator password and/or SNMP community values, a warning screen displays each time you log into the Web Configurator. Click **Password / SNMP** to open a screen where you can change the administrator and SNMP passwords simultaneously. Otherwise, click **Ignore** to close it.

#### Password/SNMP Setting

Figure 30 Web Configurator: Warning

Manage carrer	$\sim$
å. Warning:	
<ol> <li>As a security precasition, it is highly recommended that you should attempt to calle a presented.</li> <li>The SMM* community is used for SMM* management and is set to public key default. To excit tensarily terms by precent along a the community shing for a value other than do built setting.</li> </ol>	
Configure <u>Present (2000</u> , selling	
Ignere	

Figure 31 Web Configurator: Password

Pasamond defendencies	
Old Parawood New Parawood Setteen to contain	
electric Venezia Dell'env	
Presses Colification why Com Conservable Temps Conservable	kA. – public public public
74.10	(Sec.

Change the default administrator and/or SNMP passwords, and then click Apply to save your changes.

TADET	DECOMPTO N				
IABEL	DESC RIPIIO N				
Administrator					
This is the default ac user name.	Iministrator account with the "admin" user name. You cannot change the default administrator				
Old Password	Type the existing system password (1234 is the default password when shipped).				
New Password	Enter your new system password.				
Retype to confirm	Retype your new system password for confirmation.				
General Setting					
Use this section to sp	pecify the SNMP version and community (password) values.				
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c (v2c), SNMP version 3 (v3) or both (v3v2c).				
	Note: SNMP version 2c is backwards compatible with SNMP version 1.				
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNext-requests from the management station.				
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.				

LABEL	DESC RIPTIO N			
Set Community	Enter the Set $Community$ string, which is the password for the incoming Set- requests from the management station.			
	The Set $Community$ string is only used by SNMP managers using SNMP version 2c or lower.			
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.			
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

 Table 4
 Web Configurator: Password/SNMP (continued)

# 4.3 Zyxel One Network (ZON) Utility

ZON Utility is a program designed to help you deploy and manage a network more efficiently. It detects devices automatically and allows you to do basic settings on devices in the network without having to be near it.

The ZON Utility issues requests via Zyxel Discovery Protocol (ZDP) and in response to the query, the device responds back with basic information including IP address, firmware version, location, system and model name in the same broadcast domain. The information is then displayed in the ZON Utility screen and you can perform tasks like basic configuration of the devices and batch firmware upgrade in it. You can download the ZON Utility at www.zyxel.com and install it on a PC.

#### 4.3.1 Requirements

Before installing the ZON Utility on your PC, please make sure it meets the requirements listed below.

#### Operating System

At the time of writing, the ZON Utility is compatible with:

- Windows 7 (both 32-bit / 64-bit versions)
- Windows 8 (both 32-bit / 64-bit versions)
- Windows 8.1 (both 32-bit / 64-bit versions)
- Window 10 (both 32-bit / 64-bit versions)

Note: To check for your Windows operating system version, right-click on **My Computer**> **Properties**. You should see this information in the **General** tab.

#### Hardware

Here are the minimum hardware requirements to use the ZON Utility on your PC.

- Core i3 processor
- 2GB RAM

- 100MB free hard disk
- WXGA (Wide XGA 1280x800)

#### 4.3.2 Run the ZON Utility

- 1 Double-click the ZON Utility to run it.
- 2 The first time you run the ZON Utility, you will see if your device and firmware version support the ZON Utility. Click the **OK** button to close this screen.

(EL		
Her to the top	le no ensute spur device l'im	wate a supporting the 2.5N utility.
wart.	Average and Average	terrendere terren
		From Wilde
	WAX855 4 M R 8	<ul> <li>WARSECTION &amp; WARDON</li> <li>WARSECTION WARDON</li> <li>WARSECTION WARDON</li> <li>WARSECTION WARDON</li> <li>WARSECTION WARDON</li> <li>WARSECTION WARDON</li> <li>WARSECTION</li>     &lt;</ul>
		<ul> <li>WACKSYGE K, YSRUE</li> <li>WACKSYGE K, HORSEN TOP</li> <li>WACKSYGE K, HORSEN TOP</li> <li>WACKSYGE K, HORSEN K</li></ul>
	0.9336145997	From VS-15 • MARIE FISIS STR-02 - 4
	web (1) (1,500 (1	Frank (42) • MACT 128-1 AND-1
		Fran V3.23
	1.002330-3.5enm	<ul> <li>November M. Juli B.</li> <li>November M. Juli B.</li> <li>November M. Juli B.</li> <li>November M. Juli B.</li> </ul>

If you want to check the supported models and firmware versions later, you can click the **Show information about ZON** icon in the upper right hand corner of the screen. Then select the **Supported model and firmware version** link. If your device is not listed here, see the device release notes for ZON utility support. The release notes are in the firmware zip file on the Zyxel web site.

ZYXE	L								Q	6 (
188	(G) (d)	1. (89)	100 1	8) (G)	Ø	6	-	0	18	\$
			1		1		102			
20	ana	NO DE	3025-0870	1,000,000	(04.00)					
	100004	tale and the	(self-add)	it_ ingenit	UA.U	100	100			
in.	0000100-00	10.000000.0	. No to shirt	ia	1243_34	30,00				
-	icontra-e	643634828 S	0.18-08/23	H. 6638	(LANS.)		ALC: NOT			
- Para	100004	100000000	Ferral Pro-	in	(242,0)	(8) (5)				
-	00003180-04	14.05.0428-0.		172,148,1.1	1240,00	11.00				
200	1003705-0	VERSEARCE II	entited a	in Himmer	1944,39	also a				
2	HORSTNEE.	Vellow-DE IL	1+15-1111	ie	OWNER	1. 111				
i in	instruction of	Vergoorn n.	a ser the server	Ci 116.148.1.1	0.000 je					
	-0130.44	VATION DIS	100-07-04-0		C11355					


Figure 33 ZON Utility Screen

3 Select a network adapter to which your supported devices are connected.

#### Figure 34 Network Adapter



4 Click the Go button for the ZON Utility to discover all supported devices in your network.



5 The ZON Utility screen shows the devices discovered.

	ZYXEL	(A) 6 (C
	1 2 2 3 4 5 6 7	8, 9 10 11 12 13
	State State Strengt State States & States	i laharingka (anaya) yaki (ana
		(24,29)
-	🔉 minora (educedam_ peloastat_ repart)	04,0 90,00
$\mathcal{P}_{-}$	📾 coomerae volacimente en lesarrean rectacul	1242_04 milli
	an entrale explanation of the second	UARLIN PORTALIN
	🔁 ellerte (volume). Detteller, (volume).	(242,0) PHE
	🐂 coorde-ar talm(secold, m-d-arrow, Volubli)	inkujis mas
	according and according to be there the international and the inte	SALM M.C.

Figure 36 ZON Utility Screen

6 Select a device and then use the icons to perform actions. Some functions may not be available for your devices.

Note: You must know the selected device admin password before taking actions on the device using the ZON utility icons.

Figure 37 Password Prompt

ZYXEL	editelon C	>
লি	eloso entre l'in acciditator provins provies provies provies provies (1227/2020) ecoword	ni m
	CK (Lassier	Carrest

The following table describes the icons numbered from left to right in the ZON Utility screen.

ICON	DESC RIPTIO N
1 IP Configuration	Change the selected device's IP address.
2 Renew IP Address	Update a DHCP-assigned dynamic IP address.
3 Reboot Device	Use this icon to restart the selected devices. This may be useful when troubleshooting or upgrading new firmware.
4 Reset Configuration to Default	Use this icon to reload the factory-default configuration file. This means that you will lose all previous configurations.
5 Locator LED	Use this icon to locate the selected device by causing its <b>Locator</b> LED to blink.
6 Web GUI	Use this to access the selected device Web Configurator from your browser. You will need a user name and password to log in.
7 Firmware Upgrade	Use this icon to upgrade new firmware to selected devices of the same model. Make sure you have downloaded the firmware from the Zyxel website to your computer and unzipped it in advance.

Table 5 ZON Utility Icons

50

ICON	DESC RIPIIO N
8 Change Password	Use this icon to change the admin password of the selected device. You must know the current admin password before changing to a new one.
9 Configure NCC Discovery	You must have Internet access to use this feature. Use this icon to enable or disable the Nebula Control Center (NCC) discovery feature on the selected device. If it is enabled, the selected device will try to connect to the NCC. Once the selected device is connected to and has registered in the NCC, it will go into the Nebula cloud management mode.
10 ZAC	Use this icon to run the Zyxel AP Configurator of the selected AP.
11 Clear and Rescan	Use this icon to clear the list and discover all devices on the connected network again.
12 Save Configuration	Use this icon to save configuration changes to permanent memory on a selected device.
13 Settings	Use this icon to select a network adapter for the computer on which the ZON utility is installed, and the utility language.

The following table describes the fields in the ZON Utility main screen.

IABEL	DESC RIPIIO N
Туре	This field displays an icon of the kind of device discovered.
Model	This field displays the model name of the discovered device.
Firmware Version	This field displays the firmware version of the discovered device.
MAC Address	This field displays the MAC address of the discovered device.
IP Address	This field displays the IP address of an internal interface on the discovered device that first received an ZDP discovery request from the ZON utility.
System Name	This field displays the system name of the discovered device.
Location	This field displays where the discovered device is.
Status	This field displays whether changes to the discovered device have been done successfully. As the Switch does not support <b>IP Configuration</b> , <b>Renew IP address</b> and <b>Flash Locator IED</b> , this field displays "Update failed", "Not support Renew IP address" and "Not support Flash Locator LED" respectively.
Controller Discovery	This field displays if the discovered device supports the Nebula Control Center (NCC) discovery feature. If it is enabled, the selected device will try to connect to the NCC. Once the selected device is connected to and has registered in the NCC, it will go into the Nebula cloud management mode.
Serial Number	Enter the admin password of the discovered device to display its serial number.
Hardware Version	This field displays the hardware version of the discovered device.

Table 6	70N	Utility	Fields
	2011	Ommy	TICICIS

#### 4.4 Wizard

The Setup Wizard contains the following parts:

- **Basic** to configure the Switch IP address, DNS server, system password, SNMP community and link aggregation (trunking).
- Protection to enable loop guard and broadcast storm control on the Switch and its ports.
- VIAN to create a static VLAN, assign ports to the VLAN and set the ports to tag or untag outgoing frames.

• QoS - to determine a port's IEEE 802.1p priority level for QoS.

#### 4.4.1 Basic

In  $\mathbf{Basic}$ , you can set up IP/DNS, set up your password, SNMP community, link aggregation, and view finished results.

In order to set up your IP/DNS, please do the following. Click Wiza rd > Ba sic > Step 1 IP to access this screen.

#### Figure 38 Wizard > Basic > Step 1 IP

etup IP			
-od some	Maria - Asires 🗿 1902/desi		
1000			
3 Address	THE REAL PROPERTY OF		
+ 54400100000	1944 mar. 2000 C		
Detakil Solayoy	115.11 al. 154		
ALC: 2017-2017	manna		

Each field is described in the following table.

Table 7	Wizard > Basic > Step 1 IP	

LABEL	DESC RIPTIO N
Host Name	This field displays a host name.
IP Interface	Select <b>DHCPClient</b> if the Switch is connected to a router with the DHCP server enabled. You then need to check the router for the IP address assigned to the Switch in order to access the Switch's Web Configurator again.
	Select <b>Static IP Address</b> when the Switch is NOT connected to a router or you want to assign it a fixed IP address.
VID	This field displays the VLAN ID.
IP Address	The Switch needs an IP address for it to be managed over the network.
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.

IABEL	DESC RIPIIO N
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and vice versa. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.
Next	Click Next to show the next screen.
Cancel	Click <b>Cancel</b> to exit this screen without saving.

Table 7 Wizard > Basic > Step 1 IP

After clicking Next, the Password screen appears.

#### Figure 39 Wizard > Basic > Step 2 Password

nange administrator's p	assword and	I SNMP	
I is recommended to choose posses	and and SKMP-com	nunity embodic ovaid po	sherifol and only breach.
Attiministration's Passworld		shwr	
Current providers		200272	Original C water
lina prankinci		Seulon	* *
Control and South		Children et al.	salitie:
		191 Control 111	ortale:
		1007.0000-25	weak.

Each field is described in the following table.

	Table 8	Wizard > Basic > Step 2 Password
--	---------	----------------------------------

rpe the existing system password (1234 is the default password when shipped). Inter your new system password. Betype your new system password for confirmation.
nter your new system password.
etype your new system password for confirmation.
elect <b>Enabled</b> to let the Switch act as an SNMP agent, which allows a manager station to anage and monitor the Switch through the network. Select <b>Disabled</b> to turn this feature if.
elect the SNMP version for the Switch. The SNMP version on the Switch must match the ersion on the SNMP manager. Choose SNMP version 2c (v2c), SNMP version 3 (v3) or both 3v2c). ote: SNMP version 2c is backwards compatible with SNMP version 1.
iC ff. el

LABEL	DESC RIPIIO N
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNextrequests from the management station.
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the <b>Set Community</b> string, which is the password for the incoming Set- requests from the management station.
	The Set $Community$ string is only used by SNMP managers using SNMP version 2c or lower.
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

Table 8Wizard > Basic > Step 2 Password (continued)

After clicking Next, the Link Aggregation screen appears.



Each field is described in the following table.

Table 9 Wizard > Basic > Step 3 Link Aggregation

LABEL	DESC RIPIIO N	
Link Aggregation		
T1-Tx	Click the arrows to add or delete icons located on the left to desired preference.	
	Select Static if the ports are configured as static members of a trunk group.	
	Select <b>IACP</b> if the ports are configured to join a trunk group via LACP.	

GS1350 Series User's Guide

54

Tuble 7 Wizdid > busic > Step 3 Link Aggregation	
LABEL DESC RIPTIO N	
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

Table 9 Wizard > Basic > Step 3 Link Aggregation

After clicking Next, the Summary screen appears.

Figure 41	Wizard > Basic > Step 4 Summary	
-----------	---------------------------------	--

ummary					
Setup IP			Change administra	alor's possword a	nd actions skiw?
Here's March 19	325(9.6)		New Lossen		
fi h in toys	DECT CRAS		38-ME:	504595	
7152	2		CHAR OT	57	
11.5 Collection			(+8.Comprete)	parties.	
$\Phi(2,q_1,\ldots,q_{n+1}) \in \{0,1\}$	3.8.29(3.9)		Sector model	100	
Periodi Coliveration			trep Comments	61666	
fina Second	110000-0				
link Appropriate					
10(41)	100-	- Incolation			
1	5000	3.8			

Each field is described in the following table.

IABEL	DESC RIPTIO N
Setup IP	
Host Name	This field displays a host name.
IP Interface	This field displays whether the WAN interface is using a DHCP IP address or a static IP address.
VID	This field displays the VLAN ID.
IP Address	The Switch needs an IP address for it to be managed over the network.
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and vice versa. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.
Change administrate	r's password and activate SNMP
New Password	This field displays asterisks when a new password has been created.

G\$1350 Series User's Guide

LABEL	DESC RIPTIO N
SNMP	This field displays whether the Switch acts as an SNMP agent.
Version	This field displays the SNMP version for the Switch.
Get Community	This field displays the GetCommunity string.
Set Community	This field displays the <b>Set Community</b> string.
Trap Community	This field displays the <b>Tap Community</b> string.
Link Aggregation	
Group	This field displays the group number.
Туре	This field displays <b>Static</b> or <b>IACP</b> of this group.
Member	This field displays the members of this group.
Previous	Click <b>Previous</b> to show the previous screen.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

Table 10 Wizard > Basic > Step 4 Summary (continued)

#### 4.4.2 Protection

In Protection, you can set up loop guard and broadcast storm control.

In order to set up loop guard, please do the following. Click **Wizard** > **Protection** > **Step 1 Loop Guard** to access this screen.

Figure 42 Wizard > Protection > Step 1 Loop Guard

1 Loop Guard	2 Reportation Corres	3 summary
Loop Guard		
icited effects	-	3 1 1 200400 Marined
		Neal Contest

LABEL	DESC RIPTIO N	
Loop Guard		
Select all ports	Select all ports to enable the loop guard feature on all ports.	
	You can select a port by clicking it.	
Next	Click Next to show the next screen.	
Cancel	Click Cancel to exit this screen without saving.	

Table 11 Wizard > Protection > Step 1 Loop Guard

After clicking Next, the Broadcast Storm Control screen appears.

Figure 43 Wizard > Protection > Step 2 Broadcast Storm Control

4 lessoi	Boote	2 Broadcast Starm Control	3 Communy.
Broadcas	t Slorm Contr		
le est algeste			
isiden uity	2.00		
	1919	0.63	
	-	tim	(120)
		100	-
	- E2	14	
	( ere	( Prod.	1799
		in the	ious Next Concel

Each field is described in the following table.

Table 12 Wizard > Protection > Step 2 Broadcast Storm Control

IABEL	DESC RIPIIO N		
Broadcast Storm Cor	htrol		
Select all ports	Select all ports to apply settings on all ports.		
	You can select a port by clicking it.		
Broadcast pkt/s	Specify how many broadcast packets the port receives per second.		
Previous	Click Previous to show the previous screen.		
Next	Click <b>Next</b> to show the next screen.		
Cancel	Click Cancel to exit this screen without saving.		

After clicking Next, the Summary screen appears.

1 - Loop Geard	2 Becocontermidential	3 Summary
Summary		2
nep Guard		
. 1.	2.42	1
101	ia.	Seller .
101	100	100
1	3	(T)
		👘 Charlester 🖬 14945
oodcaal Slorm Control		
14	1.4	
	<b>m</b>	
121	11.40	000
-	<b>*</b>	
1		1.1
(200)	1000	1003
		🖉 ana an 📓 Sea
	10000	
	Humo.	a tarish Control

Figure 44 Wizard > Protection > Step 3 Summary


Table 13	Wizard > Protection > Step 3 Summary
----------	--------------------------------------

IABEL	DESC RIPTIO N
Summary	
Loop Guard	If the loop guard feature is enabled on a port, the Switch will prevent loops on this port.
Broadcast Storm Control	If the broadcast storm control feature is enabled on a port, the number of broadcast packets the Switch receives per second will be limited on this port.
Previous	Click <b>Previous</b> to show the previous screen.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

#### 4.4.3 VIAN

In  $\ensuremath{\textbf{VLAN}}$  , you can create VLAN, and tag VLAN settings.

Click Wizard > VIAN > VIAN Setting to access this screen.






Table 14	Wizard >	VLAN >	VLAN Setting
----------	----------	--------	--------------

LABEL	DESC RIPTIO N
VLAN Setting	
Default VLAN 1 / Access Untagged port	After you create a VLAN and select the VLAN ID from the drop-down list box, select ports and use the right arrow to add them as the untagged ports to a VLAN group.
VLAN member port	
VLAN	Type a number between 2 and 4094 to create a VLAN.
Trunk Tagged port	Select ports and use the downward arrow to add them as the tagged ports to the VLAN group(s) you created.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

#### 4.4.4 QoS

In  $\mathbf{QoS}$  , you can create QoS settings.

In order to create QoS settings, please do the following. Click Wiza rd > QoS > QoS Setting to access this screen.

Figure 46	Wizard > QoS >	QoS Setting
-----------	----------------	-------------

Qos							
QoS Settin	g						
Select ports live it	ten apply Ges ;	atority					
Selective com-	- ieil						
	~		1			-	
			100				
	1						
		Right	NUGO-	iuii -			
					. 0	niet -	(Course)

LABEL	DESC RIPTIO N
QoS Setting	
Select all ports	Select all ports to apply settings on all ports.
	You can select a port by clicking it.
High	Select ports and click the $\operatorname{Hig} h$ button, so they will have high priority.
	The port's IEEE 802.1p priority level will be set to 5. Use the <b>Basic Setting &gt; Port Setup</b> screen to adjust the value.
Medium	Select ports and click the <b>Medium</b> button and, so they will have medium priority.
	The port's IEEE 802.1p priority level will be set to 3. Use the <b>Basic Setting &gt; Port Setup</b> screen to adjust the value.
Low	Select ports and click the Low button, so they will have low priority.
	The port's IEEE 802.1p priority level will be set to 1. Use the <b>Basic Setting &gt; Port Setup</b> screen to adjust the value.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

Table 15 Wize	ard > QoS > QoS Settir	na

# 4.5 Web Configurator Layout

This guide uses G\$1350-6HP screens as an example. The screens may very slightly for different models.

The following figure shows the navigating components of a Web Configurator screen.

ZYXEL GS139	B C	) () D	E	F G H	) (	
Anna and An	Device Type Root Vector Rootacter Vector Rootacter Vector NACI Addres Bandy Norther Hechtly Roote Typi Longe Data	ACCOUNT OF A CONTRACT OF A CONTRACT.	a ( saria;200) si CSIMA	Symmit Home Symmit Condition Symmittive Symmittive Symmittive Logie Transactivitie Registration MAC Address Obuild Control Mature	antale aryototaris attractional acceleratio Decoming	of search of operation of a search of the
	of Balabase Columnation	bet .				
	Prod. Addresses		0.0010.0010			
	2-2-21813638		1012032020			
	Defail Dollevey		17121-01-03-054		Station.	
	Prine citoscal Linkowed, P				in the second	
	PVI UNICED ADDI	8			194 2255	00
	Contract Constraint C	and the second	-			
	110	Chertoine	Catholy .	Date Date (1	Contract	in the second
	Part Minotrup	Otiobio	Ind the s	North Donielli	Ondelle	18 may
	D-CF Setter	Dispersion	Saffreg .	SMP incoging	Ceptore	lettry.
	The second second					
	Part Metal	1005540	(m. 1	Unit A increase for Data	hint for	
				the second se		
	Contraction .	Lighter 1	100 Contraction 1 ( 1 ( 1	Exercising day pages (Candrig)	Continue, o	2.00

Figure 47 Web Configurator Home Screen (Status)

 ${\bf A}$  – Click the menu items to open sub-menu links, and then click on a sub-menu link to open the screen in the main window.

**B**, **C**, **D**, **E**, **F**, **G** – These are quick links which allow you to perform certain tasks no matter which screen you are currently working in.

**B** – Click this link to update the information in the screen you are viewing currently.

c – Click this link to save your configuration into the Switch's non-volatile memory. Non-volatile memory is the configuration of your Switch that stays the same even if the Switch's power is turned off.

**D** – Click this link to go to the status page of the Switch.

 $\mathbf{E}$  - Click this icon to open the wizard screen where you can configure the Switch's IP, login password, SNMP community, link aggregation, and so on.

 ${\bf F}-$  Click this link to log out of the Web Configurator.

 ${\bf G}$  – Click this link to display web help pages. The help pages provide descriptions for all of the configuration screens.

- $\mathbf{H}$  Click this link to go to the Zyxel Community Biz Forum.
- I-Click this icon to switch between the Web Configurator's Standard or Surveillance mode.
- ${\bf J}$  Click this link to go to the NCC (Nebula Control Center) portal website.

K – Click this link to go to the **Neighbor** screen where you can see and manage neighbor devices learned by the Switch.

In the navigation panel, click a main link to reveal a list of sub-menu links.

BASIC SETTING	ADVANCED APPLICATION	IP APPLICATION	MANAGEMENT
Menu Rook Letting Advanced Application P Application Watogement System Whi General Setup Central Setup Pet Setup Pat Setup Pet Setup Pet Setup Pet Setup	Memu Sase Setting Adventual opplication II Application Wannegersten VIAN Sale WAC forwarding Sale WA Board Forwarding Sale WA Board Forwarding Sale WA Board Forwarding Sale WA Board Forwarding Board Sale Sector Forwarding Board Sale Sector Forwarding Board Sale Sector Forwarding Sale Sale Sector Forwarding Sale Sale Sector Sale Sale Sector Sale Sale Sector Sale Sale Sale Sale Sale Sale Sale Sale	Methy Role Setting Annational Application # Application Monogement SRSett SRSett SRSett SRSett	Methy Rosic Setting Annotational Application Propositional Methodocom Methodocom Annotational System Lang System L

 Table 16
 Navigation Panel Sub-links Overview (Standard Mode)

The following table describes the links in the navigation panel.

Table 17	Navigation F	Panel Links	(Standard M	ode)
----------	--------------	-------------	-------------	------

LINK	DESC RIPIIO N
Basic Settings	
System Info	This link takes you to a screen that displays general system information.
General Setup	This link takes you to a screen where you can configure general identification information about the Switch.
Switch Setup	This link takes you to a screen where you can set up global Switch parameters such as VLAN type and priority queues.
IP Setup	This link takes you to a screen where you can configure the IP address and subnet mask (necessary for Switch management) and set up to 64 IP routing domains.
Port Setup	This link takes you to a screen where you can configure settings for individual Switch ports.
PoE Setup	For PoE models.
	This link takes you to a screen where you can set priorities, PoE power-up settings and schedule so that the Switch is able to reserve and allocate power to certain PDs.
Interface Setup	This link takes you to a screen where you can configure settings for individual interface type and ID.
IPv6	This link takes you to a screen where you can view IPv6 status and configure IPv6 settings.

LINK	DESC RIPTIO N
Cloud Management	This screen displays a link to a screen where you can enable or disable the <b>Nebula Control</b> <b>Center Discovery</b> feature. If it is enabled, you can have the Switch search for the NCC (Nebula Control Center). Another link takes you to the <b>Nebula Switch Registration</b> screen which has a QR code containing the Switch's serial number and MAC address for handy registration of the Switch at NCC.
Advanced Applic	ation
VLAN	This link takes you to screens where you can configure port-based or 802.1Q VLAN (depending on what you configured in the <b>Switc h Setup</b> menu). You can also configure a voice VLAN, a MAC based VLAN or a vendor ID based VLAN in these screens.
Static MAC Forwarding	This link takes you to a screen where you can configure static MAC addresses for a port. These static MAC addresses do not age out.
Static Multicast Forwarding	This link takes you to a screen where you can configure static multicast MAC addresses for ports. These static multicast MAC addresses do not age out.
Filtering	This link takes you to a screen to set up filtering rules.
Spanning Tree Protocol	This link takes you to screens where you can configure the RSTP to prevent network loops.
Bandwidth Control	This link takes you to a screen where you can configure bandwidth limits on the Switch.
Broadcast Storm Control	This link takes you to a screen to set up broadcast filters.
Mirroring	This link takes you to screens where you can copy traffic from one port or ports to another port in order that you can examine the traffic from the first port without interference.
Link Aggregation	This link takes you to screens where you can logically aggregate physical links to form one logical, higher-bandwidth link.
Port Security	This link takes you to a screen where you can activate MAC address learning and set the maximum number of MAC addresses to learn on a port.
Time Range	This link takes you to a screen where you can define different schedules.
Queuing Method	This link takes you to a screen where you can configure queuing with associated queue weights for each port.
Multicast	This link takes you to screens where you can configure various multicast features and IGMP snooping.
AAA	This link takes you to a screen where you can configure authentication, authorization and accounting services via external servers. The external servers should be RADIUS (Remote Authentication Dial-In User Service).
DHCP Snooping	This link takes you to screens where you can configure filtering of unauthorized DHCP packets in your network.
Loop Guard	This link takes you to a screen where you can configure protection against network loops that occur on the edge of your network.
Errdisable	This link takes you to screens where you can view errdisable status and configure errdisable settings in CPU protection, errdisable detect, and errdisable recovery.
Green Ethernet	This link takes you to a screen where you can configure green Ethernet settings in EEE, auto power down, and short reach for each port.
LLDP	This link takes you to screens where you can configure LLDP settings.
Auto PD Recovery	This link takes you to a screen where you can enable and configure Auto PD Recovery on the Switch.
ONVIF	This link takes you to a screen where you can configure a specific VLAN to run ONVIF.
IP Application	
DiffServ	This link takes you to screens where you can enable DiffServ, configure marking rules and set DSCP-to-IEEE802.1p mappings.
· · · · · · · · · · · · · · · · · · ·	

 Table 17
 Navigation Panel Links (Standard Mode) (continued)

LINK	DESC RIPTIO N
DHCP	This link takes you to screens where you can configure the DHCP settings.
ARP Setup	This link takes you to screens where you can configure the ARP learning settings for each port.
Management	
Maintenance	This link takes you to screens where you can perform firmware and configuration file maintenance as well as reboot the system.
Access Control	This link takes you to screens where you can change the system login password and configure SNMP and remote management.
Diagnostic	This link takes you to a screen where you can ping IP addresses, run traceroute, test port(s) and show the Switch's location.
System Log	This link takes you to a screen where you can view system logs.
Syslog Setup	This link takes you to a screen where you can setup system logs and a system log server.
Cluster Management	This link takes you to screens where you can configure clustering management and view its status.
MAC Table	This link takes you to a screen where you can view the MAC addresses (and types) of devices attached to what ports and VLAN IDs.
ARP Table	This link takes you to a screen where you can view the MAC addresses – IP address resolution table.
Path MTU Table	This link takes you to a screen where you can view the path MTU aging time, index, destination address, MTU, and expire settings.
Configure Clone	This link takes you to a screen where you can copy attributes of one port to other ports.
IPv6 Neighbor Table	This link takes you to a screen where you can view the IPv6 neighbor table which includes index, interface, neighbor address, MAC address, status and type.
Port Status	This link takes you to a screen where you can view the port statistics.

 Table 17
 Navigation Panel Links (Standard Mode) (continued)

#### Table 18 Navigation Panel Sub-links Overview (Surveillance Mode)

SUMMARY	Q UIC K SEIUP	SYSTEM	PORT
Standard P Succession	.9° quex saue	SYSTEM Dystem Internation Monunal schop Cloud Wangement	<ul> <li>PORT</li> <li>Ande RC case very</li> <li>Pot Setup</li> <li>Pot Setup</li> </ul>

SWIICHING	NEIWO RKING	SEC URITY	MAINTENANCE
SWITCHING           Acceleral State Control           IncAggragelion           IncAggragelion           IncAggragelion           IncAggragelion           IncAggragelion	HEIWORRING Prake CHAT	SOCURINY - Assess Control - Assess Control - Sogne - Benedia Vanagement - State - Sources Assess Control - Sources Assess Control - Sources Assess Control - Sources Assess	MAINTENANEE       Handorsman       Handorsman

LINK	DESC RIPTIO N
Summary	This screen displays the Switch's general device information, connected ports, and used power.
Quick Setup	This link takes you to a screen where you can display the <b>IP Address Information</b> of the Switch and use the links to the <b>IP Setup</b> , <b>Auto PD Recovery</b> , <b>PoE Setup</b> , <b>Port Setup</b> , and <b>ONVIF</b> screens.
SYSTEM	
System Information	This link takes you to a screen that displays general system information.
General Setup	This link takes you to a screen where you can configure general identification information about the Switch.
Cloud Management	This screen displays a link to a screen where you can enable or disable the <b>Nebula Control</b> <b>Center Discovery</b> feature. If it is enabled, you can have the Switch search for the NCC (Nebula Control Center). Another link takes you to the <b>Nebula Switch Registration</b> screen which has a QR code containing the Switch's serial number and MAC address for handy registration of the Switch at NCC.
PORT	
Auto PD Recovery	This screen allows you to enable and configure Auto PD Recovery on the Switch.
PoE Setup	For PoE models.
	This screen allows you to set priorities, PoE power-up settings and schedule so that the Switch is
	able to reserve and allocate power to certain PDs.
Port Setup	This screen allows you to configure settings for individual Switch ports.
SWITCHING	
Broadcast Storm Control	This link takes you to a screen to set up broadcast filters.
Link Aggregation	This link takes you to screens where you can logically aggregate physical links to form one logical, higher-bandwidth link.
Loop Guard	This link takes you to a screen where you can configure protection against network loops that occur on the edge of your network.
VLAN	This link takes you to screens where you can configure port-based or 802.1Q VLAN (depending on what you configured in the <b>Switc h Se tup</b> menu). You can also configure a voice VLAN, a MAC based VLAN or a vendor ID based VLAN in these screens.
NETWORKING	
IP Setup	This screen allows you to configure the IP address and subnet mask (necessary for Switch management) and set up to 64 IP routing domains.
ONVIF	This screen allows you to configure a specific VLAN to run ONVIF.
SECURITY	
Access Control	
Logins	This link takes you to a screen where you can change the system login password, as well as configure up to four login details.
Remote Management	This link takes you to a screen where you can specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
SNMP	This link takes you to screens where you can specify the SNMP version and community (password) values, configure where to send SNMP traps from the Switch, enable loopguard/ errdisable/poe/linkup/linkdown/lldp/transceiver-ddm/storm-control on the Switch, specify the types of SNMP traps that should be sent to each SNMP manager, and add/edit user information.
Service Access Control	This link takes you to a screen where you can decide what services you may use to access the Switch.

 Table 19
 Navigation Panel Links (Surveillance Mode)

LINK	DESC RIPTIO N
Maintenance	
Backup Configuration	This link takes you to a screen where you can save your Switch's configurations (settings) for later use.
Firmware Upgrade	This link takes you to a screen to upload firmware to your Switch.
Reboot System	This link takes you to a screen to reboot the Switch without turning the power off.
Restore Configuration	This link takes you to a screen where you can upload a stored device configuration file.
Save Configuration	This link takes you to a screen where you can save the current configuration (settings) to a specific configuration file on the Switch.
Tech-Support	This link takes you to a screen where you can download related log reports for issue analysis. Log reports include CPU history and utilization, crash and memory.

 Table 19
 Navigation Panel Links (Surveillance Mode) (continued)

#### 4.5.1 Change Your Password

After you log in for the first time, it is recommended you change the default administrator password. Click **Management > Access Control > Logins** to display the next screen.

اوما Asiministicala			6	cces Control
10 IM two				
New Yours				
Robinsta	nord <b>a</b> ren			
Hereitaan Juopilen yn		enever you doorged the	rsystem will hads your and dryne	e herver
Fall Largers				
Login	User Name	Fourward	Retype to confirm	Tiblege
1 I.				
2				
3				
4				
		Apply Consol		

Figure 48 Change Administrator Login Password

## 4.6 Save Your Configuration

When you are done modifying the settings in a screen, click **Apply** to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

Click the **Save** link in the upper right hand corner of the Web Configurator to save your configuration to non-volatile memory. Non-volatile memory refers to the Switch's storage that remains even if the Switch's power is turned off.

Note: Use the **Save** link when you are done with a configuration session.

# 4.7 Switch Lockout

You could block yourself (and all others) from managing the Switch if you do one of the following:

- 1 Delete the management VLAN (default is VLAN 1).
- 2 Delete all port-based VLANs with the CPU port as a member. The "CPU port" is the management port of the Switch.
- **3** Filter all traffic to the CPU port.
- 4 Disable all ports.
- 5 Misconfigure the text configuration file.
- 6 Forget the password and/or IP address.
- 7 Prevent all services from accessing the Switch.
- 8 Change a service port number but forget it.

Note: Be careful not to lock yourself and others out of the Switch.

### 4.8 Reset the Switch

If you lock yourself (and others) from the Switch or forget the administrator password, you will need to reload the factory-default configuration file or reset the Switch back to the factory defaults.

#### 4.8.1 Restore Button

Press the **RESTO RE** button for more than 7 seconds to have the Switch automatically reboot and restore the factory default file. See Section 3.3 on page 39 for more information about the LED behavior.

#### 4.8.2 Restore Custom Default


Press the **RESTO RE** button for 3 to 7 seconds to have the Switch automatically reboot and restore the lastsaved custom default file. See Section 3.3 on page 39 for more information about the LED behavior.

#### 4.8.3 Reboot the Switch

Press the **RESET** button to reboot the Switch without turning the power off. See Section 3.3 on page 39 for more information about the LED behavior.

# 4.9 Log Out of the Web Configurator

Click **Logout** in a screen to exit the Web Configurator. You have to log in with your password again after you log out. This is recommended after you finish a management session for security reasons.



# 4.10 Help

The Web Configurator's online help has descriptions of individual screens and some supplementary information.

Click the Help link from a Web Configurator screen to view an online help description of that screen.

# C HAPTER 5 Initial Setup Example

# 5.1 Overview

This chapter shows how to set up the Switch for an example network.

The following lists the configuration steps for the initial setup:


- Create a VLAN
- Set Port VID
- Configure Switch Management IP Address

#### 5.1.1 Create a VLAN

VLANs confine broadcast frames to the VLAN group in which the ports belongs. You can do this with port-based VLAN or tagged static VLAN with fixed port members.

In this example, you want to configure port 1 as a member of VLAN 2.

Figure 50 Initial Setup Network Example: VLAN



1 Click Advanced Application > VIAN > VIAN Configuration in the navigation panel and click the Static VIAN Setup link.

VIAN Contependen	VIAN 6
Gine V An temp	Clock and
V AN Ford Script	Carlo Here.
Volee VLAN Selup	Click for
Michiller Andreas	Carlo Maria
Vender 10 Seere MCAN Seriep	Clicking

2 In the Static VIAN screen, select ACTIVE, enter a descriptive name in the Name field and enter 2 in the VIAN Group ID field for the VIAN2 network.

Shifter MIGN				MAR Cooling
<b>x</b> -		<u></u>		
н		bong	4e	
Group D		9		
Port		Cartral		legging
-		Normal	v	zi Tk logging
6	C Normal	S Tool	C Tarbidden	
- <u>-</u>	C Normal	C tood	C terbidden	It legging) Z it legging
3	S Normal	C foed		
			C Tarbidden	z≤ Tk Topging T
A	8 Normal	C fixed	C Forbidden	$\mathbb{Z}$ 1k legging
÷	S. Harrisol	C. Famil	C. Foriúlien	<ul> <li>Taloquing</li> </ul>
÷.	🕷 tiomai	C fixed	C Tarbidden	≓ Tkilogging
		Add Conc	cel Clear	
VID:	active	N	ame	
1	Yes			1
		Delete	Connel	
		LIGHT	LIG TOBI	

Note: The VIAN Group ID field in this screen and the VID field in the IP Setup screen refer to the same VLAN ID.

- 3 Since the VIAN2 network is connected to port 1 on the Switch, select Fixed to configure port 1 to be a permanent member of the VLAN only.
- 4 To ensure that VLAN-unaware devices (such as computers and hubs) can receive frames properly, clear the **TX Tagging** check box to set the Switch to remove VLAN tags before sending.
- 5 Click Add to save the settings to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.


#### 5.1.2 Set Port VID

Use PVID to add a tag to incoming untagged frames received on that port so that the frames are forwarded to the VLAN group that the tag defines.

In the example network, configure 2 as the port VID on port 1 so that any untagged frames received on

that port get sent to VLAN 2.





1 Click Advanced Applications > VIAN > VIAN Configuration in the navigation panel. Then click the VIAN Port Setup link.


	VLAN Port Setting				YLA	N Configuration
Port	Ingress Check	PVID	Acceptable	Frome Type	VLAN Trunking	Isolation
	Г		AL	~	7	٦
	L	2	AL	~		
2		1	AL	~		
з	Г	1	AL	×		
4	L	1	AL	×		
5		1	AL	×		
6	Г	1	AL	×		
			Apply Our	cel		

2 Enter 2 in the **PVID** field for port 1 and click **Apply** to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

#### 5.1.3 Configure Switch Management IP Address

If the Switch fails to obtain an IP address from a DHCP server, the Switch will use 192.168.1.1 as the management IP address. You can configure another IP address in a different subnet for management purposes. The following figure shows an example.





- 1 Connect your computer to any Ethernet port on the Switch. Make sure your computer is in the same subnet as the Switch.
- 2 Open your web browser and enter 192.168.1.1 (the default IP address) in the address bar to access the Web Configurator. See Section 4.2 on page 43 for more information.
- 3 Click Basic Setting > IP Setup > IP Configuration in the navigation panel.

Second Management	Statuter		12 I NW
e Alexènia		Cipitana (Stri	M
		Contest	2 via Compatible
	O Sets Pixes	CHO COLOR	
	Contraction of the second	P.S.Akers.	172:01.22.1
		• September Variation	Weight 51.541
		Jerout Ceneway	172.21 48.284
	90		
		and Carter	
ana generali P Address		an Carter	
anagementif Address # Address			
2.0	- 	9 ( ) 9 ( )	
n Activity		9 ( ) 9 ( )	
* Ostion 8 Silver (Mak VE 16 out 1 in reary	1V2/565 9/01/2555 2 01/21/01	9 ( ) 9 ( )	
e Octoren 6 Sulveet Maak VIC	1W2/563 1W2/563 2	9 ( ) 9 ( )	
* Ostion 8 Silver (Mak VE 16 out 1 in reary	142/1842 142/1842 142/1842 2 11/211/2	9 ( ) 9 ( )	

GS1350 Series User's Guide

- 4 Configure the related fields in the IP Setup screen.
- 5 For the VIAN2 network, enter 192.168.2.1 as the IP address and 255.255.255.0 as the subnet mask.
- 6 In the VID field, enter the ID of the VLAN group to which you want this management IP address to belong. This is the same as the VLAN ID you configure in the Static VIAN screen.
- 7 Click Add to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

# C HA PTER 6 Tuto ria ls

# 6.1 Overview

This chapter provides some examples of using the Web Configurator to set up and use the Switch. The tutorials include:

- How to Use DHCPv4 Snooping on the Switch
- How to Use DHCPv4 Relay on the Switch

# 6.2 How to Use DHC Pv4 Snooping on the Switch

You only want DHCP server  $\mathbf{A}$  connected to port 4 to assign IP addresses to all devices in VLAN network ( $\mathbf{V}$ ). Create a VLAN containing ports 4, 5 and 6. Connect a computer  $\mathbf{M}$  to the Switch for management.




Figure 53 Tutorial: DHCP Snooping Tutorial Overview

Note: For related information about DHCP snooping, see Section 23.2 on page 185.

The settings in this tutorial are as the following.

HOST	PORTCONNECTED	VIAN	PVID	DHC P SNO O PING PORT TRUSTED		
DHCP Server (A)	4	1 and 100	100	Yes		
DHCP Client (B)	5	1 and 100	100	No		
DHCP Client ( $\mathbf{C}$ )	6	1 and 100	100	No		

Table 20 Tutorial: Settings in this Tutorial

1 Access the Switch through http://192.168.1.1 by default. Log into the Switch by entering the user name (default: admin) and password (default: 1234).

2 Go to Advanced Application > VIAN > VIAN Configuration > Static VIAN Setup, and create a VLAN with ID of 100. Add ports 4, 5 and 6 in the VLAN by selecting **Fixed** in the **Control** field as shown.

De-select  $\mathbf{T}_{\mathbf{X}} \mathbf{T}_{\mathbf{A}} \mathbf{g} \mathbf{g} \mathbf{i} \mathbf{g}$  because you do not want outgoing traffic to contain this VLAN tag.

Figure 54 Tutorial: Create a VLAN and Add Ports to It

Static VIAN				VLAH Configuration
ACTIVE		2		
Hame		M ANH	00	
VLAN Compute		100	/	
Port		Control		ia gaing
-		11101110	n/	⊠ tx tecana
1	(6) New real	C. Faced	C. Fortunities	🖂 ta kappag
2	R. Harrisol	C. Famil	C. Solidier	<ul> <li>Talk point</li> </ul>
2	🖲 Normal	C tood	C torteddon	<u> ⊇ tx tecene</u>
(+	C. New York	S. Frank	C. Fortunities	The background
<b>1</b>	C Normal	🗟 Reed	C Farbidden	I tx Topping
6	C Normal	B tood	C Farbiddon	⊟ te locano
-				
		Add Cane	of Cear	
V D	Active	N	aree-	
1	Yes			
		10 distantes	Chevron I.	

3 Go to Advanced Application > VIAN > VIAN Configuration > VIAN Port Setup, and set the PVID of the ports 4, 5 and 6 to 100. This tags untagged incoming frames on ports 4, 5 and 6 with the tag 100.

	VLON Port Setting				VLA	N Configuration
Port	Ingress Check	PVID	Acceptable	Frame Type	VLAN Trunking	soletion
			Al	~		11
1		1	AL	$\sim$	=	
2		1	Al	V	_	
8		I	Al	V	_	
(÷		100	AL	Ý		
- 5		100	AL	×	—	
6		100	Al	V	_	
			Apply Con	icel i		

Figure 55 Tutorial: Tag Untagged Frames

4 Go to Advanced Application > DHCP Snooping > Configure, activate and specify VLAN 100 as the DHCP VLAN as shown. Click Apply.

Figure 56	Tutorial: Specify DHCP VLAN
-----------	-----------------------------

DHCP Snooping Configure			DHCP Snoopl	ng Port	VLAN
Active D100 <sup>a</sup> Vien	<b>⊽</b> ⊜ 083516 ⊛ 100	)			
Database					_
Agent IIM					
TmeoutInterval	300	seconds			
Write delay interval	300	seconds			
Ronew DHCP Snooping URL				bnow	
is a reason of the data of the				<u></u>	
-		ncel			

- 5 Click the **Port** link at the top right corner.
- 6 The DHCP Snooping Port Configure screen appears. Select Trusted in the Server Trusted state field for port 4 because the DHCP server is connected to port 4. Keep ports 5 and 6 Untrusted because they are connected to DHCP clients. Click Apply.

DHC	P Snooping Port Configure		Configure
Port	Server Trusted state	Rote (pp	<b>(5)</b>
	Uninsteed 🛩		
1	Untrusted 🛩	0	
2	Unitusted 🗸	0	
3	Untrustoci 🗸	0	
(1	Trusted 🗸 🗸	0	
5	Unirosled 🗸	0	
6	Unfrusted 🗸 🖉	0	
	Apply Concel		

Figure 57 Tutorial: Set the DHCP Server Port to Trusted

7 Go to Advanced Application > DHC P Snooping > Configure > VIAN, show VLAN 100 by entering 100 in the VIAN Search by VID field and click Search. Then select Yes in the Enabled field of the VLAN 100 entry shown at the bottom section of the screen.

If you want to add more information in the DHCP request packets such as source VLAN ID or system name, you can also select an **Option82 Profile** in the entry. See Section 23.4.1.3 on page 194.

Figure 58 Tutorial: Enable DHCP Snooping on this VLAN

ier of Search Results: 1	
VID Enabled.	Option 82 Profile
No 😒	× .
(10) Yes V	V

8 Click Save at the top right corner of the Web Configurator to save the configuration permanently.



- 9 Connect your DHCP server to port 4 and a computer (as DHCP client) to either port 5 or 6. The computer should be able to get an IP address from the DHCP server. If you put the DHCP server on port 5 or 6, the computer will NOT be able to get an IP address.
- **10** To check if DHCP snooping works, connect to the Switch via Telnet. Use the command "show dhcp snooping binding" to see the DHCP snooping binding table as shown next.

sysname#	show dhcp snoop	ing binding					
	MacAddress	IpAddress	Lease	Туре	VLAN	Port	
00:02:	00:00:00:1c	10.10.1.16	6d23h59m20s	dhcp-snooping	100	5	
Total	number of bindin	gs: 1					


# 6.3 How to Use DHC Pv4 Re lay on the Switch

This tutorial describes how to configure your Switch to forward DHCP client requests to a specific DHCP server. The DHCP server can then assign a specific IP address based on the information in the DHCP requests.

## 6.3.1 DHC P Re la y Tuto ria l Intro d uc tio n

In this example, you have configured your DHCP server (192.168.2.3) and want to have it assign a specific IP address (say 172.16.1.18) to DHCP client **A** based on the system name, VLAN ID and port number in the DHCP request. Client **A** connects to the Switch's port 2 in VLAN 102.

#### Figure 59 Tutorial: DHCP Relay Scenario



#### 6.3.2 Create a VIAN

Follow the steps below to configure port 2 as a member of VLAN 102.

- 1 Access the Web Configurator through the Switch's management port.
- 2 Go to Basic Setting > Switch Setup and set the VLAN type to 802.1Q. Click Apply to save the settings to the run-time memory.

Figure 60 Tutorial: Set VLAN Type to 802.1Q

Sector for Section pr				_
MARHam.		)		
MAC Address Learning	Aging Time	300	240.00X2	
Arts Argony Lea	Segura de com	500	SCOMP.	
Pletty Goese Assignment	Priority Priority Priority Priority Priority Priority Priority	$\begin{array}{c} 7 \\ 6 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\ 7 \\$		
	Apple Central			
	steads, see and			

- $\label{eq:lick} \textbf{3} \quad Click \, \textbf{Advanced Application} > \textbf{VIAN} > \textbf{VIAN Configuration} > \textbf{Static VIAN Setup} \,.$
- 4 In the Static VIAN screen, select ACTIVE, enter a descriptive name (VLAN 102 for example) in the Name field and enter 102 in the VIAN Group ID field.
- 5 Select Fixed to configure port 2 to be a permanent member of this VLAN.
- 6 Clear the TX Tagging check box to set the Switch to remove VLAN tags before sending.
- 7 Click Add to save the settings to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

rig ure 61 1010	nui. Cieule u	I SIGIIC VLAIN		
Staffic VLAN				VLAH Configuration
ACTIVE		2		
Name		VLAN 1	102	
MAN Group ID		102		
Pari		Carbol		Tagging
4		Normal	~	Z to to group
1	90 Harrisol	C Famil	C. Fortúkien	<ul> <li>Tyle puipe</li> </ul>
0	C Hornol	8 Ford	C. Forbidden	- Tallagging
1	R. Record	C Faced	C. Fortunities	Z to logging
4.	S. Harrisol	C. Famil	C. Fasticities	<ul> <li>Tyle pairs</li> </ul>
5	8 Normal	C tood	C Hartadd an	⊠ tx lessing
6	(6) Record	C mont	C. Rocket Kines	Z to logger
		$\frown$		
			of Close	
				_
VD	Active	P	ome	4
1	¥40			
		Detelor	Connect	

Figure 61 Tutorial: Create a Static VLAN

8 Click the VIAN Configuration link in the Static VIAN Setup screen and then the VIAN Port Setup link in the VIAN Configuration screen.

ngure 62 TOTOHOL. CICK THE VLAN FOR SETTING LINK	
VLAN Configuration	MLAH Status
Maille MEAN Sellup	Wick likes
Call Port Setup	All as liere
Manual V. A Nasalaga	Co. F. House
MAC Event Viol Safet	<u>Allo S Here</u>
Monarce ID Research AN Society	Co. F. House

Figure 62 Tutorial: Click the VLAN Port Setting Link

- 9 Enter 102 in the **PVID** field for port 2 to add a tag to incoming untagged frames received on that port so that the frames are forwarded to the VLAN group that the tag defines.
- 10 Click Apply to save your changes back to the run-time memory.

	VLAN Port Setting				VLA	d Configuratio
Port	Ingress Check	PVID	Acceptable	home Type	VLAN Trynking	Isolation
•			Al	$\mathbf{v}$	=	
1	11	1	AL	¥		
2		102	AL	~	—	
3		1	Al	v		
4		1	All	×	_	
5		I	<u>A1</u>	<u> </u>	_	
6	11	1	AL	¥		
			— —			

Figure 63 Tutorial: Add Tag for Frames Received on Port 2

11 Click the **Save** link in the upper right corner of the Web Configurator to save your configuration permanently.

#### 6.3.3 Configure DHC Pv4 Re lay

Follow the steps below to enable DHCP relay on the Switch and allow the Switch to add relay agent information (such as the VLAN ID) to DHCP requests.

- 1 Click IP Application > DHCP > DHCPv4 and then the Global link to open the DHCP Relay screen.
- 2 Select the Active check box.
- 3 Enter the DHCP server's IP address (192.168.2.3 in this example) in the **Remote DHCP Server1** field.
- 4 Select default1 or default2 in the Option 82 Profile field.
- 5 Click **Apply** to save your changes back to the run-time memory.

Figure 64 Tutorial: Set DHCP Server and Relay Information

DHCP Kring		This For
An Iron	2	
A second a 1986 Of which in	192.180.2.2	
A contract OFF Of Annalysis 2	0.000	
Steel 1, 1988 Waarson 2	0.000	
Op for 32 Notice	defeel the	

- 6 Click the Save link in the upper right corner of the Web Configurator to save your configuration permanently.
- 7 The DHCP server can then assign a specific IP address based on the DHCP request.

#### 6.3.4 Trouble shooting

Check the client **A**'s IP address. If it did not receive the IP address 172.16.1.18, make sure:

- 1 Client **A** is connected to the Switch's port 2 in VLAN 102.
- 2 You configured the correct VLAN ID, port number and system name for DHCP relay on both the DHCP server and the Switch.

You clicked the  $\mathbf{Save}$  link on the Switch to have your settings take effect.

# C HAPTER 7 Status

# 7.1 Overview

This chapter describes the screens for System Status, and Neighbor Details.

## 7.1.1 What You Can Do

- Use the Status screen (Section 7.2 on page 82) to see the Switch's general device information, system status, and IP addresses. You can also display other status screens for more information.
- Use the **Neighbor** screen (Section 7.2.1 on page 84) to view a summary and manage Switch's neighbor devices.
- Use the **Neighbor Detail** screen (Section 7.2.2 on page 86) to view more detailed information on the Switch's neighbor devices.

# 7.2 Status

The **Status** screen displays when you log into the Switch or click **Status** at the top right corner of the Web Configurator. The **Status** screen displays general device information, system status, and its IP addresses.

igure 65 Status					
3 hele a					Bastles
Device Information					
Terrary Type:	COLOUR ADD		April 10 States at	CX1080	
Read Streams	- 24 CO   C2/C1/	2015	Apple and the second		
For two in the two ends	244 20 <b>5 2010</b> 000	e i navnagorinni -	April 10 Million 1	01/21/2010	62 <i>4</i> 2 62
Line is one Written of	241 C		Apple and the Taxas	000 mm (m 24	a na shekara na Sugara na S
MARCAR Interaction	least distants	•	Legendor and the set		
Canad Mandalana	215/01/125/026		Hoggshachter VACCAstations	to a did di dV	AU1
Hylen i Marke	2 her alle some <u>22</u>	- Cashe	COMPANY COMPANY AND A	Description	est.
ташынары	outrouv w jere				
ueto)					
P A debrar Information					
Park As the rest		172.0140.0			
Second Second		205 259 292 6			
Technoli Carlesser,		172.0143.054		Private pr	
Providence descendary	den a				
We the subscript $\Delta r$ is in as				<b>Even and see</b>	No. 14
Device Status and Gu	tele Configuratio				
81	u kibi+	.effing	v sever u karus 🐧	unable	setting.
r artieling	<b>Lieble</b>	. effing	viors control	utoble.	setting .
Land ricelay	<b>L</b> icible	.affing	KAHE photoing	<b>Libolois</b>	setting.
Guich Linia					
Leri violus	(custo)	a	Unit Apprepation Jonus	VAU 103	
<b>Dispranta</b>	Withern L	9 <b>9</b>	Kemple Appear Vonirol	rechoso	cort
vuer latus		Colla Contro			

Figure 65 Status

Table 21	Status
	510105

	DESC RIPTIO N
Device Informatio	on
Device Type	This field displays the model name of this Switch.
System Name	This field displays the name used to identify the Switch on any network.
Boot Version	This field displays the version number and date of the boot module that is currently on the Switch.
System Location	This field displays the geographic location of your Switch. You can change the setting in the <b>Basic Setting &gt; General Setup</b> screen.
Firmware Version	This field displays the version number and date of the firmware the Switch is currently running.
System Time	This field displays the current date and time in the UAG. The format is mm-dd-yyyy hh:mm:ss.
Hardware Version	This field displays the hardware version number of the Switch. The integer is the model version, and the decimal is the version of the hardware change. For example, V1.0 is a hardware version for the Switch where 1 identifies the GS1350 Series, and .0 is the first hardware change.
System Up Time	This field displays how long the Switch has been running since it last restarted or was turned on.
MAC Address	This field displays the MAC addresses of the Switch.
Login Timeout(mins)	This field displays how many minutes a management session can be left idle before the session times out. After it times out you have to log in with your password again.
Serial Number	This field displays the serial number of this Switch. The serial number is used for device tracking and control.

Table 21 Status (continued)

LABEL	DESC RIPIIO N						
Registration MAC Address	This field displays the MAC address of the Switch that you must use to register at myZyxel.com or the NCC (Nebula Control Center).						
Hybrid Mode	This field displays whether the Switch is in <b>Standalone</b> mode or <b>Cloud</b> mode. In <b>Standalone</b> mode you can see a link to a QR code to register the Switch to use NCC (Nebula Control Center).						
Cloud Control Status	This field displays the registration and connection status between the Switch and the NCC (Nebula Control Center). See Section 3.3 on page 39 for more information on the Cloud LED.						
	In Standalone mode, the status will display <b>Disconnected</b> or <b>Unregistered</b> . In cloud mode the status will display <b>Connected</b> or <b>Disconnected</b> .						
	Connected – The Switch is registered with and connected to the NCC.						
	<b>Disconnected</b> – The Switch is not connected to the NCC.						
	Unregistered – The Switch is not registered with the NCC.						
PoE Usage	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices and the total power the Switch can provide to the connected PDs. It also shows the percentage of PoE power usage.						
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in <b>Basic Setting</b> $>$ <b>PoE Se tup</b> .						
Detail	Click this link to go to the <b>Basic Setting &gt; System Info</b> screen to check other detailed information, such as system resource usage and the Switch temperature, fan speeds or voltage.						
IP Address Inform	ation						
IPv4 Address	This field displays the Switch's current IPv4 address.						
Subnet Mask	This field displays the Switch's subnet mask.						
Default Gateway	This field displays the IP address of the Switch's default gateway.						
IP Setup	Click the link to go to the <b>Basic Setting</b> > <b>IP Setup</b> screen.						
IPV6 Global Unicast Address	This field displays the Switch's IPv6 global unicast address						
IPV6 Link-Local Address	This field displays the Switch's IPv6 link-local address.						
IPv6 configuration	Click the link to go to the <b>Basic Setting</b> > <b>IPv6</b> screen.						
Device Status and Quick	This section shows whether a feature is enabled or not on the Switch. You can click a feature's <b>Setting</b> link to go to the configuration screen for the feature.						
Configuration	Hover your cursor over a red exclamation mark to display information about the feature.						
Quick Links	This section provides the shortcut link to a specific configuration screen.						

## 7.2.1 NeighborScreen

The **Neighbor** screen allows you to view a summary and manage the Switch's neighboring devices. It uses Layer Link Discovery Protocol (LLDP) to discover all neighbor devices connected to the Switch including non-Zyxel devices. You can use this screen to perform tasks on the neighboring devices like login, power cycle (turn the power off and then back on again), and reset to factory default settings. For more information on LLDP, see (Section 27.1 on page 208).

This screen shows the neighboring device first recognized on an Ethernet port of the Switch. Device information is displayed in gray when the neighboring device is offline.

Click Status > Neighbor to see the following screen.

Politika 👘	Fori regnee	es nestra	disk.	FOLLINGS (A)	vystem name	1955	<b>P</b> 0-	zwa cycle	Routed the centerality
1			Desce	0-1				the de-	the second second
2			Design	<u>(*)</u>				Contra-	E-com
$\boldsymbol{\lambda}_{i} = \boldsymbol{\lambda}_{i}$	-	-	DOM:	N9	1262.54	0.000	-	Acres in 1	the second
А —			Desce	0-1				the de-	the second second
8			16.97	<u>en</u>				(Contra-	E men
2	-	-	North 1	502	-	-	-	Accession	the second

Figure 66 Status > Neighbor

The following table describes the fields in the above screen.

Table 22 Status > Neighbo	or
---------------------------	----

IABEL	DESC RIPTIO N
Port	This shows the port of the Switch, on which the neighboring device is discovered.
Port Name	This shows the port description of the Switch.
PD Health	This shows the status of auto PD recovery on this port. See Section 28.2 on page 230 for more information on how to enable auto PD recovery on the Switch and ports.
	<ul> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not</li> </ul>
	supply power to the connected PD. Note: The status will NOT be updated instantaneously after enabling or disabling the <b>Active</b> switch in the <b>Advanced Application</b> > <b>Auto PD Recovery</b> screen (see Section 28.2 on page 230 for details). It will wait until the configured <b>Resume Polling Interval</b> (sec) has lapsed.
Link	This shows the speed (either 10M for 10Mbps, 100M for 100Mbps, or 1G for 1 Gbps) and the duplex (F for full duplex or H for half). This field displays <b>Down</b> if the port is not connected to any device.
PoE Draw (W)	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.
System Name	This shows the system name of the neighbor device.
IPv4	This shows the IPv4 address of the neighbor device. The IPv4 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.
IPv6	This shows the IPv6 address of the neighbor device. The IPv6 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.
PWR Cycle	Click the <b>Cycle</b> button to turn OFF the power of the neighbor device and turn it back ON again. A count down button (from 5 to 0) starts.
	Note: The Switch must support power sourcing (PSE) or the network device is a powered device (PD).

Table 22 S	Status > Neighbor (	(continued)	
------------	---------------------	-------------	--

IABEL	DESC RIPTIO N
Reset to Default	Click the <b>Reset</b> button to reset the neighboring device to its factory default settings. A warning message " <b>Are you sure you want to load factory default?</b> " appears prompting you to confirm the action. After confirming the action a count down button (from 5 to 0) starts.
	Note:
	• The Switch must support power sourcing (PSE) or the network device is a powered device (PD).
	<ul> <li>If multiple neighbor devices use the same port, the Reset button is not available.</li> <li>You can only reset Zyxel powered devices that support the ZON utility.</li> </ul>
	Select an entry's check box to select a specific port. Otherwise, select the check box in the table heading row to select all ports.
Flush	Click the <b>Flush</b> button to remove information about neighbors learned on the selected ports.

#### 7.2.2 Neighbor Detail

Use this screen to view detailed information about the neighboring devices. Device information is displayed in gray when the neighboring device is currently offline.

Up to 10 neighboring device records per Ethernet port can be retained in this screen even when the devices are offline. When the maximum number of neighboring device records per Ethernet port is reached, new device records automatically overwrite existing offline device records, starting with the oldest existing offline device record first.

Click the Neighbor Detail link in the Status > Neighbor screen to see the following screen.

annal Part 1										
	-	R3 Health	-	- Merch	Deser	Pell Dava (	N.	0.0	PWR Cycle	
local Part 2										
Need.	-	PO Health	-	1000	Deve	Pot Drow (	<b>A</b>	0.0	PWR Cycle	
iopal Port 3										
Detect.	-	PO Health	-	646	10064/5	Poli Drow (	A1	0.8	PWR Cycle	
kernigte-										
Evolution Home	1043.04	Model	1668970	046		frances	WARDOLAG JORY	801 20807102_013	IMAG	e4-18-5b-17-bo-0d
Pet.		00.00				Prob			-	
Part 37	Dense.	Louistics	9102						Reset to Defend	
local Pot 4										
Deero.	-	FO Health	-	1000	Down	Pot Drow (	W	0.0	PWR Cycle	
local Port 6										
Deepo.	-	R0 Health		100	10.4	Poli Drow (	A1	0.0	PWR Cycle	
kerniste.										
System Monte		Model				Free and			MMAG	depic levilsed
(Past						Pede				
Part de de Sed. Des St	Deve	Course No.	-						Receiptor Distance	Truct .
local Pat 4										
Seec.		PO Health		Res.	Down	Pot Drow C	80	0.9	PWR Grote	

Figure 67 Status > Neighbor > Neighbor Detail

The following table describes the fields in the above screen.

Table 23 Status > Neighbor > Neighbor Detail

LABEL	DESC RIPIIO N
Local Port	This shows the port of the Switch, on which the neighboring device is discovered.
Desc.	This shows the port description of the Switch.

G\$1350 Series User's Guide

Table 23	Status > Neighbor > Neighbor Detail (continued)
----------	---

LABEL	DESC RIPTIO N			
PD Health	This shows the status of auto PD recovery on this port.			
	<ul> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not supply power to the connected PD.</li> </ul>			
Link	This shows the speed (either <b>10M</b> for 10Mbps, <b>100M</b> for 100Mbps, or <b>1G</b> for 1 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). This field displays <b>Down</b> if the port is not connected to any device.			
PoE Draw (W)	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.			
PWR Cycle	Click the <b>Cycle</b> button to turn OFF the power of the neighbor device and turn it back ON again. A count down button (from 5 to 0) starts.			
	Note: The Switch must support power sourcing (PSE) or the network device is a powered device (PD).			
Remote				
System Name	This shows the system name of the neighbor device.			
Model	This shows the model name of the neighbor device. This field will show "-" for devices that do not support the ZON utility.			
Firmware	This shows the firmware version of the neighbor device. This field will show "-" for devices that do not support the ZON utility.			
IPv4	This shows the IPv4 address of the neighbor device. The IPv4 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.			
IPv6	This shows the IPv6 address of the neighbor device. The IPv6 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.			
Port	This show the number of the neighbor device's port which is connected to the Switch.			
Desc.	This shows the description of the neighbor device's port which is connected to the Switch.			
Location	This shows the geographic location of the neighbor device. This field will show "-" for devices that do not support the ZON utility.			
MAC	This shows the MAC address of the neighbor device.			
Reset to Default	Click the <b>Reset</b> button to reset the neighbor device to its factory default settings. A warning message " <b>Are you sure you want to load factory default</b> ?" appears prompting you to confirm the action. After confirming the action a count down button (from 5 to 0) starts.			
	<ul> <li>Note:</li> <li>The Switch must support power sourcing (PSE) or the network device is a powered device (PD).</li> <li>If multiple neighbor devices use the same port, the Reset button is not available.</li> <li>You can only reset Zyxel powered devices that support the ZON utility.</li> </ul>			

# C HA PTER 8 Basic Setting

# 8.1 Overview

This chapter describes how to configure the System Info, General Setup, Switch Setup, IP Setup, Port Setup, PoE Setup, Interface Setup, IPv6, and Cloud Management screens.

#### 8.1.1 What You Can Do

- Use the **System Info** screen (Section 8.2 on page 88) to check the firmware version number and monitor the Switch temperature.
- Use the General Setup screen (Section 8.3 on page 90) to configure general settings such as the system name and time.
- Use the Switch Setup screen (Section 8.5 on page 92) to choose your VLAN type and assign priorities to queues.
- Use the **IP Setup** screen (Section 8.6 on page 94) to configure the Switch IP address, default gateway device, management VLAN ID, and proxy server.
- Use the Port Setup screen (Section 8.7 on page 99) to configure Switch port settings.
- Use the **PoE Setup** screens (Section 8.8 on page 101) to view the current amount of power that PDs are receiving from the Switch and set the priority levels for the Switch in distributing power to PDs. This screen is available for PoE model(s) only.
- Use the Interface Setup screens (Section 8.9 on page 107) to configure Switch interface type and interface ID settings.
- Use the IPv6 screens (Section 8.10 on page 108) to view IPv6 status and IPv6 configuration.
- Use the Cloud Management screen (Section 8.11 on page 119) to display links to Nebula Control Center Discovery and Nebula Switch Registration screens.

# 8.2 System Information

In the navigation panel, click **Basic Setting** > **System Info** to display the screen as shown. Use this screen to view general system information. You can check the firmware version number and monitor the Switch temperature.

Figure 68 Basic Setting > System Info

systematic					
Synam Hane		461,60			
i noduch wode				•	
AND IN MARKED				018   04/14/2020	
There is Addition			terretata?	281	
ALL History					
COLUMN TRANSPORT					
CURPER (A)			1267		
warrory utilization					
Нате	Tek	al (byte)	Vae	d (byte)	Villization (%)
14 M 10 M 10 M	20	a 12/8	4	12161	12
hardware Manilar					
Foreissen Maniles Foreissen für 15 1 <u>C</u>					
	Current	MAX	WN	Trachold	Statur
$\operatorname{targetedently}(\underline{C}, \times)$	Corrent 414	MAX 12.7	MIN 644	Three hald	Status Hornal

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N		
System Name	This field displays the descriptive name of the Switch for identification purposes.		
Product Model	This field displays the product model of the Switch. Use this information when searching for firmware upgrade or looking for other support information in the website.		
ZyNOS F/W Version	This field displays the version number of the Switch 's current firmware including the date created.		
Ethernet Address	This field refers to the Ethernet MAC (Media Access Control) address of the Switch.		
CPU Utilization	CPU utilization quantifies how busy the system is. <b>Cument</b> (%) displays the current percentage of CPU utilization.		
Memory Utilization	Memory utilization shows how much DRAM memory is available and in use. It also displays the current percentage of memory utilization.		
Name	This field displays the name of memory pool.		
Total (byte)	This field displays the total number of bytes in this memory pool.		
Used (byte)	This field displays the number of bytes being used in this memory pool.		
Utilization (%)	This field displays the percentage (%) of memory being used in this memory pool.		
Hardware Monit	or		
Temperature Unit	The Switch has temperature sensors that are capable of detecting and reporting if the temperature rises above the threshold. You may choose the temperature unit (Centigrade or Fahrenheit) in this field.		
Temperature (C/F)	CPU/MAC refers to the location of the temperature sensor on the Switch printed circuit board.		
Current	This shows the current temperature at this sensor.		
MAX	This field displays the maximum temperature measured at this sensor.		
MIN	This field displays the minimum temperature measured at this sensor.		

Table 24 Basic Setting > System Info

G\$1350 Series User's Guide

<b>T</b> I I O (	<b>D 1 D 1 U</b>		, ,, ,,
Table 24	Basic Setting > S	vstem Into	(continued)

LABEL	DESC RIPTIO N
Threshold	This field displays the upper temperature limit at this sensor.
Status	This field displays $Nomal$ for temperatures below the threshold and $Emor$ for those above.

# 8.3 General Setup

Use this screen to configure general settings such as the system name and time. Click **Basic Setting** > **General Setup** in the navigation panel to display the screen as shown.

Figure 69	Basic Setting > General Setup
-----------	-------------------------------

Report String	
Ayrian Barris	C20.040
fam.	
Contract Francis Report	
In The American Socker	NC NEW N
land a second Affaire as	1 and a parage
free stays symplet and	Salah - Meraka
Daniel en i	24 - 11 - 24 - 12 March - 24 - 12 March - 24 - 25 - 25 March - 26 - 27 March
New Joint (Encoded)	22. · · · · · · · · · · · · · · · · · ·
Carried Date:	2017. 01 01
New York (1995 Alternal)	2017. 01 01
la esta e	48: -
Barry and the second second	
- Kell Cale	red of Sandry in An way in 1928 in
the Hards of	Tel Zusting
l sell inter Altere and all these areas	e la asecon se sie
	Approx Control

LABEL	DESC RIPTIO N
System Name	Choose a descriptive name for identification purposes. This name consists of up to 64 printable characters; spaces are allowed.
Location	Enter the geographic location of your Switch. You can use up to 32 printable ASCII characters; spaces are allowed.
Contact Person's Name	Enter the name of the person in charge of this Switch. You can use up to 32 printable ASCII characters; spaces are allowed.

T		/ II IN
Table 25	Basic Setting > General Setup	(continued)

LABEL	DESC RIPTIO N			
Use Time Server when Bootup	Enter the time service protocol that your time server uses. Not all time servers support all protocols, so you may have to use trial and error to find a protocol that works. The main differences between them are the time format.			
	When you select the <b>Daytime</b> ( <b>RFC 867</b> ) format, the Switch displays the day, month, year and time with no time zone adjustment. When you use this format it is recommended that you use a Daytime timeserver within your geographical time zone.			
	<b>Time</b> ( <b>RFC-868</b> ) format displays a 4-byte integer giving the total number of seconds since 1970/ 1/1 at 0:0:0.			
	NTP (RFC-1305) is similar to Time (RFC-868).			
	<b>None</b> is the default value. Enter the time manually. Each time you turn on the Switch, the time and date will be reset to 1970-1-1 0:0:0.			
Time Server IP Address	Enter the IP address or domain name of your timeserver. The Switch searches for the timeserver for up to 60 seconds.			
Time Server Sync Interval	Enter the period in minutes between each time server synchronization. The Switch checks the time server after every synchronization interval.			
Current Time	This field displays the time you open this menu (or refresh the menu).			
New Time (hh:min:ss)	Enter the new time in hour, minute and second format. The new time then appears in the <b>Current Time</b> field after you click <b>Apply</b> .			
Current Date	This field displays the date you open this menu.			
New Date (yyyy- mm-dd)	Enter the new date in year, month and day format. The new date then appears in the Current Date field after you click Apply.			
Time Zone	Select the time difference between UTC (Universal Time Coordinated, formerly known as GMT, Greenwich Mean Time) and your time zone from the drop-down list box.			
Daylight Saving Time	Daylight saving is a period from late spring to early fall when many countries set their clocks ahead of normal local time by one hour to give more daytime light in the evening.			
	Select this option if you use Daylight Saving Time.			
Start Date	Configure the day and time when Daylight Saving Time starts if you selected <b>Daylight Saving</b> <b>Time</b> . The time is displayed in the 24 hour format. Here are a couple of examples:			
	Daylight Saving Time starts in most parts of the United States on the second Sunday of March. Each time zone in the United States starts using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>Second</b> , <b>Sunday</b> , <b>March</b> and <b>2:00</b> .			
	Daylight Saving Time starts in the European Union on the last Sunday of March. All of the time zones in the European Union start using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last</b> , <b>Sunday</b> , <b>March</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).			
End Date	Configure the day and time when Daylight Saving Time ends if you selected <b>Daylight Saving</b> <b>Time</b> . The time field uses the 24 hour format. Here are a couple of examples:			
	Daylight Saving Time ends in the United States on the first Sunday of November. Each time zone in the United States stops using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>First</b> , <b>Sunday</b> , <b>November</b> and <b>2:00</b> .			
	Daylight Saving Time ends in the European Union on the last Sunday of October. All of the time zones in the European Union stop using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last</b> , <b>Sunday</b> , <b>October</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).			

LABEL	DESC RIPTIO N		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click Cancel to begin configuring this screen afresh.		

Table 25 Basic Setting > General Setup (continued)

# 8.4 Introduction to VLANs

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Devices on a logical network belong to one group. A device can belong to more than one group. With VLAN, a device cannot directly talk to or hear from devices that are not in the same group(s); the traffic must first go through a router.

In MTU (Multi-Tenant Unit) applications, VLAN is vital in providing isolation and security among the subscribers. When properly configured, VLAN prevents one subscriber from accessing the network resources of another on the same LAN, thus a user will NOT see the printers and hard disks of another user in the same building.

VLAN also increases network performance by limiting broadcasts to a smaller and more manageable logical broadcast domain. In traditional switched environments, all broadcast packets go to each and every individual port. With VLAN, all broadcasts are confined to a specific broadcast domain.

Note: VLAN is unidirectional; it only governs outgoing traffic.

See Chapter 9 on page 121 for information on port-based and 802.1Q tagged VLANs.

# 8.5 Switch Setup

Click **Basic Setting** > **Switch Setup** in the navigation panel to display the screen as shown. The VLAN setup screens change depending on whether you choose **802.1Q** or **Port Based** in the **VLAN Type** field in this screen. Refer to Chapter 9 on page 121 for more information on VLAN.

4N Type	⊖ are rig ⊕ ter based i		
AAC Accles without high	Aging line	500	seconds.
RT Aging Time	Aging Time	200	sector and s
Samily Symposite Assignment	Print by 2	7 😪	
	hise has	8 W	
	Crienty2	$\sim$	
	<b>Montys</b>	4 😼	
	Anna 178	3 👽	
	Prior 1-22	$1 \sim 1$	
	Priority1	0 😒	
	Anna 178	2 👾	

#### Figure 70 Basic Setting > Switch Setup

Table 26	Basic Setting > Switch Setup
----------	------------------------------

IABEL	DESC RIPTIO N				
VLAN Type	Choose 802.1Q or Port Based. The VIAN Setup screen changes depending on whether you choose 802.1Q VLAN type or Port Based VLAN type in this screen. See Chapter 9 on page 121 for more information.				
MAC Address Le	arning				
MAC address le must be active.	arning reduces outgoing traffic broadcasts. For MAC address learning to occur on a port, the port				
Aging Time	Enter a time from 10 to 1000000 seconds. This is how long all dynamically learned MAC addresses remain in the MAC address table before they age out (and must be relearned).				
ARP Aging Time					
Aging Time	Enter a time from 60 to 1000000 seconds. This is how long dynamically learned ARP entries remain in the ARP table before they age out (and must be relearned). The setting here applies to ARP entries which are newly added in the ARP table after you click <b>Apply</b> .				
Priority Queue A	ssignment				
define class of se	tes up to eight separate traffic types by inserting a tag into a MAC-layer frame that contains bits to ervice. Frames without an explicit priority tag are given the default priority of the ingress port. Use configure the priority level-to-physical queue mapping.				
	ight physical queues that you can map to the 8 priority levels. On the Switch, traffic assigned to eues gets through faster while traffic in lower index queues is dropped if the network is congested.				
Priority Level (The incorporates the	e following descriptions are based on the traffic types defined in the IEEE 802.1d standard (which 802.1p).				
Priority 7	Typically used for network control traffic such as router configuration messages.				
Priority 6	Typically used for voice traffic that is especially sensitive to jitter (jitter is the variations in delay).				
Priority 5	Typically used for video that consumes high bandwidth and is sensitive to jitter.				
Priority 4	Typically used for controlled load, latency-sensitive traffic such as SNA (Systems Network Architecture) transactions.				
Priority 3	Typically used for "excellent effort" or better than best effort and would include important business traffic that can tolerate some delay.				
Priority 2	This is for "spare bandwidth".				

IABEL	DESC RIPTIO N
Priority 1	This is typically used for non-critical "background" traffic such as bulk transfers that are allowed but that should not affect other applications and users.
Priority 0	Typically used for best-effort traffic.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

Table 26 Basic Setting > Switch Setup (continued)

## 8.6 IP Setup

Use the IP Setup screen to configure the default gateway device, the default domain name server and add IP domains.

#### 8.6.1 IP Interfaces

The Switch needs an IP address for it to be managed over the network. When the Switch (in standalone mode) fails to obtain an IP address from a DHCP server, the static IP address 192.168.1.1 will be automatically added and used as the Switch's management IP address.

On the Switch, an IP address is not bound to any physical ports. Since each IP address on the Switch must be in a separate subnet, the configured IP address is also known as IP interface (or routing domain). In addition, this allows routing between subnets based on the IP address without additional routers.

You can configure multiple routing domains on the same VLAN as long as the IP address ranges for the domains do not overlap. To change the IP address of the Switch in a routing domain, simply add a new routing domain entry with a different IP address in the same subnet.

You can configure up to 64 IP domains which are used to access and manage the Switch from the ports belonging to the pre-defined VLANs.

Note: You must configure a VLAN first. Each VLAN can have multiple management IP addresses, and you can log into the Switch via different management IP addresses simultaneously.

#### 8.6.2 IP Status

Figure 71 Basic Setting > IP Setup

	la la					P Control street
	Financia National	Service 1			in the second	
	1.701110	I		1	HI X H	
IF Interfaces						
index -	P iddeen	P Ashered Marsh	STD:	Type		diana 👘
	212,000	000000.00	I.	20 M 1	Former	<b>H</b> abertan

IABEL	DESC RIPTIO N
IP Status	
Domain Name Server	This field displays the IP address of the DNS server.
Source	This field displays whether the DNS server address is configured manually ( <b>Static</b> ) or obtained automatically using <b>DHC Pv4</b> .
IP Interface	
Index	This field displays the index number of an entry.
IP Address	This field displays IP address of the Switch in the IP domain.
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.
VID	This field displays the VLAN identification number of the IP domain on the Switch.
Туре	This shows whether this IP address is dynamically assigned from a DHCP server or manually assigned ( <b>Sta tic</b> ).
Renew	Click this to renew the dynamic IP address.
Release	Click this to release the dynamic IP address.

Table 27 Basic Setting > IP Setup

#### 8.6.3 IP Status Details

Use this screen to view IP status details. Click a number in the **Index** column in the **IP Status** screen to display the screen as shown next.

193 Island Dated		E PM/
here .	Den.	
¥15	and the second se	
<ul> <li>Addreigi</li> </ul>	A 222 (* 273	
er sylonien eksik	2,020,2200	

Table 28	Basic Setting > IP Setup > IP Status Details: Static
----------	--

LABEL	DESC RIPIIO N
Туре	This shows the IP address is manually assigned (Static).
VID	This is the VLAN identification number to which an IP routing domain belongs.
IP Address	This is the IP address of your Switch in dotted decimal notation for example 192.168.1.1.
IP Subnet Mask	This is the IP subnet mask of your Switch in dotted decimal notation for example 255.255.255.0.

Miktories für kont		D'Shee
hit	(1963)	
YID .	1	
4 Address	Cartosena y	
Carlos et Want :	- 465 478 539 F .	
.acto line	36400 (perioda	
Antonio Lenie	4.978 C	
Rediratione	75ol0 seconds	
Long live (left	1018-01-01-021266	
many later first	2012-01-02-0012-02-02-02-02-02-02-02-02-02-02-02-02-02	
Detault Generican		
Body some		
Of 2 Server		

Figure 73 Basic Setting > IP Setup > IP Status Details: DHCP

LABEL	DESC RIPTIO N
Туре	This shows the IP address is dynamically assigned from a DHCP server (DHCP).
VID	This is the VLAN identification number to which an IP routing domain belongs.
IP Address	This is the IP address of your Switch in dotted decimal notation for example 192.168.1.1.
IP Subnet Mask	This is the IP subnet mask of your Switch in dotted decimal notation for example 255.255.255.0.
Lease Time	This displays the length of time in seconds that this interface can use the current dynamic IP address from the DHCP server.
Renew Time	This displays the length of time from the lease start that the Switch will request to renew its current dynamic IP address from the DHCP server.
Rebind Time	This displays the length of time from the lease start that the Switch will request to get any dynamic IP address from the DHCP server.
Lease Time Start	This displays the date and time that the current dynamic IP address assignment from the DHCP server began. You should configure date and time in <b>Basic Setting</b> $>$ <b>General Setup</b> .
Lease Time End	This displays the date and time that the current dynamic IP address assignment from the DHCP server will end. You should configure date and time in <b>Basic Setting</b> > <b>General Setup</b> .
Default Gateway	This displays the IP address of the default gateway assigned by the DHCP server. 0.0.0.0 means no gateway is assigned.
DNS Server	This displays the IP address of the primary and secondary DNS servers assigned by the DHCP server. 0.0.0.0 means no DNS server is assigned.

## 8.6.4 IP Configuration

Use this screen to configure the default gateway device, default domain name server and add IP domains.

T-Iska	-	C.15st	ar Haterads Diarse Configurati
Collegia Norma Servar I			
Family Honor Search			
216 ALTO 220 ALTO			
	1.2		
Color, 1 Manadoméry IP Addresi	<b>W</b> 196 2 ( Sec.	Clatter-63	F
		Con U	Mail Corporation
	7704050100001		Face collocated
	O \$166 (\$46)	le Adares	1/2/21/40/4
		P Subnah Mosk	255,265,252,0
		Delcal Colevor	172,21,43,254
		102	1/2/2010/12/2014
P Ada ka P Ada ka P Sepert Mose V S	-35 		
P Addrea Missionet Mark			
P Ada wa P Sopret More V/S Delou 1 Sofewar	00 00 00 00 00 00 00 00 00 00 00		
P Adales P sopert More V/1 Celou 1 Schevop	20 2.0 00 2.0 00 2.0		Saladt Sofeed).

Figure 74 Basic Setting > IP Setup > IP Configuration

IABEL	DESC RIPTIO N
Domain Name Server 1/2	Enter a domain name server IPv4 address in order to be able to use a domain name instead of an IP address.
Default Managen	nent IP Address
Use these fields to	create or edit IP routing domains on the Switch.
DHCP Client	Select this option if you have a DHCP server that can assign the Switch an IP address, subnet mask, a default gateway IP address and a domain name server IP address automatically.
Option-60	DHCP Option 60 is used by the Switch for identification to the DHCP server using the VCI (Vendor Class Identifier) on the DHCP server. The Switch adds it in the initial DHCP discovery message that a DHCP client broadcasts in search of an IP address. The DHCP server can assign different IP addresses or options to clients with the specific VCI or reject the request from clients without the specific VCI.
	Select this and enter the device identity you want the Switch to add in the DHCP discovery frames that go to the DHCP server. This allows the Switch to identify itself to the DHCP server.
Class-ID	Type a string of up to 32 characters to identify this Switch to the DHCP server. For example, Zyxel- TW.
Static IP Address	Select this option if you do not have a DHCP server or if you wish to assign static IP address information to the Switch. You need to fill in the following fields when you select this option.
IP Address	Enter the IP address of your Switch in dotted decimal notation, for example, 172.21.40.x. This is the IP address of the Switch in an IP routing domain.


G\$1350 Series User's Guide

IABEL	DESC RIPTIO N				
IP Subnet Mask	Enter the IP subnet mask of an IP routing domain in dotted decimal notation, for example, 255.255.252.0.				
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 172.21.43.254.				
VID	Enter the VLAN identification number to which an IP routing domain belongs.				
Apply Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses th changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation pane your changes to the non-volatile memory when you are done configuring.					
Cancel	Click Cancel to reset the fields to your previous configuration.				
Management IP	Address				
Use these fields to	o set the settings for the management port.				
IP Address	Enter the out-of-band management IP address of your Switch in dotted decimal notation. For example, 192.168.0.1.				
IP Subnet Mask	Enter the IP subnet mask of your Switch in dotted decimal notation, for example, 255.255.255.0.				
VID	Enter the VLAN identification number to which an IP routing domain belongs.				
Default Gateway	Enter the IP address of the default outgoing gateway in dotted decimal notation, for example, 192.168.0.254.				
Add	Click this to create a new entry.				
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to reset the fields to your previous configuration.				
Index	This field displays the index number of an entry.				
IP Address	This field displays IP address of the Switch in the IP domain.				
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.				
VID	This field displays the VLAN identification number of the IP domain on the Switch.				
Default Gateway	This field displays the IP address of the default outgoing gateway in dotted decimal notation.				
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.				
Delete	Click <b>De le te</b> to remove the selected entry from the summary table.				
	Note: Deleting all IP subnets locks you out of the Switch.				
Cancel	Click Cancel to clear the check boxes.				

 Table 30
 Basic Setting > IP Setup > IP Configuration (continued)

## 8.6.5 Network Proxy Configuration

The proxy server of an organization may prohibit communication between the Switch and NCC (Nebula Control Center) (Section 8.11 on page 119). Use this screen to enable communication between the Switch and NCC through the proxy server.





As of this writing, this setting only allows communication between the Switch and the NCC.

Figure 76	Basic Setting > IP S	Setup > IP Configuration >	Network Proxy Configuration

Heles Chase Contractor	wa internet in the second s	E bek a
Automotive States		
An en		
4.4		
A discussion of the second		
Station in		
Parament		
	Apple Science	

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Active	Select this option to enable communication between the Switch and NCC through a proxy server.
Server	Enter the IP address (dotted decimal notation) or host name of the proxy server. When entering the host name, up to 128 alphanumeric characters are allowed for the <b>Server</b> including special characters inside the square quotes $[-!@#$%^&*()_+{}]:"<>?=[]\;',./']$
Port	Enter the port number of the proxy server (1 – 65535).
Authentication	Select this option to enable proxy server authentication using a Usemame and Password.
Username	Enter a login user name from the proxy server administrator. Up to 32 alphanumeric characters are allowed for the <b>Usemame</b> including special characters inside the square quotes $[\sim!@#\$\%^&*()_+{}]:"<>?==[]::]$
Password	Enter a login password from the proxy server administrator. Up to 32 alphanumeric characters are allowed for the <b>Password</b> including special characters inside the square quotes $[\sim!@#\%\%\&"()_+{}]:"<>?==[]::$
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to your previous configuration.

Table 31 Basic Setting > IP Setup > IP Configuration > Network Proxy Configuration

# 8.7 Port Setup

Use this screen to configure Switch port settings. Click Basic Setting > Port Setup in the navigation panel to display the configuration screen.

Port	Ashve	Name	Speed / I	Noplan.	Difended Range 🙃	How Control	802.1p Priority
•	-		Auto	~	_	_	$c \sim$
1	<b>.</b>	port1	Auto	¥	÷.		0.54
2	E.		Auto	$\sim$	=	Ξ	0.84
$\mathbf{x}_{i}$	м.		Auro	¥			6 w
4	<b>Z</b>		Auto	$\sim$	=	=	$\frac{c}{<\omega}$
6	м <sup>а</sup> (		Auto	¥			0.54
6	<u>.</u>		Aut o	$\sim$	_	_	0.94

Forum 77	Basic Setting > Port Setup
rigure 77	pasic seming > rom semp

Table 32 Basic Setting > Port Setup

IABEL	DESC RIPTIO N
Port	This is the port index number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable a port. The factory default for all ports is enabled. A port must be enabled for data transmission to occur.
Name	Enter a descriptive name that identifies this port. You can enter up to 64 alpha-numerical characters.
	Note: Due to space limitation, the port name may be truncated in some Web Configurator screens.
Speed/Duplex	Select the speed and the duplex mode of the Ethernet connection on this port. Choices are <b>Auto</b> , <b>10-an</b> (10M/auto-negotiation), <b>10M/Half Duplex</b> , <b>10M/Full Duplex</b> , <b>100-an</b> (100M/auto-negotiation), <b>100M/Half Duplex</b> , <b>100M/Full Duplex</b> and <b>1G/Full Duplex</b> (Gigabit connections only).
	Selecting <b>Auto</b> (auto-negotiation) allows one port to negotiate with a peer port automatically to obtain the connection speed and duplex mode that both ends support. When auto-negotiation is turned on, a port on the Switch negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer port does not support auto-negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, a port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer port are the same in order to connect.

IABEL	DESC RIPTIO N
Extended	Select this check box to extend the PoE range up to 250 meters.
Range	After you enable this feature, the port will transfer data at a rate up to10 Mbps in full duplex mode. If a PD is connected to the port, the Switch follows the IEEE 802.3at PoE+ standard to supply power to the connected PD during power-up.
	Note: Maximum PoE power that can be supplied to a PD at 250 m is 15 W.
	Note: If you enable extended range on a port after the connected PD starts up completely, you must disable PoE and enable it again or disconnect and reconnect the cable to the port for extended mode to take effect.
	Note: The port speed and duplex mode you previously configured will be applied automatically when the extend range feature is disabled.
Flow Control	A concentration of traffic on a port decreases port bandwidth and overflows buffer memory causing packet discards and frame losses. <b>Flow Control</b> is used to regulate transmission of signals to match the bandwidth of the receiving port.
	The Switch uses IEEE802.3x flow control in full duplex mode and backpressure flow control in half duplex mode.
	IEEE802.3x flow control is used in full duplex mode to send a pause signal to the sending port, causing it to temporarily stop sending signals when the receiving port memory buffers fill.
	Back Pressure flow control is typically used in half duplex mode to send a "collision" signal to the sending port (mimicking a state of packet collision) causing the sending port to temporarily stop sending signals and resend later. Select <b>Flow Control</b> to enable it.
802.1p Priority	This priority value is added to incoming frames without a (802.1p) priority queue tag. See <b>Priority</b> <b>Queue Assignment</b> in Table 26 on page 93 for more information.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 32 Basic Setting > Port Setup (continued)

# 8.8 PoEStatus

A powered device (PD) is a device such as an access point or a switch, that supports PoE (Power over Ethernet) so that it can receive power from another device through an Ethernet port.

In the figure below, the IP camera and IP phone get their power directly from the Switch. Aside from minimizing the need for cables and wires, PoE removes the hassle of trying to find a nearby electric outlet to power up devices.




Figure 78 Powered Device Examples

You can also set priorities so that the Switch is able to reserve and allocate power to certain PDs.

Note: The PoE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.

To view the current amount of power that PDs are receiving from the Switch, click Basic Setting > PoESetup.

Figure 79 Basic Setting > PoE Status

Pu	E Status					PoETin	ic Range Selve - P	oE Se
PoE Mox	de la				Consumption			
lotel Per	wer (W)				60.0			
PoE Use	ger ( <b>R</b> )				0			
Pol. Uso	ge Ibreshold	(5)			25			
Consum	ing Power (V	0			0.0			
Allocated Power (W)				NA				
- nor one	ed toomer had				40.0			
	ing Fower (W				60.0			
			Priatity	Power-Up		Max Power (W)	Time-Range Sl	la he
Remoini	ing Forwar (N	1	Priority	Power-Up 902.3Li	Consuming	Max Power (W) 0.0	Time-Range 31	
Romeini Port	ing Power (W Shate	d			Consuming Power (W)		Time-Ronge St	ahe
Romaînî Part 1	ing Power (W shele Endble	ciona 0	Low	002.364	Consuming Power (W) 0.0	0.0		ate
Romainí Part 1 7	Shohe Engble	⊂less 0 0	Low	002.364 ND2 364	Consuming Power (W) 0.0 100	0.0 0.0		ahə

Table 33 Basic Setting > PoE Status

IABEL	DESC RIPTIO N
PoE Mode	This field displays the power management mode used by the Switch, whether it is in <b>Classific a tion</b> or <b>Consumption</b> mode.
Total Power (W)	This field displays the total power the Switch can provide to the connected PoE-enabled devices on the PoE ports.
PoE Usage (%)	This field displays the amount of power currently being supplied to connected PoE devices (PDs) as a percentage of the total PoE power the Switch can supply.
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in <b>Basic Setting</b> $>$ <b>PoESetup</b> .
PoE Usage Threshold (%)	This field displays the percentage of PoE usage. The Switch will generate a trap and/or a log when the usage exceeds the specified threshold.
Consuming Power (W)	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices.
Allocated Power (W)	This field displays the total amount of power the Switch (in classification mode) has reserved for PoE after negotiating with the connected PoE devices. It shows <b>NA</b> when the Switch is in consumption mode.
	Consuming Power(W) can be less than or equal but not more than the Allocated Power(W).
Remaining Power (W)	This field displays the amount of power the Switch can still provide for PoE.
	Note: The Switch must have at least 16 W of remaining power in order to supply power to a PoE device, even if the PoE device needs less than 16 W.
Port	This is the port index number.

IABEL	DESC RIPHO N
State	<ul> <li>This field shows which ports can receive power from the Switch. You can set this in Section 8.8.2 on page 104.</li> <li>Disable - The PD connected to this port cannot get power supply.</li> <li>Enable - The PD connected to this port can receive power.</li> </ul>
Class	<ul> <li>This shows the power classification of the PD. Each PD has a specified maximum power that fall under one of the classes.</li> <li>The Class is a number from 0 to 6, where each value represents the range of power that the Switch provides to the PD. The power ranges in PoE standards are as follows.</li> <li>Class 0 - default: 0.44 W to 15.4 W.</li> <li>Class 1 - default: 0.44 W to 4 W.</li> <li>Class 2 - default: 0.44 W to 7 W.</li> <li>Class 3 - default: 0.44 W to 15.4 W.</li> <li>Class 4 - default: 0.44 W to 30 W.</li> <li>Class 5 - default: 0.44 W to 45 W.</li> <li>Class 6 - default: 0.44 W to 60 W.</li> </ul> Note: You can extend or set a limit on the maximum power the connected PD can use on a port in Basic Setting > PoESetup > PoESetup.
Priority	<ul> <li>When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority first.</li> <li>Critic al has the highest priority.</li> <li>High has the Switch assign power to the port after all critical priority ports are served.</li> <li>Low has the Switch assign power to the port after all critical and high priority ports are served.</li> </ul>
Power-Up	This field displays the PoE standard the Switch uses to provide power on this port.
Consuming Power (W)	This field displays the current amount of power consumed by the PD from the Switch on this port.
Max Power (W)	This field displays the maximum amount of power the PD could use from the Switch on this port.
Time-Range State	<ul> <li>This field shows whether or not the port currently receives power from the Switch according to its schedule.</li> <li>It shows "In" followed by the time range name if PoE is currently enabled on the port.</li> <li>It shows "Out" if PoE is currently disabled on the port.</li> <li>It shows "" if no schedule is applied to the port. PoE is enabled by default.</li> </ul>

 Table 33
 Basic Setting > PoE Status (continued)

## 8.8.1 PoETime Range Setup

Use this screen to apply a schedule to the ports on the Switch. You must first configure a schedule in the **Advanced Application** > **Time Range** screen.

Click the PoETime Range Setup link in the Basic Setting > PoEStatus screen. The following screen opens.

Figure 80	Basic Setting >	PoE Setup >	PoE Time Range	e Setup
-----------	-----------------	-------------	----------------	---------

PoE Time Range Setup		PoE Status
Port		
Time Ronge		
	Apply Ceor	
Port	Time Range Profiles	
1	-	
2		
3		
4		
5		Г
	Delete Cancel	

IABEL	DESC RIPTIO N
Port	Enter the number of the port to which you want to apply a schedule.
Time Range	This field displays the name of the schedule that you have created using the Advanced Application > Time Range screen.
	Select a pre-defined schedule to control when the Switch enables PoE to provide power on the port. To select more than one schedule, press [SHIFT] and select the choices at the same time.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Port	This field displays the index number of the port. Click a port number to change the schedule settings.
Time Range Profiles	This field displays the name of the schedule which is applied to the port. PoE is enabled at the specified time or date.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the rules that you want to remove and then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the selected check boxes.

Table 34 Basic Setting > PoE Setup > PoE Time Range Setup

#### 8.8.2 **PoESetup**

Use this screen to set the PoE power management mode, priority levels, power-up mode and the maximum amount of power for the connected PDs.

Click the PoESetup link in the Basic Setting > PoEStatus screen. The following screen opens.

Pot Schop Ruf Made Continuous Pot Ros Bargin Bare	:			ntestan®⊘ tec ⊠	antemptan	[ol.95)
Part	saino	study	Рамонир	Mas Pawer (mW)		LLOP Power VI MDI
-		collection - v	1002200	~	11	
1	Z	Low v	802,3br	~		Z
2	$\overline{\nabla}$	Low x	802.851	Y		$\overline{\nabla}$
3	2	inw – v	002.355			<u>z^</u>
4	$\geq$	bow v	802.3cf	×		Z
4		10W V	10022601	· ·	11	~
			Apply Conect			

Figure 81 Basic Setting > PoE Setup

Table 35	Basic Setting > PoE Setup
TUDIE 33	Dusic seriiriy - i or serop

IABEL	DESC RIPTIO N
PoE Mode	<ul> <li>Select the power management mode you want the Switch to use.</li> <li>Classific ation - Select this if you want the Switch to reserve the maximum power for each PD according to the PD's power class and priority level. If the total power supply runs out, PDs with lower priority do not get power to function. In this mode, the maximum power is reserved based on what you configure in Max Power or the standard power limit for each class.</li> <li>Consumption - Select this if you want the Switch to supply the actual power that the PD needs. The Switch also allocates power based on a port's Max Power and the PD's power class and priority level. The Switch puts a limit on the maximum amount of power the PD can request and use. In this mode, the default maximum power that can be delivered to the PD is 33 W (IEEE 802.3at Class 4) or 22 W (IEEE 802.3af Classes 0 to 3).</li> </ul>
Continuous PoE	Select Active to guarantee continuous power supply to the connected PDs while the Switch is restarting after a warm reboot. The Switch will NOT perform a power cycle on the connected PDs. If you do a cold reboot, the Switch also restarts the connected PDs.
PoE Usage Threshold (%)	Enter a number ranging from 1 to 99 to set the threshold. The Switch will generate a trap and/or log when the actual PoE usage is higher than the specified threshold.
Port	This is the port index number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Changes in this row are copied to all the ports as soon as you make them.
Active	Select this to provide power to a PD connected to the port. If left unchecked, the PD connected to the port cannot receive power from the Switch.
Priority	<ul> <li>When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority.</li> <li>Select Critic al to give the highest PD priority on the port.</li> <li>Select High to set the Switch to assign the remaining power to the port after all critical priority ports are served.</li> <li>Select Low to set the Switch to assign the remaining power to the port after all critical and high priority ports are served.</li> </ul>

Table 2E	Basic Setting >	DoESatura	(continued)
Tuble 33	Dasic semina ≥	FOE SEIUD	iconiinueai

IABEL	DESC RIPTIO N
Power-Up	Set how the Switch provides power to a connected PD at power-up.
	802.3af – the Switch follows the IEEE 802.3af Power over Ethernet standard to supply power to the connected PDs during power-up.
	$\mathbf{Legacy}$ – the Switch can provide power to the connected PDs that require high inrush currents at power-up. Inrush current is the maximum, instantaneous input current drawn by the PD when first turned on.
	<b>Pre</b> - <b>802.3a t</b> – the Switch initially offers power on the port according to the IEEE 802.3af standard, and then switches to support the IEEE 802.3at standard within 75 milliseconds after a PD is connected to the port. Select this option if the Switch is performing 2-event Layer-1 classification (PoE+ hardware classification) or the connected PD is NOT performing Layer 2 power classification using Link Layer Discovery Protocol (LLDP).
	802.3at – the Switch supports the IEEE 802.3at High Power over Ethernet standard and can supply power of up to 30W per Ethernet port. IEEE 802.3at is also known as PoE+ or PoE Plus. An IEEE 802.3at compatible device is referred to as Type 2. Power Class 4 (High Power) can only be used by Type 2 devices. If the connected PD requires a Class 4 current when it is turned on, it will be powered up in this mode.
	For $e-802.3at - the Switch offers power of up to 33 W on the port without performing PoE hardware classification. Select this option if the connected PD does not comply with any PoE standard and requests power higher than a standard power limit.$
	$P_{Re}$ - 802.3bt – the Switch offers power on the port according to the IEEE 802.3bt standard. Select this option if the connected PD was developed before the IEEE 802.3bt standard is implemented but requires power between 33 W and 60 W.
	802.3bt – the Switch supports the IEEE 802.3bt standard and can supply power of up to 60 W per Ethernet port to the connected PDs at power-up.
Max Power (mW)	Specify the maximum amount of power the PD could use from the Switch on this port. If you leave this field blank, the Switch refers to the standard or default maximum power for each class.
	Note: The setting you enter here will NOT take effect when the power-up mode is set to <b>802.3b t</b> .
Wide Range	Select this to let the Switch have a wider detection range for the PD.
Detection	The Switch detects whether a connected device is a powered device or not before supplying power to the port. For the PD detection, the Switch applies a fixed voltage to the device and then receives returned current. If the returned current is within the IEEE 802.3AF/AT standard range, the device will be considered as a valid PD by the Switch.
	However, in real cases, environmental interferences might easily cause the returned current to be out of the standard range.
LLDP Power Via MDI	Select this to have the Switch negotiate PoE power with the PD connected to the port by transmitting LLDP Power Via MDI TLV frames. This helps the Switch allocate less power to the PD on this port. The connected PD must be able to request PoE power through LLDP.
	The Power Via MDI TLV allows PoE devices to advertise and discover the MDI power support capabilities of the sending port on the remote device.
	Port Class
	MDI Supported
	MDI Enabled     Reir Centrellable
	Pair Controllable
	PSE Power Pairs

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 35 Basic Setting > PoE Setup (continued)

# 8.9 Interface Setup

An IPv6 address is configured on a per-interface basis. The interface can be a physical interface (for example, an Ethernet port) or a virtual interface (for example, a VLAN). The Switch supports the VLAN interface type for IPv6 at the time of writing.

Use this screen to set IPv6 interfaces on which you can configure an IPv6 address to access and manage the Switch. Click **Basic Setting** > Interface Setup in the navigation panel to display the configuration screen.

-	ur trhu			
he other only	ų 11	VLAN #		
In other 0	1			
		Ac.4 Cancel		
Incles	Interlace Type	interface ID	interior e	
		Addition of the second		

Figure 82 Basic Setting > Interface Setup

IABEL	DESC RIPTIO N	
Interface Type	Select the type of IPv6 interface for which you want to configure. The Switch supports the VLAN interface type for IPv6 at the time of writing.	
Interface ID	Specify a unique identification number (from 1 to 4094) for the interface.	
	To have IPv6 function properly, you should configure a static VLAN with the same ID number in the <b>Advanced Application &gt; VIAN</b> screens.	
Add	Click this to create a new entry.	
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click <b>Cancel</b> to reset the fields to your previous configuration.	
Index	This field displays the index number of an entry.	
Interface Type	This field displays the type of interface.	
Interface ID	This field displays the identification number of the interface.	

IABEL	DESC RIPTIO N
Interface	This field displays the interface's descriptive name which is generated automatically by the Switch. The name is from a combination of the interface type and ID number.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>De le te</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

Table 36 Basic Setting > Interface Setup (continued)

# 8.10 IPv6

Use this screen to view the IPv6 interface status and configure Switch's management IPv6 addresses.

#### 8.10.1 IPv6 Status

Click Basic Setting > IPv6 in the navigation panel to display the IPv6 status screen as shown next.

Figure 83 Basic Setting > IPv6

Divid their in			<b>Bull Country on text</b>
Person Name Inco		Denne a	
i Nod To Ho m dett	rintea		A.C. 144

The following table describes the labels in this screen.

#### Table 37 Basic Setting > IPv6

IABEL	DESC RIPTIO N	
IPv6 Status		
Domain Name Server	This field displays the IP address of the DNS server.	
Source	This field displays whether the DNS server address is configured manually (Static) or obtained automatically using DHC Pv6.	
IPv6 Table		
Index	This field displays the index number of an IPv6 interface. Click on an index number to view more interface details.	
Interface	This is the name of the IPv6 interface you created.	
Active	This field displays whether the IPv6 interface is activated or not.	

#### 8.10.2 IPv6 Interface Status

Use this screen to view a specific IPv6 interface status and detailed information. Click an interface index number in the **Basic Setting** > **IPv6** screen. The following screen opens.

if viciniariase i	Statu.			Eve Status
Interface: VLAN100		_		
I'v/ active		decele		
800 Aven				
KWA VS KORE DAT BLOK				
Kuning Date Init Inc.	niervol			
$\Delta h$ distance $\Delta h$ have $\Delta h$ in	only in the			
Unklosed Aderess				
Globel Unicast Address	(MC)			
Treast Comp. Address	(rs)			
ND DAD Active				
Number of DAD Alterno	<b>2</b> 7			
NA bit was the design of the	1			
ND Receives The int	Decement			
1.00 Post fact for loss			Ku	
	IA Type			
	WD D			
	12			
leanily /axe afon	Sink			
	SI 6			
	Adviness	_		
	Treferred Cl With Libbo			
645				
Dom of r DH				
Resteri Di K156 Citerri			Cickline	
NO VERSION SINT			1.52011434	

Figure 84 Basic Setting > IPv6 > IPv6 Interface Status

The following table describes the labels in this screen.

Table 38	Basic Setting > IPv6 > IPv6 Interface Status
----------	--

LABEL	DESC RIPTIO N
IPv6 Active	This field displays whether the IPv6 interface is activated or not.
MTU Size	This field displays the Maximum Transmission Unit (MTU) size for IPv6 packets on this interface.
ICMPv6 Rate Limit Bucket Size	This field displays the maximum number of ICMPv6 error messages which are allowed to transmit in a given time interval. If the bucket is full, subsequent error messages are suppressed.
ICMPv6 Rate Limit Error Interval	This field displays the time period (in milliseconds) during which ICMPv6 error messages of up to the bucket size can be transmitted. 0 means no limit.
Stateless Address Autoconfig	This field displays whether the Switch's interface can automatically generate a link-local address via stateless auto-configuration.

IABEL	DESC RIPTIO N			
Link Local Address	This field displays the Switch's link-local IP address and prefix generated by the interface. It also shows whether the IP address is preferred, which means it is a valid address and can be used as a sender or receiver address.			
Global Unicast Address(es)	This field displays the Switch's global unicast address to identify this interface.			
Joined Group Address(es)	This field displays the IPv6 multicast addresses of groups the Switch's interface joins.			
ND DAD Active	This field displays whether Neighbor Discovery (ND) Duplicate Address Detection (DAD) is enabled on the interface.			
Number of DAD Attempts	This field displays the number of consecutive neighbor solicitations the Switch sends for this interface.			
NS-Interval (millisecond)	This field displays the time interval (in milliseconds) at which neighbor solicitations are re-sent for this interface.			
ND Reachable Time (millisecond)	This field displays how long (in milliseconds) a neighbor is considered reachable for this interface.			
DHCPv6 Client Active	This field displays whether the Switch acts as a DHCPv6 client to get an IPv6 address from a DHCPv6 server.			
Identity Association	An Identity Association (IA) is a collection of addresses assigned to a DHCP client, through which the server and client can manage a set of related IP addresses. Each IA must be associated with exactly one interface.			
ІА Туре	The IA type is the type of address in the IA. Each IA holds one type of address. <b>IA_NA</b> means an identity association for non-temporary addresses and <b>IA_TA</b> is an identity association for temporary addresses.			
IAID	Each IA consists of a unique IAID and associated IP information.			
TI	This field displays the DHCPv6 T1 timer. After T1, the Switch sends the DHCPv6 server a Renew message.			
	An IA_NA option contains the T1 and T2 fields, but an IA_TA option does not. The DHCPv6 server uses T1 and T2 to control the time at which the client contacts with the server to extend the lifetimes on any addresses in the IA_NA before the lifetimes expire.			
T2	This field displays the DHCPv6 T2 timer. If the time T2 is reached and the server does not respond, the Switch sends a Rebind message to any available server.			
State	This field displays the state of the TA. It shows			
	$\mathbf{Active}$ when the Switch obtains addresses from a DHCpv6 server and the TA is created.			
	${f Re}{f ne}{f w}$ when the TA's address lifetime expires and the Switch sends out a Renew message.			
	${f Re} b {f ind}$ when the Switch does not receive a response from the original DHCPv6 server and sends out a Rebind message to another DHCPv6 server.			
SID	This field displays the DHCPv6 server's unique ID.			
Address	This field displays the Switch's global address which is assigned by the DHCPv6 server.			
Preferred Lifetime	This field displays how long (in seconds) that the global address remains preferred.			
Valid Lifetime	This field displays how long (in seconds) that the global address is valid.			
DNS	This field displays the DNS server address assigned by the DHCPv6 server.			
Domain List	This field displays the address record when the Switch queries the DNS server to resolve domain names.			
Restart DHCPv6 Client	Click <b>Click Here</b> to send a new DHCP request to the DHCPv6 server and update the IPv6 address and DNS information for this interface.			

 Table 38
 Basic Setting > IPv6 > IPv6 Interface Status (continued)

### 8.10.3 IPv6 Configuration

Use this screen to configure IPv6 settings on the Switch. Click the **IPv6 Configuration** link in the **Basic** Setting > **IPv6** screen. The following screen opens.

Figure 85 Basic Setting > IPv6 > IPv6 Configuration

<u> </u>		
Pas Conliguidad		Pao Status
Pv6C obe Solup		Cleftlere
I'w irredove letip		<u>Cishilan</u>
Pref. Achile song c	Rest free free of Articles - Archig	Child House
	Pro Clobel Aderess Scrop	Cleft.Here
I'm Neighbor Maxwery	I'm heighdor Dhoovery Setup	<u>Cishilan</u>
Pref Kingdon an Station		Child House
DHCPV/ Citer Lise op		Cleftlere

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
IPv6 Global Setup	Click the link to go to a screen where you can configure the global IPv6 settings on the Switch.
IPv6 Interface Setup	Click the link to go to a screen where you can enable an IPv6 interface on the Switch.
IPv6 Addressing	
IPv6 Link-Local Address Setup	Click the link to go to a screen where you can configure the IPv6 link-local address for an interface.
IPv6 Global Address Setup	Click the link to go to a screen where you can configure the IPv6 global address for an interface.
IPv6 Neighbor Discovery	
IPv6 Neighbor Discovery Setup	Click the link to go to a screen where you can configure the IPv6 neighbor discovery settings.
IPv6 Neighbor Setup	Click the link to go to a screen where you can create a static IPv6 neighbor entry in the Switch's IPv6 neighbor table.
DHCPv6 Client Setup	Click the link to go to a screen where you can configure the Switch DHCPv6 client settings.

Table 39 Basic Setting > IPv6 > IPv6 Configuration

### 8.10.4 IPv6 Global Setup

Use this screen to configure the global IPv6 settings. Click the link next to **IPv6 Global Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

Figure 86	Basic Setting >	IPv6 > IPv6	Configuration	> IPv6	Global Setup
ing une ou	basic coming r	11 10 1 11 10	coningeration	- 11 + 0	

I'né Ciobal Selup			Pes Configuration
The Rep Chil	64		
KIM fan Rote Limit Rucker Ste	139		
0.004-28 Andret for Percellahors of	1000	millippendb	
	Page 1	Concel Close	

LABEL	DESC RIPTIO N
IPv6 Hop Limit	Specify the maximum number of hops (from 1 to 255) in router advertisements. This is the maximum number of hops on which an IPv6 packet is allowed to transmit before it is discarded by an IPv6 router, which is similar to the TTL field in IPv4.
ICMPv6 Rate Limit Bucket Size	Specify the maximum number of ICMPv6 error messages (from 1 to 200) which are allowed to transmit in a given time interval. If the bucket is full, subsequent error messages are suppressed.
ICMPv6 Rate Limit Error Interval	Specify the time period (from 0 to 2147483647 milliseconds) during which ICMPv6 error messages of up to the bucket size can be transmitted. 0 means no limit.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.

Table 40 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Global Setup

#### 8.10.5 IPv6 Interface Setup

Use this screen to turn on or off an IPv6 interface and enable stateless auto-configuration on it. Click the link next to **IPv6 Interface Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

Figure 87 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Interface Setup

1745 Interface Setup			Pv5 Conliguration
hisros.	MAURO #		
Ar fee A deless Arter of by			
	Supp. 35	n 4 i an	
holes	Interface v	Aving	Address Active only
1	M ALLER	No	No.

Table 11	Basic Setting > IPv6 >	Pv6 Configuration >	IPv6 Interface Setup
	DUSIC SETTING / IF VO /	r ir vo Coniiguraiion /	

IABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
Active	Select this option to enable the interface.
Address Autoconfig	Select this option to allow the interface to automatically generate a link-local address via stateless auto-configuration.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
Active	This field displays whether the IPv6 interface is activated or not.
Address Autoconfig	This field displays whether stateless auto-configuration is enabled on the interface.

#### 8.10.6 IPv6 Link-Local Address Setup

A link-local address uniquely identifies a device on the local network (the LAN). It is similar to a "private IP address" in IPv4. You can have the same link-local address on multiple interfaces on a device. A link-local unicast address has a predefined prefix of fe80::/10.

Use this screen to configure the interface's link-local address and default gateway. Click the link next to **IPv6 Link-Local Address Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

Figure 88 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Link-Local Address Setup

Phi Unio-Looki	Address Setup	Pvé Coni guiol or
In vilave	MI AU 100 P	
litio locale/day		
Induct Colorway		
	Apple 0	Renoved Closer
indes interlace	If we Link-Local Addres	a If vé Detout: Soteway
V12N101		

The following table describes the labels in this screen.

Table 42	Basic Setting >	IPv6 > IPv6 Configuration >	> IPv6 Link-Local Address Setup

IABEL	DESC RIPTIO N		
Interface	Select the IPv6 interface you want to configure.		
Link-Local Address	Manually configure a static IPv6 link-local address for the interface.		
Default Gateway	Set the default gateway IPv6 address for the interface. When an interface cannot find a routing information for a frame's destination, it forwards the packet to the default gateway.		

G\$1350 Series User's Guide

Table 12	Paria Sattina	$\sim 10/2 \sim 10/2$	Configuration >	Dv/Linklagal Addr	ess Setup (continued)
	DARC SETTING	/ IF VO / IF VC	$\sim$	' IF VO LIHK-LUCUI AUUI	

LABEL	DESC RIPHO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
IPv6 Link-Local Address	This is the static IPv6 link-local address for the interface.
IPv6 Default Gateway	This is the default gateway IPv6 address for the interface.

## 8.10.7 IPv6 Global Address Setup

Use this screen to configure the interface's IPv6 global address. Click the link next to IPv6 Global Address Setup in the IPv6 Configuration screen to display the screen as shown next.

By A. Charles As Manaya Sa Jupa		Design of parallel
Variation Hanne General 1		
We can then a become a		
	Any Dece	
Erste Grobelt Address Series		
Mediate -		
Periodical Audies		L L H. AN
Ander Long B		
	and Concer Cline	
Indus Interfasio	Ped Chatest Address Photo Long In	alter 🗖
	Dente: Dente:	

The following table describes the labels in this screen.

Table 43	Basic Setting > IPv6 >	IPv6 Configuration > II	Pv6 Global Address Setup
----------	------------------------	-------------------------	--------------------------

LABEL	DESC RIPIIO N
Domain Name Server 1/2	Enter a domain name server IPv6 address in order to be able to use a domain name instead of an IP address.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the <b>Domain Name Server</b> values in this screen to their last-saved values.
Interface	Select the IPv6 interface you want to configure.

LABEL	DESC RIPTIO N
IPv6 Global Address	Manually configure a static IPv6 global address for the interface.
Prefix Length	Specify an IPv6 prefix length that specifies how many most significant bits (start from the left) in the address compose the network address.
EUI-64	Select this option to have the interface ID be generated automatically using the EUI-64 format.
Add	Click this to create a new entry.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
IPv6 Global Address/Prefix Length	This field displays the IPv6 global address and prefix length for the interface.
EUI-64	This shows whether the interface ID of the global address is generated using the EUI-64 format.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove and then click <b>De le te</b> to remove the selected entries from the summary table.
Cancel	Click Cancel to clear the check boxes.

Table 43	Basic Settina >	> IPv6 > IPv6	5 Configuration >	> IPv6 Global	Address Setup	(continued)
	basic coming -	11 10 - 11 10	coningeranori		/ (ddi 033 0010p	

## 8.10.8 IPv6 Neighbor Discovery Setup

Use this screen to configure neighbor discovery settings for each interface. Click the link next to **IPv6 NeighborDiscovery Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

Figure 90 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Neighbor Discovery Setup

Evi Heighbor D	Goovery Setup			The Configuration
Interface 240 Attacquis	VEAN RC 1			
<ul> <li>With stread</li> </ul>	1000	milluera:	rek.	
Reachable Time	30000	r alisan o	dK.	
		Connect Carrie		
indes ini	ericce 0A0	Allempts	NS Interval	Reachable Time
1 V	2010	1	10-20	X2288

Table 44 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Neighbor Disco
--

IABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
DAD Attempts	The Switch uses Duplicate Address Detection (DAD) with neighbor solicitation and advertisement messages to check whether an IPv6 address is already in use before assigning it to an interface, such as the link-local address it creates through stateless address auto-configuration.
	Specify the number of consecutive neighbor solicitations (from 0 to 600) the Switch sends for this interface. Enter 0 to turn off DAD.
NS Interval	Specify the time interval (from 1000 to 3600000 milliseconds) at which neighbor solicitations are re- sent for this interface.
Reachable Time	Specify how long (from 1000 to 3600000 milliseconds) a neighbor is considered reachable for this interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
DAD Attempts	This field displays the number of consecutive neighbor solicitations the Switch sends for this interface.
NS Interval	This field displays the time interval (in milliseconds) at which neighbor solicitations are re-sent for this interface.
Reachable Time	This field displays how long (in milliseconds) a neighbor is considered reachable for this interface.

## 8.10.9 IPv6 Neighbor Setup

Use this screen to create a static IPv6 neighbor entry in the Switch's IPv6 neighbor table to store the neighbor information permanently. Click the link next to **IPv6 Neighbor Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

Figure 91 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Neighbor Setup

i Neighbor Setup		Eve Configuration
Maria a Igra Mariado ID Neight a Addres MAR	VI AN #	
	Add Control Clear	
index interface	Neighbor Address	W5C =
	Distance Channell	

LABEL	DESC RIPTIO N
Interface Type	Select the type of IPv6 interface for which you want to configure. The Switch supports the VLAN interface type for IPv6 at the time of writing.
Interface ID	Specify a unique identification number (from 1 to 4094) for the interface.
	A static IPv6 neighbor entry displays in the <b>Management</b> > <b>Neighbor Table</b> screen only when the interface ID is also created in the <b>Basic Setup</b> > <b>Interface Setup</b> screen.
	To have IPv6 function properly, you should configure a static VLAN with the same ID number in the <b>Advanced Application &gt; VIAN</b> screens.
Neighbor Address	Specify the IPv6 address of the neighboring device which can be reached through the interface.
MAC	Specify the MAC address of the neighboring device which can be reached through the interface.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the nonvolatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
Neighbor Address	This field displays the IPv6 address of the neighboring device which can be reached through the interface.
MAC	This field displays the MAC address of the neighboring device which can be reached through the interface.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove and then click <b>Delete</b> to remove the selected entries from the summary table.
Cancel	Click Cancel to clear the check boxes.

Table 45 Basic Setting > IPv6 > IPv6 Configuration > IPv6 Neighbor Setup

## 8.10.10 DHC Pv6 C lie nt Se tup

Use this screen to configure the Switch's DHCP settings when it is acting as a DHCPv6 client. Click the link next to **DHCPv6 Client Setup** in the **IPv6 Configuration** screen to display the screen as shown next.

	<b>DBCPVS Client Se</b>					IFV& Configuration
Freitore			VI A5:100 *			
lA type Option			I IN NA I CNS Comain-Ust	Rapie Corami		
	Robus (Milianan			re conds		
locies.	and the second	id-N.5	Apply Co		Demoin-List	Womation Selfesh Minisum
1	SLAN100	H5	No	No.	No.	\$6100

#### Figure 92 Basic Setting > IPv6 > IPv6 Configuration > DHCPv6 Client Setup

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
ІА Туре	Select IA-NA to set the Switch to get a non-temporary IP address from the DHCPv6 server for this interface.
	Optionally, you can also select <b>Rapid-Commit</b> to have the Switch send its DHCPv6 Solicit message with a Rapid Commit option to obtain information from the DHCPv6 server by a rapid two- message exchange. The Switch discards any Reply messages that do not include a Rapid Commit option. The DHCPv6 server should also support the Rapid Commit option to have it work well.
Options	Select <b>DNS</b> to have the Switch obtain DNS server IPv6 addresses and/or select <b>Domain-List</b> to have the Switch obtain a list of domain names from the DHCP server.
Information Refresh Minimum	Specify the time interval (from 600 to 4294967295 seconds) at which the Switch exchanges other configuration information with a DHCPv6 server again.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.
Index	This is the interface index number. Click on an index number to change the settings.
Interface	This is the name of the IPv6 interface you created.
IA-NA	This field displays whether the Switch obtains a non-temporary IP address from the DHCPv6 server.
Rapid-Commit	This field displays whether the Switch obtains information from the DHCPv6 server by a rapid two- message exchange.
DNS	This field displays whether the Switch obtains DNS server IPv6 addresses from the DHCPv6 server.
Domain-List	This field displays whether the Switch obtains a list of domain names from the DHCP server.
Information Refresh Minimum	This field displays the time interval (in seconds) at which the Switch exchanges other configuration information with a DHCPv6 server again.

Table 46 Basic Setting > IPv6 > IPv6 Configuration > DHCPv6 Client Setup

# 8.11 Cloud Management

Note: NebulaFlex for hybrid mode and NCC registration are NOT supported at the time of writing and reserved for future use.

The Zyxel Nebula Control Center (NCC) is a cloud-based network management system that allows you to remotely manage and monitor Zyxel Nebula APs, Ethernet switches and security gateways.

The Switch is managed and provisioned automatically by the NCC (Nebula Control Center) when:

- It is connected to the Internet.
- The Nebula Control Center Discovery feature is enabled.
- It has been registered in the NCC.

This screen displays links to **Nebula Control Center Discovery** where you can have the Switch search for the NCC (Nebula Control Center) and to **Nebula Switch Registration** which has a QR code containing the Switch's serial number and MAC address for handy registration of the Switch at NCC.

Click **Basic Setting > Cloud Management** in the navigation panel to display this screen.

Figure 93 Basic Setting > Cloud Management

Cletifice
Cititize

### 8.11.1 Nebula Center Control Discovery

Click Basic Setting > Cloud Management > Nebula Control Center Discovery to display this screen.

Figure 94 Basic Setting > Cloud Management > Nebula Control Center Discovery

Methodic Condinal Condex Dear	in a start of the	Grout Management
Ac No	Z	
	Apple Centrel	

Select **Active** to turn on NCC discovery on the Switch. If the Switch has Internet access and has been registered in the NCC, it will go into cloud management mode.

In cloud management mode, then NCC will first check if the firmware on the Switch needs to be upgraded. If it does, the Switch will upgrade the firmware immediately. If the firmware does not need to be upgraded, but there is newer firmware available for the Switch, then it will be upgraded according to the firmware upgrade schedule for the Switch on the NCC. Below is the process for upgrading firmware:

- 1 Download firmware via the NCC.
- 2 Upgrade the firmware and reboot.

Note: While the Switch is rebooting, do NOT turn off the power.

Clear Active to turn off NCC discovery on the Switch. The Switch will NOT discover the NCC and remain in standalone mode.

## 8.11.2 Nebula Switch Registration

Click Basic Setting > Cloud Management > Nebula Switch Registration to display this screen.

Figure 95 Basic Setting > Cloud Management > Nebula Switch Registration



This screen has a QR code containing the Switch's serial number and MAC address for handy NCC registration of the Switch using the Nebula Mobile app. First, download the app from the Google Play store for Android devices or the App Store for iOS devices and create an organization and site.

# C HAPTER 9 VIAN

# 9.1 Overview

This chapter shows you how to configure 802.1Q tagged and port-based VLANs. The type of screen you see here depends on the **VIAN Type** you selected in the **Switch Setup** screen.

### 9.1.1 What You Can Do

- Use the VIAN screen (Section 9.2 on page 123) to view and search all VLAN groups.
- Use the VIAN Detail screen (Section 9.2.1 on page 124) to view detailed port settings and status of the VLAN group.
- Use the Static VIAN Setup screen (Section 9.4 on page 126) to configure and view 802.1Q VLAN parameters for the Switch.
- Use the **VIAN Port Setup** screen (Section 9.5 on page 127) to configure the static VLAN (IEEE 802.1Q) settings on a port.
- Use the **Voice VIAN Setup** screen (Section 9.6 on page 128) to set up VLANs that allow you to group voice traffic with defined priority and enable the Switch port to carry the voice traffic separately from data traffic to ensure the sound quality does NOT deteriorate.
- Use the **MAC Based VIAN Setup** screen (Section 9.7 on page 130) to set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. This eliminates the need to reconfigure the Switch when you change ports. The Switch will forward the packets based on the source MAC address you set up previously.
- Use the **Vendor ID Based VIAN Setup** screen (Section 9.8 on page 131) to set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. You can specify a mask for the MAC address to create a MAC address filter and enter a weight to set the VLAN rule's priority.
- Use the **Port-Based VIAN Setup** screen (Section 9.9 on page 133) to set up VLANs where the packet forwarding decision is based on the destination MAC address and its associated port.

## 9.1.2 What You Need to Know

Read this section to know more about VLAN and how to configure the screens.

#### IEEE 802.1Q Tagged VIANs

A tagged VLAN uses an explicit tag (VLAN ID) in the MAC header to identify the VLAN membership of a frame across bridges – they are not confined to the switch on which they were created. The VLANs can be created statically by hand. The VLAN ID associates a frame with a specific VLAN and provides the information that switches need to process the frame across the network. A tagged frame is 4 bytes longer than an untagged frame and contains 2 bytes of TPID (Tag Protocol Identifier, residing within the type/length field of the Ethernet frame) and 2 bytes of TCI (Tag Control Information, starts after the source address field of the Ethernet frame).

The CFI (Canonical Format Indicator) is a single-bit flag, always set to zero for Ethernet switches. If a frame received at an Ethernet port has a CFI set to 1, then that frame should not be forwarded as it is to an untagged port. The remaining twelve bits define the VLAN ID, giving a possible maximum number of 4,096 VLANs. Note that user priority and VLAN ID are independent of each other. A frame with VID (VLAN Identifier) of null (0) is called a priority frame, meaning that only the priority level is significant and the default VID of the ingress port is given as the VID of the frame. Of the 4096 possible VIDs, a VID of 0 is used to identify priority frames and value 4095 (FFF) is reserved, so the maximum possible VLAN configurations are 4,094.

TPID	User Priority	CFI	VLAN ID
2 Bytes	3 Bits	1 Bit	12 bits

#### Forwarding Tagged and Untagged Frames


Each port on the Switch is capable of passing tagged or untagged frames. To forward a frame from an 802.1Q VLAN-aware switch to an 802.1Q VLAN-unaware switch, the Switch first decides where to forward the frame and then strips off the VLAN tag. To forward a frame from an 802.1Q VLAN-unaware switch to an 802.1Q VLAN-aware switch, the Switch first decides where to forward the frame, and then inserts a VLAN tag reflecting the ingress port's default VID. The default PVID is VLAN 1 for all ports, but this can be changed.

A broadcast frame (or a multicast frame for a multicast group that is known by the system) is duplicated only on ports that are members of the VID (except the ingress port itself), thus confining the broadcast to a specific domain.

#### 9.1.2.1 Port VLAN Trunking

Enable **VIAN Tiunking** on a port to allow frames belonging to unknown VLAN groups to pass through that port. This is useful if you want to set up VLAN groups on end devices without having to configure the same VLAN groups on intermediary devices.

Refer to the following figure. Suppose you want to create VLAN groups 1 and 2 (V1 and V2) on devices A and B. Without **VIAN Tiunking**, you must configure VLAN groups 1 and 2 on all intermediary switches C, D and E; otherwise they will drop frames with unknown VLAN group tags. However, with **VIAN Tiunking** enabled on a port(s) in each intermediary switch you only need to create VLAN groups in the end devices (A and B). C, D and E automatically allow frames with VLAN group tags 1 and 2 (VLAN groups that are unknown to those switches) to pass through their VLAN trunking ports.



#### 9.1.2.2 VIAN Priority

At the time of writing, you can create static VLANs, Voice VLANs, MAC-based VLANs and Vendor IDbased VLANs on the Switch when the VLAN type is set to **802.1Q**. When a packet is received, the Switch processes the VLAN rules in sequence. The sequence (priority) of the VLANs is:

- 1 Vendor ID Based VLAN
- 2 Voice VLAN
- 3 MAC Based VLAN

If the packet matches a VLAN rule that has a higher priority, for example, an entry with weight 250 in the vendor ID to VLAN mapping table, the Switch assigns the corresponding VLAN ID to the packet and stops checking the subsequent VLAN rules.

#### 9.1.2.3 Select the VIAN Type

Select a VLAN type in the Basic Setting > Switch Setup screen.

4N Type	O sociug 10 ter based –		
WC Accleanting	Aying line	200	5000405
RT Apleg Time	Aging Tree	300	so mult
nady Cynesis Assignediad	Print by 2	7.94	
	hts: by	8 W	
	Priority2	$\sim 10^{-10}$	
	Priority:	4 😪	
	Since by Si	3 👽	
	Photo:	$1 \ge 1$	
	Priority1	11 👽	
	Principle .	2 😽	

Figure 97 Basic Setting > Switch Setup > Select VLAN Type

#### Static VIAN

Use a static VLAN to decide whether an incoming frame on a port should be

- sent to a VLAN group as normal depending on its VLAN tag.
- sent to a group whether it has a VLAN tag or not.
- blocked from a VLAN group regardless of its VLAN tag.

You can also tag all outgoing frames (that were previously untagged) from a port with the specified VID.

# 9.2 VIAN Status

Use this screen to view and search all static VLAN groups. Click Advanced Application > VIAN from the navigation panel to display the VIAN Status screen as shown next.

Figure 98	Advanced Application >	VLAN: VLAN Status
-----------	------------------------	-------------------

STAR 2	in the second				VI AN	Conterprete
(LAN Source)	lby VID			touch		
e Number of Index	NID NID	Name	Income and March	linion of first	Elapsed Inne	Status
Index	110	nams	Tugged Parl	Unlayged For		
				1.5	V629433	5 M N
2	123	V.A0122			6/ (20:15	Singly:

IABEL	DESC RIPTIO N			
VLAN Search by VID	Enter an existing VLAN ID numbers (separated by a comma) and click $\mathbf{Se}  \mathbf{arc}  \mathbf{h}$ to display only the specified VLANs in the list below.			
	Leave this field blank and click $\mathbf{Seach}$ to display all VLANs configured on the Switch.			
The Number of VLAN	This is the number of VLANs configured on the Switch.			
The Number of	This is the number of VLANs that match the searching criteria and display in the list below.			
Search Results	This field displays only when you use the $\mathbf{Search}$ button to look for certain VLANs.			
Index	This is the VLAN index number. Click on an index number to view more VLAN details.			
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.			
Name	This fields shows the descriptive name of the VLAN.			
Tagged Port	This field shows the tagged ports that are participating in the VLAN.			
Untagged Port	This field shows the untagged ports that are participating in the VLAN.			
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.			
Status	This field shows how this VLAN was added to the Switch.			
	Static: added as a permanent entry.			
Change Pages	Click <b>Previous</b> or <b>Next</b> to show the previous or next screen if all status information cannot be seen in one screen.			

## 9.2.1 VIAN De tails

Use this screen to view detailed port settings and status of the static VLAN group. Click on an index number in the **VIAN Status** screen to display VLAN details.

Figure 99	Advanced Application > VLAN > VLAN Detail
-----------	---

VLAN Detail					VLAN Status	
	Pro Dessen					
2.0	1.1	- 21	- A.	Hop so the s	A minst	
		A.	- 5	-		
-	<u>u</u>	11	- D -	121000	the ter	
' V V	U .	162,25592	Static			

Table 48	Advanced Application > VLAN > VLAN Detail	
----------	---	--

LABEL	DESC RIPTIO N
VLAN Status	Click this to go to the VIAN Status screen.
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.
Port Number	This column displays the ports that are participating in a VLAN. A tagged port is marked as $\mathbf{T}$ an untagged port is marked as $\mathbf{U}$ and ports not participating in a VLAN are marked as "-".
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	This field shows how this VLAN was added to the Switch.
	Static: added as a permanent entry.

# 9.3 VIAN Configuration

Use this screen to view IEEE 802.1Q VLAN parameters for the Switch. Click Advanced Application > VIAN > VIAN Configuration to see the following screen.

Figure 100 Advanced Application > VLAN > VLAN Configuration

VLUN Condugendum	stan 26
Static VIAN Setup	<u>Alizki lene</u>
VLAN Fort schop	C. Harris
Volce VLAN Selop	Clock Here
ARX: Research at AN A story of	COLOR Hanne
Veneor ID Eased VEAN Solup	Vice Here

The following table describes the labels in the above screen.

 Table 49
 Advanced Application > VLAN > VLAN Configuration

IABEL	DESC RIPHO N
Static VLAN Setup	Click Click Here to configure the Static VLAN for the Switch.
VLAN Port Setup	Click Click Here to configure the VLAN Port for the Switch.
Voice VLAN Setup	Click Click Here to configure the Voice VLAN for the Switch.
MAC Based VLAN Setup	Click Click Here to configure the MAC Based VLAN for the Switch.
Vendor ID Based VLAN Setup	Click Click Here to configure the Vendor ID Based VLAN for the Switch.

# 9.4 Configure a Static VIAN

Use this screen to configure a static VLAN for the Switch. Click the **Static VLAN Setup** link in the **VLAN Configuration** screen to display the screen as shown next.

Figure 101 Advanced Application > VLAN > VLAN Configuration > Static VLAN Setup

Static VLAN				VLAN Configurati
400070		1		
lame				
ALAN Group ID				
Port		Control		Tegging
		Normal	✓	🗹 TaTogging
1	Normal	O Red	O Forbiddon	🗹 Tx Togging
2	Normal	O Red	O Forbidden	🗹 Tx Togging
3	③ Normal	O Fixed	O Forbicklen	🗹 Ta Togging
4	Normal	O Rood	O Forbiddon	🗹 Tx Togging
5	Normal	O Red	O Forbidden	🗹 Tx Topping
6	<li>Normal</li>	O Fixed	O Forbicklen	🗹 Tx Togging
		Add Can	cel Clear	
VID	Active	ħ	lame	
1	Yes		1	
123	Yes	N	ANI 23	11
		Delete	Concel	

The following table describes the related labels in this screen.

Table 50 Advanced Application > VLAN > VLAN Configuration > Static VLAN Setup

IABEL	DESC RIPTIO N			
ACTIVE	Select this check box to activate the VLAN settings.			
Name	Enter a descriptive name for the VLAN group for identification purposes. This name consists of up to 64 printable characters. Spaces are allowed.			
VLAN Group ID	Enter the VLAN ID for this static entry; the valid range is between 1 and 4094.			
	Note: Do NOT add a VLAN ID that has been used in the <b>Voice VIAN Setup</b> .			
Port	The port number identifies the port you are configuring.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Note: Changes in this row are copied to all the ports as soon as you make them.			

IABEL	DESC RIPIIO N
Control	Select <b>Nomal</b> for the port to dynamically join this VLAN group. This is the default selection.
	Select $\mathbf{Fixed}$ for the port to be a permanent member of this VLAN group.
	Select Forbidden if you want to prohibit the port from joining this VLAN group.
Tagging	Select <b>TX Tagging</b> if you want outgoing traffic to contain this VLAN tag.
	Otherwise, to ensure that VLAN-unaware devices (such as computers and hubs) can receive frames properly, clear the <b>TX Tagging</b> check box to set the Switch to remove VLAN tags before sending.
Add	Click <b>Add</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to change the fields back to their last saved values.
Clear	Click <b>Clear</b> to start configuring the screen again.
VID	This field displays the ID number of the VLAN group. Click the number to edit the VLAN settings.
Active	This field indicates whether the VLAN settings are enabled $(Yes)$ or disabled $(No)$ .
Name	This field displays the descriptive name for this VLAN group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>Delete</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

Table 50 Advanced Application > VLAN > VLAN Configuration > Static VLAN Setup (continued)

# 9.5 Configure VIAN Port Settings

Use this screen to configure the static VLAN (IEEE 802.1Q) settings on a port. Click the **VIAN Port Setup** link in the **VIAN Configuration** screen.

	VIAN And Selling			VIA	N Carelegan dem		
Port	Ingress Check	rv D	Acceptable frame type	VEAN fronting	holainn		
•			2 <b>1</b> Y				
1	_	1	AL 🖂	_	_		
×		1	71 V				
5	=	1	A V	_	_		
4		I	<b>A V</b>				
2	_	1	AL V	_	_		
6		I	AL V				
	<ul> <li>An upday of the second of the s</li></ul>						

Figure 102 Advanced Application > VLAN > VLAN Configuration > VLAN Port Setup

IABEL	DESC RIPIIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Ingress Check	If this check box is selected, the Switch discards incoming frames on a port for VLANs that do not include this port in its member set.
	Clear this check box to disable ingress filtering.
PVID	A PVID (Port VLAN ID) is a tag that adds to incoming untagged frames received on a port so that the frames are forwarded to the VLAN group that the tag defines.
	Enter a number between 1 and 4094 as the port VLAN ID.
Acceptable	Specify the type of frames allowed on a port. Choices are All, Tag Only and Untag Only.
Frame Type	Select All from the drop-down list box to accept all untagged or tagged frames on this port. This is the default setting.
	Select $\operatorname{Tag} \mathbf{Only}$ to accept only tagged frames on this port. All untagged frames will be dropped.
	Select <b>Untag Only</b> to accept only untagged frames on this port. All tagged frames will be dropped.
VLAN Trunking	Enable <b>VIAN Tiunking</b> on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the Switch.
Isolation	Select this to allows this port to communicate only with the CPU management port and the ports on which the isolation feature is NOT enabled.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 9.6 Voice VIAN

Voice VLAN is a VLAN that is specifically allocated for voice traffic. It ensures that the sound quality of an IP phone is preserved from deteriorating when the data traffic on the Switch ports is high. It groups the voice traffic with defined priority into an assigned VLAN which enables the separation of voice and data traffic coming onto the Switch port.

The Switch can determine whether a received packet is

- an untagged voice packet when the incoming port is a fixed port for voice VLAN.
- a tagged voice packet when the incoming port and VLAN tag belongs to a voice VLAN.

It then checks the source packet's MAC address against an OUI list. If a match is found, the packet is considered as a voice packet.

You can set priority level to the Voice VLAN and add MAC address of IP phones from specific manufacturers by using its ID from the Organizationally Unique Identifiers (OUI).

Click the Voice VIAN Setup link in the VIAN Configuration screen to display the configuration screen as shown.

Figure 103	Advanced Application 3	> VLAN >	VLAN Configuration >	Voice VLAN Setup
------------	------------------------	----------	----------------------	------------------

Vel Volce VLAN SI	ice VLAN Setup obsil Schoo		3	UAN Configuration
Voice VLAH History		O Diable 60   1 5 ×		
		Apply Concel Cl	nar	
Volum VIAN OF	11Selogi			
OU oddress			Ξ	
OUI monk				
Description				
		Add Conce		
Indes	OUI ed dreas	OUI mask	Description	
		Delene Cancel		

The following table describes the fields in the above screen.

LABEL	DESC RIPIIO N				
Voice VLAN Global S	Voice VLAN Global Setup				
Voice VLAN	Click the second radio button if you want to enable the Voice VLAN feature. Enter a VLAN ID number that is associated with the Voice VLAN.				
	Click the $\mathbf{Disable}$ radio button if you do not want to enable the Voice VLAN feature.				
Priority	Select the priority level of the voice traffic from 0 to 7. Default setting is 5. The higher the numeric value you assign, the higher the priority for this voice traffic.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to begin configuring this section afresh.				
Clear	Click Clear to reset the fields to default settings.				
Voice VLAN OUI Setu	qu				
OUI address	Type the IP Phone manufacturer's OUI MAC address. The first 3 byes is the manufacturer identifier, the last 3 bytes is a unique station ID.				
OUI mask	Type the mask for the specified IP Phone manufacturer's OUI MAC address to determine which bits a packet's MAC address should match.				
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bits of the matched traffic's MAC address, which can be of any hexadecimal characters. For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria.				

LABEL	DESC RIPTIO N	
Description	Type an description up to 32 characters for the Voice VLAN device. For example: Siemens.	
Add	Click <b>Add</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this section afresh.	
Index	This field displays the index number of the Voice VLAN.	
OUI address	This field displays the OUI address of the Voice VLAN.	
OUI mask	This field displays the OUI mask address of the Voice VLAN.	
Description	This field displays the description of the Voice VLAN with OUI address.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Delete	Click <b>Delete</b> to remove the selected entry from the summary table.	
Cancel	Click Cancel to clear the check boxes.	

Table 52 Advanced Application > VLAN > VLAN Configuration > Voice VLAN Setup (continued)

# 9.7 MAC Based VIAN

The MAC-based VLAN feature assigns incoming untagged packets to a VLAN and classifies the traffic based on the source MAC address of the packet. When untagged packets arrive at the Switch, the source MAC address of the packet is looked up in a MAC to VLAN mapping table. If an entry is found, the corresponding VLAN ID is assigned to the packet. The assigned VLAN ID is verified against the VLAN table. If the VLAN is valid, ingress processing on the packet continues; otherwise, the packet is dropped.

This feature allows users to change ports without having to reconfigure the VLAN. You can assign priority to the MAC-based VLAN and define a MAC to VLAN mapping table by entering a specified source MAC address in the MAC-based VLAN setup screen. You can also delete a MAC-based VLAN entry in the same screen.

Click the MAC Based VIAN Setup link in the VIAN Configuration screen to see the following screen.

Mana Pana	HIVIAN			VI AN-	Sectorportane
Nome MAC Activo MD Noty	_				
		And Const.			
Index	None	Mác áddreis	VID	Marty	
		Colors, Commu-			

Figure 104 Advanced Application > VLAN > VLAN Configuration > MAC Based VLAN Setup

The following table describes the fields in the above screen.

Tailala CO		VII AND NII AND CONSTRUCTION NAME OF A DAMAGE DAMA AND CONTRACT
10016 23	Advanced Application >	<ul> <li>VLAN &gt; VLAN Configuration &gt; MAC Based VLAN Setup</li> </ul>

IABEL	DESC RIPTIO N
Name	Type a name up to 32 alpha numeric characters for the MAC-based VLAN entry.
MAC Address	Type a MAC address that is bind to the MAC-based VLAN entry. This is the source MAC address of the data packet that is looked up when untagged packets arrive at the Switch.
VID	Type an ID (from 1 to 4094) for the VLAN that is associated with the MAC-based VLAN entry.
Priority	Type a priority $(0 - 7)$ that the Switch assigns to frames belonging to this VLAN. The higher the numeric value you assign, the higher the priority for this MAC-based VLAN entry.
Add	Click Add to save the new MAC-based VLAN entry.
Cancel	Click Cancel to clear the fields in the MAC-based VLAN entry.
Index	This field displays the index number of the MAC-based VLAN entry.
Name	This field displays the name of the MAC-based VLAN entry.
MAC Address	This field displays the source MAC address that is bind to the MAC-based VLAN entry.
VID	This field displays the VLAN ID of the MAC-based VLAN entry.
Priority	This field displays the priority level which is assigned to frames belonging to this MAC-based VLAN.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>De le te</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

# 9.8 Vendor ID Based VIAN

The Vendor ID based VLAN feature assigns incoming untagged packets to a VLAN and classifies the traffic based on the source MAC address of the packet. When untagged packets arrive at the switch, the source MAC address of the packet is looked up in a Vendor ID to VLAN mapping table. If an entry is found, the corresponding VLAN ID is assigned to the packet. The assigned VLAN ID is verified against the VLAN table. If the VLAN is valid, ingress processing on the packet continues; otherwise, the packet is dropped.

This feature allows users to change ports without having to reconfigure the VLAN. You can assign a 802.1p priority to the vendor ID based VLAN and define a vendor ID to VLAN mapping table by entering a specified source MAC address and mask in the vendor ID based VLAN setup screen. You can also delete a vendor ID based VLAN entry in the same screen.

For every vendor ID based VLAN rule you set, you can specify a weight number to define the rule's priority level. As rules are processed one after the other, stating a priority order will let you choose which rule has to be applied first and which second.

Click the Vendor ID Based VIAN Setup link in the VIAN Configuration screen to see the following screen.

Yes	der III Anstal VIAN					MAN Do	hyrandari
Name							
MAC and	ina cu	Sent207211	9200				
Mash.		111111000000	X				
2.59							
Print		0.94					
Weight		127					
		8.3	c Concel				
Index	Natoe	MAC original	<b>Akad</b> e	VIAN	Priority	Weight	П
		Dete	le Caneo				

Figure 105 Advanced Application > VLAN > VLAN Configuration > Vendor ID Based VLAN Setup

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N
Name	Type a name up to 32 alpha numeric characters for the vendor ID based VLAN entry.
MAC Address	Type a MAC address that is bind to the vendor ID-based VLAN entry. This is the source MAC address of the data packet that is looked up when untagged packets arrive at the Switch.
Mask	Type the mask for the specified source MAC address to determine which bits a packet's MAC address should match.
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bit(s) of the matched traffic's MAC address, which can be of any hexadecimal character(s). For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria.
VLAN	Type an ID (from 1 to 4094) for the VLAN that is associated with the vendor ID based VLAN entry.
Priority	Select the priority level that the Switch assigns to frames belonging to this VLAN. The higher the numeric value you assign, the higher the priority for this vendor ID based VLAN entry.
Weight	Enter a number between 0 and 255 to specify the rule's weight. This is to decide the priority in which the rule is applied. The higher the number, the higher the rule's priority.
Add	Click Add to save the new vendor ID based VLAN entry.
Cancel	Click Cancel to clear the fields in the vendor ID based VLAN entry.
Index	This field displays the index number of the vendor ID based VLAN entry.
Name	This field displays the name of the vendor ID based VLAN entry.
MAC Address	This field displays the source MAC address that is bind to the vendor ID based VLAN entry.
Mask	This field displays the mask for the source MAC address that is bind to the vendor ID based VLAN entry.
VLAN	This field displays the VLAN ID of the vendor ID based VLAN entry.
Priority	This field displays the priority level which is assigned to frames belonging to this vendor ID based VLAN.
Weight	This field displays the weight of the vendor ID based VLAN entry.

Table 54 Advanced Application > VLAN > VLAN Configuration > Vendor ID Based VLAN Setup

LABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>De le te</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

 Table 54
 Advanced Application > VLAN > VLAN Configuration > Vendor ID Based VLAN Setup

# 9.9 Port-Based VIAN Setup

Port-based VLANs are VLANs where the packet forwarding decision is based on the destination MAC address and its associated port.

Port-based VLANs require allowed outgoing ports to be defined for each port. Therefore, if you wish to allow two subscriber ports to talk to each other, for example, between conference rooms in a hotel, you must define the egress (an egress port is an outgoing port, that is, a port through which a data packet leaves) for both ports.

Port-based VLANs are specific only to the Switch on which they were created.

Note: When you activate port-based VLAN, the Switch uses a default VLAN ID of 1. You cannot change it.

Note: In screens (such as IP Setup and Filtering) that require a VID, you must enter 1 as the VID.

The port-based VLAN setup screen is shown next. The **CPU** management port forms a VLAN with all Ethernet ports.

## 9.9.1 Configure a Port-Based VIAN

Select **Port Based** as the **VIAN Type** in the **Basic Setting** > **Switch Setup** screen and then click **Advanced Applic ation** > **VIAN** from the navigation panel to display the next screen.

Figure 100	6 Ad	vance	ed Ap	plicati	on > \	/LAN:	Port B	ased '
P	d Norse	I MI AN	2a daga					
	5.0	о <u>р</u> М		A co	nnad	$\sim \sim$	-	1117
							herene	
		1	- 9	3	$-2^{-1}$	5	- A -	
	1	÷.	×* -	М	÷.	- <b>1</b>	М	1
1	1	2	2	2	М	2		- 2
	3	~	×* -	М	~		М	.i
Outgoing	4	7	7	<b>M</b>	7	7		-
	<u>:</u>	- <b>-</b> -		M	÷.	- 1	M	- 3
	÷	Υ.	¥.	М	4	¥.	M	- A -
	C19	R	$\mathbf{Z}$	2	R	2	2	$\subset V_{n}$
		1	$\sim 2$	<b>X</b> .	1	- 0		
						1	opy -	Carro

Figure 106 Advanced Application > VLAN: Port Based VLAN Setup (All Connected)

Figure 107 Advanced	Application > VLA	N: Port Based VLAN	Setup (Port Isolation)
---------------------	-------------------	--------------------	------------------------

lig ule 10	ri Sarres			•				
		ing Mar		Falis	olurior	, v	2	ap y
							Incom	ng -
		1	2 - A	5.	1200	- 5	÷	
	1	Ξ.	_					- 1
	- <u>2</u>		. <b>.</b> .					Ŷ.
	× .			M				X
Outgoing:	4	_	_		1	_		$(-\infty)^{-1}$
	÷.					×* -		
	- <b>6</b> -							÷
	CNI	4	а. С	M	<b>.</b>	×* .	М	C. N.
		1	2	2	-	5	6	
				•				
	Page y Commission							

IABEL	DESC RIPTIO N
Setting Wizard	Choose All connected or Port isolation.
	All connected means all ports can communicate with each other, that is, there are no virtual LANs. All incoming and outgoing ports are selected. This option is the most flexible but also the least secure.
	<b>Port isolation</b> means that each port can only communicate with the CPU management port and cannot communicate with each other. All incoming ports are selected while only the CPU outgoing port is selected. This option is the most limiting but also the most secure.
	After you make your selection, click <b>Apply</b> (top right of screen) to display the screens as mentioned above. You can still customize these settings by adding or deleting incoming or outgoing ports, but you must also click <b>Apply</b> at the bottom of the screen.
Incoming	These are the ingress ports; an ingress port is an incoming port, that is, a port through which a data packet enters. If you wish to allow two subscriber ports to talk to each other, you must define the ingress port for both ports. The numbers in the top row denote the incoming port for the corresponding port listed on the left (its outgoing port). <b>CPU</b> refers to the Switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the Switch cannot be managed from that port.
Outgoing	These are the egress ports; an egress port is an outgoing port, that is, a port through which a data packet leaves. If you wish to allow 2 subscriber ports to talk to each other, you must define the egress port for both ports. <b>CPU</b> refers to the Switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the Switch cannot be managed from that port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 55 Advanced Application > VLAN: Port Based VLAN Setup

# C HAPTER 10 Static MAC Forwarding

# 10.1 Overview

This chapter discusses how to configure forwarding rules based on MAC addresses of devices on your network.

Use these screens to configure static MAC address forwarding.

#### 10.1.1 What You Can Do

Use the Static MAC Forwarding screen (Section 10.2 on page 136) to assign static MAC addresses for a port.

# 10.2 Configure Static MAC Forwarding

A static MAC address is an address that has been manually entered in the MAC address table. Static MAC addresses do not age out. When you set up static MAC address rules, you are setting static MAC addresses for a port. This may reduce the need for broadcasting.

Click Advanced Application > Static MAC Forwarding in the navigation panel to display the configuration screen as shown.

Signic MAC Forward	ing			
Active	2			
Nome				
Mag address MD				
	ado Concel Cleo	<b>r</b>		
Index Active 1	Nome MAC Address	V D	Pat	
	Delete Concel			

Figure 108 Advanced Application > Static MAC Forwarding

GS1350 Series User's Guide

LABEL	DESC RIPTIO N
Active	Select this check box to activate your rule. You may temporarily deactivate a rule without deleting it by clearing this check box.
Name	Enter a descriptive name for identification purposes for this static MAC address forwarding rule.
MAC Address	Enter the MAC address in valid MAC address format, that is, 6 hexadecimal character pairs.
	Note: Static MAC addresses do NOT age out.
VID	Enter the VLAN identification number.
Port	Enter the port where the MAC address entered in the previous field will be automatically forwarded.
Add	Click <b>Add</b> to save your rule to the Switch's run-time memory. The Switch loses this rule if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to their last saved values.
Clear	Click <b>Clear</b> to begin configuring this screen afresh.
Index	Click an index number to modify a static MAC address rule for a port.
Active	This field displays whether this static MAC address forwarding rule is active $(Yes)$ or not $(No)$ . You may temporarily deactivate a rule without deleting it.
Name	This field displays the descriptive name for identification purposes for this static MAC address- forwarding rule.
MAC Address	This field displays the MAC address that will be forwarded and the VLAN identification number to which the MAC address belongs.
VID	This field displays the ID number of the VLAN group.
Port	This field displays the port where the MAC address shown in the next field will be forwarded.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>Delete</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

Table 56 Advanced Application > Static MAC Forwarding

# C HAPTER 11 Static Multic ast Forwarding

# 11.1 Overview

This chapter discusses how to configure forwarding rules based on multicast MAC addresses of devices on your network.

Use these screens to configure static multicast address forwarding.

## 11.1.1 What You Can Do

Use the **Static Multic ast Forwarding** screen (Section 11.2 on page 139) to configure rules to forward specific multicast frames, such as streaming or control frames, to specific port(s).

### 11.1.2 What You Need To Know

A multicast MAC address is the MAC address of a member of a multicast group. A static multicast address is a multicast MAC address that has been manually entered in the multicast table. Static multicast addresses do not age out. Static multicast forwarding allows you (the administrator) to forward multicast frames to a member without the member having to join the group first.

If a multicast group has no members, then the switch will either flood the multicast frames to all ports or drop them. Figure 109 on page 138 shows such unknown multicast frames flooded to all ports. With static multicast forwarding, you can forward these multicasts to ports within a VLAN group. Figure 110 on page 139 shows frames being forwarded to devices connected to port 3. Figure 111 on page 139 shows frames being forwarded to ports 2 and 3 within VLAN group 4.






Figure 109 No Static Multicast Forwarding









# 11.2 Configure Static Multicast Forwarding

Use this screen to configure rules to forward specific multicast frames, such as streaming or control frames, to specific ports.

Click Advanced Application > Static Multicast Forwarding to display the configuration screen as shown.

rigule 112 /	avancea /	pplication		orwaraing		
Stalic A	la lle set l'erres	ed ing				
Active		0				
Norna		_				
MAC Address						
910 1	•					
TML						
			Ked Cance Clear			
Index Ac	alay Na	us <i>I</i>	AC Address	VID	Peri	-
			Jacia Careel			

#### Figure 112 Advanced Application > Static Multicast Forwarding

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N				
Active	Select this check box to activate your rule. You may temporarily deactivate a rule without deleting it by clearing this check box.				
Name	Type a descriptive name (up to 32 printable ASCII characters) for this static multicast MAC address forwarding rule. This is for identification only.				
MAC Address	Enter a multicast MAC address which identifies the multicast group. The last binary bit of the first octet pair in a multicast MAC address must be 1. For example, the first octet pair 00000001 is 01 and 00000011 is 03 in hexadecimal, so 01:00:5e:00:00:0A and 03:00:5e:00:00:27 are valid multicas MAC addresses.				
VID	You can forward frames with matching destination MAC address to ports within a VLAN group. Enter the ID that identifies the VLAN group here. If you do NOT have a specific target VLAN, enter 1.				
Port	Enter the ports where frames with destination MAC address that matched the entry above are forwarded. You can enter multiple ports separated by (no space) comma (,) or hyphen (–). For example, enter "3–5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.				
Add	Click <b>Add</b> to save your rule to the Switch's run-time memory. The Switch loses this rule if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to reset the fields to their last saved values.				
Clear	Click <b>Clear</b> to begin configuring this screen afresh.				
Index	Click an index number to modify a static multicast MAC address rule for ports.				
Active	This field displays whether a static multicast MAC address forwarding rule is active $(Yes)$ or not $(No)$ . You may temporarily deactivate a rule without deleting it.				
Name	This field displays the descriptive name for identification purposes for a static multicast MAC address-forwarding rule.				
MAC Address	This field displays the multicast MAC address that identifies a multicast group.				
VID	This field displays the ID number of a VLAN group to which frames containing the specified multicast MAC address will be forwarded.				
Port	This field displays the ports within a identified VLAN group to which frames containing the specified multicast MAC address will be forwarded.				

 Table 57
 Advanced Application > Static Multicast Forwarding

Table 57 Advanced Application > Static Multicast Forwarding (continued)

IABEL	DESC RIPIIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>Delete</b> to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the check boxes.

# C HAPTER 12 Filtering

# 12.1 Filtering Overview

This chapter discusses MAC address port filtering.

Filtering means sifting traffic going through the Switch based on the source and/or destination MAC addresses and VLAN group (ID).

#### 12.1.1 What You Can Do

Use the Filtering screen (Section 12.2 on page 142) to create rules for traffic going through the Switch.

# 12.2 Configure a Filtering Rule

Use this screen to create rules for traffic going through the Switch. Click Advanced Application > Filtering in the navigation panel to display the screen as shown next.

ig uit 110			9		
As by		0			
With:					
Action		D. Essent see to D. Essent des actions			
2000					
ND:					
		Add Cancel	2 ear		
indes Ac	dhe Nome	MAE, Address	VIC	Action	
		Dalete Co	0/24		

Figure 113 Advanced Application > Filtering

LABEL	DESC RIPIIO N
Active	Make sure to select this check box to activate your rule. You may temporarily deactivate a rule without deleting it by de-selecting this check box.
Name	Type a descriptive name (up to 32 printable ASCII characters) for this rule. This is for identification only.
Action	Select <b>Discard source</b> to drop the frames from the source MAC address (specified in the <b>MAC</b> field). The Switch can still send frames to the MAC address.
	Select <b>Disc and destination</b> to drop the frames to the destination MAC address (specified in the <b>MAC</b> address). The Switch can still receive frames originating from the MAC address.
	Select <b>Discard source</b> and <b>Discard destination</b> to block traffic to and from the MAC address specified in the <b>MAC</b> field.
MAC	Type a MAC address in valid MAC address format, that is, six hexadecimal character pairs.
VID	Type the VLAN group identification number.
Add	Click <b>Add</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to your previous configuration.
Clear	Click Clear to clear the fields to the factory defaults.
Index	This field displays the index number of the rule. Click an index number to change the settings.
Active	This field displays $Yes$ when the rule is activated and $No$ when is it deactivated.
Name	This field displays the descriptive name for this rule. This is for identification purpose only.
MAC Address	This field displays the source or destination MAC address with the VLAN identification number to which the MAC address belongs.
VID	This field displays the VLAN group identification number.
Action	This field displays the action taken for this rule.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the rules that you want to remove and then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the selected check boxes.

Table 58 Advanced Application > Filtering

# CHAPTER 13 Spanning Tree Protocol

# 13.1 Spanning Tree Protocol Overview

The Switch supports Spanning Tree Protocol (STP) and Rapid Spanning Tree Protocol (RSTP) as defined in the following standards.

- IEEE 802.1D Spanning Tree Protocol
- IEEE 802.1w Rapid Spanning Tree Protocol

## 13.1.1 What You Can Do

- Use the Rapid Spanning Tire Protocol Status screen (Section 13.2 on page 146) to view the RSTP status.
- Use the Rapid Spanning The Protocol screen (Section 13.3 on page 147) to configure RSTP settings.

### 13.1.2 What You Need to Know

Read on for concepts on STP that can help you configure the screens in this chapter.

#### (Rapid) Spanning Tree Protocol

(R)STP detects and breaks network loops and provides backup links between switches, bridges or routers. It allows a switch to interact with other (R)STP -compliant switches in your network to ensure that only one path exists between any two stations on the network.

The Switch uses IEEE 802.1w RSTP (Rapid Spanning Tree Protocol) that allows faster convergence of the spanning tree than STP (while also being backwards compatible with STP-only aware bridges). In RSTP, topology change information is directly propagated throughout the network from the device that generates the topology change. In STP, a longer delay is required as the device that causes a topology change first notifies the root bridge that then notifies the network. Both RSTP and STP flush unwanted learned addresses from the filtering database. In RSTP, the port states are Discarding, Learning, and Forwarding.

Note: In this user's guide, "STP" refers to both STP and RSTP.

#### SIP Termino logy

The root bridge is the base of the spanning tree.

Path cost is the cost of transmitting a frame onto a LAN through that port. The recommended cost is assigned according to the speed of the link to which a port is attached. The slower the media, the

higher the cost.

	able 37 STF Fall Costs					
	LINK SPEED	RECOMMENDED VALUE	RECOMMENDED RANGE	ALLO WED RANGE		
Path Cost	4Mbps	250	100 to 1000	1 to 65535		
Path Cost	10Mbps	100	50 to 600	1 to 65535		
Path Cost	16Mbps	62	40 to 400	1 to 65535		
Path Cost	100Mbps	19	10 to 60	1 to 65535		
Path Cost	1Gbps	4	3 to 10	1 to 65535		
Path Cost	10Gbps	2	1 to 5	1 to 65535		

Table 59 STP Path Costs

On each bridge, the root port is the port through which this bridge communicates with the root. It is the port on this switch with the lowest path cost to the root (the root path cost). If there is no root port, then this switch has been accepted as the root bridge of the spanning tree network.

For each LAN segment, a designated bridge is selected. This bridge has the lowest cost to the root among the bridges connected to the LAN.

#### How STP Works

After a bridge determines the lowest cost-spanning tree with STP, it enables the root port and the ports that are the designated ports for connected LANs, and disables all other ports that participate in STP. Network packets are therefore only forwarded between enabled ports, eliminating any possible network loops.

STP-aware switches exchange Bridge Protocol Data Units (BPDUs) periodically. When the bridged LAN topology changes, a new spanning tree is constructed.

Once a stable network topology has been established, all bridges listen for Hello BPDUs (Bridge Protocol Data Units) transmitted from the root bridge. If a bridge does not get a Hello BPDU after a predefined interval (Max Age), the bridge assumes that the link to the root bridge is down. This bridge then initiates negotiations with other bridges to reconfigure the network to re-establish a valid network topology.

#### SIP Port States

STP assigns five port states to eliminate packet looping. A bridge port is not allowed to go directly from blocking state to forwarding state so as to eliminate transient loops.

PORTSTATE	DESC RIPIIO N
Disabled	STP is disabled (default).
Blocking	Only configuration and management BPDUs are received and processed.
Listening	All BPDUs are received and processed. Note: The listening state does NOT exist in RSTP.
Learning	All BPDUs are received and processed. Information frames are submitted to the learning process but not forwarded.
Forwarding	All BPDUs are received and processed. All information frames are received and forwarded.

Table 60 STP Port States

## 13.2 Rapid Spanning Tree Protocol Status

Click Advanced Application > Spanning Thee Protocol in the navigation panel to display the status screen as shown next. See Section 13.1 on page 144 for more information on RSTP.

Figure 114	Advanced	Application >	· Spanning Tree	Protocol >	Status: RSTP
riguie 114	nuvunccu	/ ppiculion /	spanning nee		510105. 1(511

	present for Probability es Profecob BSTP	a de se			
Fridge		Rest		Ceur Bridge	
Mdyc IC -		5000-001	Sct-000001	C000 0015/4500000	
lio o line	(Javond)	2		2	
ian Agel	(KOMK)	23		20	
oneorain.	g Delay (record)	15		15	
an In Br		10			
Post II:		10.3251			
republic political point to the		×			
manifesting for 12 strong st		0400 IN			
l'ert	Port State	Fort Role	Designated Eridge 10	Designated Part 10	<ul> <li>Designated Cast</li> </ul>
1	HERAMONIC INC.	Compared at	2022/01/21/21 21/2020	1007001	0
7	LINE CONTINUES	Description 1	(C-3) 2 3 8 C-3 8 C 3 1	10x 3 5 C 1	
A	DORWARD N.S.	Dedgnoted	0000-0010-2000001	0.000	<u>0</u>
4	TORWARD N.S.	Designated	0000-00125-x000001	020004	9
.5	DISCARDING	<b>Masseled</b>	1001-00100010000	00000	0
	DISCARDING	Mappled	0001-001000100001	0.000	0

Table 61 Advanced Application > Spanning Tree Protocol > Status: RSTP

IABEL	DESC RIPTIO N		
RSTP	Click <b>RSTP</b> to edit RSTP settings on the Switch.		
Bridge	<b>Root</b> refers to the base of the spanning tree (the root bridge). <b>Our Bridge</b> is this Switch. This Switch may also be the root bridge.		
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for <b>Root</b> and <b>Our Bridge</b> if the Switch is the root switch.		
Hello Time (second)	This is the time interval (in seconds) at which the root switch transmits a configuration message. The root bridge determines Hello Time, Max Age and Forwarding Delay.		
Max Age (second)	This is the maximum time (in seconds) the Switch can wait without receiving a configuration message before attempting to reconfigure.		
Forwarding Delay (second) This is the time (in seconds) the root switch will wait before changing states (the learning to forwarding). Note: The listening state does NOT exist in RSTP.			
Cost to Bridge	This is the path cost from the root port on this Switch to the root switch.		
Port ID	This is the priority and number of the port on the Switch through which this Switch must communicate with the root of the Spanning Tree.		
Topology Changed TimesThis is the number of times the spanning tree has been reconfigured.			
Time Since Last Change	This is the time since the spanning tree was last reconfigured.		

IABEL	DESC RIPTIO N				
Port	This field displays the number of the port on the Switch.				
Port State	This field displays the port state in STP.				
	<ul> <li>Disc and ing – The port does not forward/process received frames or learn MAC addresses, but still listens for BPDUs.</li> </ul>				
	<ul> <li>Leaming – The port learns MAC addresses and processes BPDUs, but does NOT forward frames yet.</li> </ul>				
	<ul> <li>Forwarding – The port is operating normally. It learns MAC addresses, processes BPDUs and forwards received frames.</li> </ul>				
Port Role	This field displays the role of the port in STP.				
	<ul> <li>Root – A forwarding port on a non-root bridge, which has the lowest path cost and is the best port from the non-root bridge to the root bridge. A root bridge does NOT have a root port.</li> </ul>				
	<ul> <li>Designated – A forwarding port on the designated bridge for each connected LAN segment. A designated bridge has the lowest path cost to the root bridge among the bridges connected to the LAN segment. All the ports on a root bridge (root switch) are designated ports.</li> </ul>				
	<ul> <li>Altemate – A blocked port, which has a best alternate path to the root bridge. This path is different from using the root port. The port moves to the forwarding state when the designated port for the LAN segment fails.</li> </ul>				
	<ul> <li>Backup – A blocked port, which has a backup/redundant path to a LAN segment where a designated port is already connected when a switch has two links to the same LAN segment.</li> </ul>				
	• <b>Disabled</b> – Not strictly part of STP. The port can be disabled manually.				
Designated Bridge ID	This field displays the identifier of the designated bridge to which this port belongs when the port is a designated port. Otherwise, it displays the identifier of the designated bridge for the LAN segment to which this port is connected.				
Designated Port ID	This field displays the priority and number of the bridge port (on the designated bridge), through which the designated bridge transmits the stored configuration messages.				
Designated Cost	This field displays the path cost to the LAN segment to which the port is connected when the port is a designated port. Otherwise, it displays the path cost to the root bridge from the designated port for the LAN segment to which this port is connected.				

Table 61         Advanced Application > Spanning Tree Protocol > Status: RSTP (continued)
---

## 13.3 Configure Rapid Spanning Tree Protocol

Use this screen to configure RSTP settings, see Section 13.1 on page 144 for more information on RSTP. Click RSTP in the Advanced Application > Spanning Thee Protocol screen.

Rapid Spann	ing Tree Protocol			Statu			
Active		7					
Bridge Priority		32/68	32/68 🗸				
Hello lime		2 Se	2 Seconds				
MAX Age 20 Seconds							
Forwarding Delay		15 Sc	15 Seconds				
Port	Active	Edge	Priority	Path Cost			
*	I	1					
1	L	L	128	4			
2	Г	Г	128	4			
3	I		128	4			
4	L	L	128	4			
5	Г	Г	128	4			
6	I	I	128	4			
				1			
			-				
	- A	opty Cando					

Figure 115 Advanced Application > Spanning Tree Protocol > RSTP

Table 62 Advanced Application > Spanning Tree Protocol > RSTP

IABEL	DESC RIPTIO N
Status	Click Status to display the RSIP Status screen (see Figure 114 on page 146).
Active	Select this check box to activate RSTP. Clear this check box to disable RSTP.
Bridge Priority	Bridge priority is used in determining the root switch, root port and designated port. The Switch with the highest priority (lowest numeric value) becomes the STP root switch. If all Switches have the same priority, the Switch with the lowest MAC address will then become the root switch. Select a value from the drop-down list box.
	The lower the numeric value you assign, the higher the priority for this bridge.
	Bridge Priority determines the root bridge, which in turn determines Hello Time, Max Age and Forwarding Delay.
Hello Time	This is the time interval in seconds between BPDU (Bridge Protocol Data Units) configuration message generations by the root switch. The allowed range is 1 to 10 seconds.
Max Age	This is the maximum time (in seconds) the Switch can wait without receiving a BPDU before attempting to reconfigure. All Switch ports (except for designated ports) should receive BPDUs at regular intervals. Any port that ages out STP information (provided in the last BPDU) becomes the designated port for the attached LAN. If it is a root port, a new root port is selected from among the Switch ports attached to the network. The allowed range is 6 to 40 seconds.
Forwarding Delay	This is the maximum time (in seconds) the Switch will wait before changing states. This delay is required because every Switch must receive information about topology changes before it starts to forward frames. In addition, each port needs time to listen for conflicting information that would make it return to a blocking state; otherwise, temporary data loops might result. The allowed range is 4 to 30 seconds. As a general rule:
	2 * (Forward Delay - 1) >= Max Age >= 2 * (Hello Time + 1)
Port	This field displays the port number.

G\$1350 Series User's Guide

Table 62 Advanced Application > Spanning Tree Protocol > RSTP (continued)

IABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to activate RSTP on this port.
Edge	Select this check box to configure a port as an edge port when it is directly attached to a computer. An edge port changes its initial STP port state from blocking state to forwarding state immediately without going through listening and learning states right after the port is configured as an edge port or when its link status changes.
	Note: An edge port becomes a non-edge port as soon as it receives a Bridge Protocol Data Unit (BPDU).
Priority	Configure the priority for each port here.
	Priority decides which port should be disabled when more than one port forms a loop in a switch. Ports with a higher priority numeric value are disabled first. The allowed range is between 0 and 255 and the default value is 128.
Path Cost	Path cost is the cost of transmitting a frame on to a LAN through that port. It is recommended to assign this value according to the speed of the bridge. The slower the media, the higher the cost - see Table 59 on page 145 for more information.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 14 Bandwidth Control

## 14.1 Bandwidth Control Overview

This chapter shows you how you can cap the maximum bandwidth using the **Bandwidth Control** screen.

Bandwidth control means defining a maximum allowable bandwidth for incoming and/or out-going traffic flows on a port.

### 14.1.1 What You Can Do

Use the **Bandwidth Control** screen (Section 14.2 on page 150) to limit the bandwidth for traffic going through the Switch.

## 14.2 Bandwidth Control Setup

Click Advanced Application > Bandwidth Control in the navigation panel to bring up the screen as shown next.

gure 116	Advanced P	pplication		an Coniroi		
in ris	and the Charachand					
Achy			Ξ			
Fort	Active	Ingrees	Role	Active	Egreen	Role
1	=		ktope	=		kinge
I.		64	Nope		64	Nope
9	_	14	H g s	_	is	H ps
7		8 <b>4</b>	Nope		64	Nope
100		14	H ges		is	H (rs
>	-	68	kbye	-	63	kinge:
A.		14	H gas		14	H grs
			Apple Cone	м		

Figure 116 Advanced Application > Bandwidth Control

IABEL	DESC RIPTIO N	
Active	Select this check box to enable bandwidth control on the Switch.	
Port	This field displays the port number.	
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.	
Active	Select this check box to activate ingress rate limits on this port.	
Ingress Rate	Specify the maximum bandwidth allowed in kilobits per second (Kbps) for the incoming traffic flow on a port.	
	Note: Ingress rate bandwidth control applies to layer 2 traffic only.	
Active	Select this check box to activate egress rate limits on this port.	
Egress Rate	Specify the maximum bandwidth allowed in kilobits per second (Kbps) for the out-going traffic flow on a port.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to reset the fields.	

 Table 63
 Advanced Application > Bandwidth Control

# CHAPTER 15 Broadcast Storm Control

## 15.1 Broadcast Storm Control Overview

This chapter introduces and shows you how to configure the broadcast storm control feature.

Broadcast storm control limits the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports. When the maximum number of allowable broadcast, multicast and/or DLF packets is reached per second, the subsequent packets are discarded. Enable this feature to reduce broadcast, multicast and/or DLF packets in your network. You can specify limits for each packet type on each port.

### 15.1.1 What You Can Do

Use the **Broadcast Stom Control** screen (Section 15.2 on page 152) to limit the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports.

## 15.2 Broadcast Storm Control Setup

Click Advanced Application > Broadcast Storm Control in the navigation panel to display the screen as shown next.

\$1111A	ns Phoen Conclud		
Active			
Fol	Broadcast (pkt/s)	Mollicust (philo)	BUF (pkLA)
			=
1	0	11 3	6
2	11	11 5	0
8	0	11 3	6
±	11	11.0	0
6	0	11.5	0
		poly Centred	
		tear and	

Figure 117 Advanced Application > Broadcast Storm Control

IABEL	DESC RIPTIO N
Active	Select this check box to enable traffic storm control on the Switch. Clear this check box to disable this feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Broadcast (pkt/s)	Select this option and specify how many broadcast packets the port receives per second.
Multicast (pkt/s)	Select this option and specify how many multicast packets the port receives per second.
DLF (pkt/s)	Select this option and specify how many destination lookup failure (DLF) packets the port receives per second.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

Table 64 Advanced Application > Broadcast Storm Control

# C HAPTER 16 Mirroring

## 16.1 Minoring Overview

This chapter discusses port mirroring setup screens.

Port mirroring allows you to copy a traffic flow to a monitor port (the port you copy the traffic to) in order that you can examine the traffic from the monitor port without interference.

### 16.1.1 What You Can Do

Use the **Minoring** screen (Section 16.2 on page 154) to select a monitor port and specify the traffic flow to be copied to the monitor port.

## 16.2 Port Mirroring Setup

Click **Advanced Application** > **Minoring** in the navigation panel to display the **Minoring** screen. Use this screen to select a monitor port and specify the traffic flow to be copied to the monitor port.

igune 118 Auvunceu /		
Maroning		
Active	11	
Monitor Port		
Fart	Winored	Direction
•		ingnoss se
I		ing new M
2	-	ing www. Ma
1		ingress M
A		ingnoss sz
5	_	ing next M
5	_	ingree M
	Apply Connect	

Figure 118 Advanced Application > Mirroring

IABEL	DESC RIPTIO N
Active	Select this check box to activate port mirroring on the Switch. Clear this check box to disable the feature.
Monitor Port	The monitor port is the port you copy the traffic to in order to examine it in more detail without interfering with the traffic flow on the original ports. Enter the port number of the monitor port.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Mirrored	Select this option to mirror the traffic on a port.
Direction	Specify the direction of the traffic to mirror by selecting from the drop-down list box. Choices are <b>Egress</b> (outgoing), <b>Ingress</b> (incoming) and <b>Both</b> .
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

Table 65 Advanced Application > Mirroring

# C HAPTER 17 Link Aggregation

## 17.1 Link Aggregation Overview

This chapter shows you how to logically aggregate physical links to form one logical, higher-bandwidth link.

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

The beginning port of each trunk group must be physically connected to form a trunk group.

### 17.1.1 What You Can Do

- Use the **Link Aggregation Status** screen (Section 17.2 on page 157) to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.
- Use the Link Aggregation Setting screen (Section 17.3 on page 158) to configure static link aggregation.
- Use the **Link Aggregation Control Protocol** screen (Section 17.3.1 on page 160) to enable Link Aggregation Control Protocol (LACP).

### 17.1.2 What You Need to Know

The Switch supports both static and dynamic link aggregation.

Note: In a properly planned network, it is recommended to implement static link aggregation only. This ensures increased network stability and control over the trunk groups on your Switch.

See Section 17.4.1 on page 161 for a static port trunking example.

#### Dynamic Link Aggregation

The Switch adheres to the IEEE 802.3ad standard for static and dynamic (LACP) port trunking.

The IEEE 802.3ad standard describes the Link Aggregation Control Protocol (LACP) for dynamically creating and managing trunk groups.

When you enable LACP link aggregation on a port, the port can automatically negotiate with the ports at the remote end of a link to establish trunk groups. LACP also allows port redundancy, that is, if an

operational port fails, then one of the "standby" ports become operational without user intervention. Please note that:

- You must connect all ports point-to-point to the same Ethernet switch and configure the ports for LACP trunking.
- LACP only works on full-duplex links.
- All ports in the same trunk group must have the same media type, speed, duplex mode and flow control settings.

Configure trunk groups or LACP before you connect the Ethernet switch to avoid causing network topology loops.

#### Link Aggregation ID

LACP aggregation ID consists of the following information<sup>1</sup>:

Table 66 Link Aggregation ID: Local Switch

SYSTEM PRIO RITY	MAC ADDRESS	KEY	PO RT PRIO RITY	PORTNUMBER
0000	00-00-00-00-00	0000	00	0000

 Table 67
 Link Aggregation ID: Peer Switch

SYSTEM PRIORITY	MAC ADDRESS	KEY	PO RT PRIO RITY	PORTNUMBER
0000	00-00-00-00-00	0000	00	0000

## 17.2 Link Aggregation Status

Click Advanced Application > Link Aggregation in the navigation panel. The Link Aggregation Status screen displays by default. See Section 17.1 on page 156 for more information.

Figure 119 Advanced Application > Link Aggregation Status

Group ID	Enabled Ports	Synchronized Parts	Aggregator D	Criteria	Shiftle
<b>1</b>	•	-	-	and defined a	
12		-		anovdisternes a	
10		-		and demonstra	-

<sup>1.</sup> Port Priority and Port Number are 0 as it is the aggregator ID for the trunk group, not the individual port.

LABEL	DESC RIPTIO N	
Group ID	This field displays the group ID to identify a trunk group, that is, one logical link containing multiple ports.	
Enabled Ports	These are the ports you have configured in the Link Aggregation screen to be in the trunk group	
	The port numbers displays only when this trunk group is activated and there is a port belonging to this group.	
Synchronized Ports	These are the ports that are currently transmitting data as one logical link in this trunk group.	
Aggregator ID	Link Aggregator ID consists of the following: system priority, MAC address, key, port priority and port number. Refer to Link Aggregation ID on page 157 for more information on this field.	
	The ID displays only when there is a port belonging to this trunk group and LACP is also enabled for this group.	
Criteria	This shows the outgoing traffic distribution algorithm used in this trunk group. Packets from the same source and/or to the same destination are sent over the same link within the trunk.	
	$\operatorname{src}$ - $\operatorname{mac}$ means the Switch distributes traffic based on the packet's source MAC address.	
	dst mac means the Switch distributes traffic based on the packet's destination MAC address.	
	src-dst-mac means the Switch distributes traffic based on a combination of the packet's source and destination MAC addresses.	
	$\mathbf{src}$ - $\mathbf{ip}$ means the Switch distributes traffic based on the packet's source IP address.	
	dst-ip means the Switch distributes traffic based on the packet's destination IP address.	
	src - dst-ip means the Switch distributes traffic based on a combination of the packet's source and destination IP addresses.	
Status	This field displays how these ports were added to the trunk group. It displays:	
	<ul> <li>Static - if the ports are configured as static members of a trunk group.</li> <li>IACP - if the ports are configured to join a trunk group via LACP.</li> </ul>	

 Table 68
 Advanced Application > Link Aggregation Status

## 17.3 Link Aggregation Setting

Click Advanced Application > Link Aggregation > Link Aggregation Setting to display the screen shown next. See Section 17.1 on page 156 for more information on link aggregation.

Unk Aggregation Setting		Status LACP
Group ID	Active	Criteria
TI		sro-dst-mac ∨
T2	Г	sro-dst-maio 🛩
TO		sro-dst-maio 🛩
Port		Group
1		None 🗸
2		None 🛩
3		None 🛩
4		None 🛩
5		None 🐱
		None: 🗸
	Apply Concel	
	Opply Concer	

#### Figure 120 Advanced Application > Link Aggregation > Link Aggregation Setting

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N	
Link Aggregation Setting	This is the only screen you need to configure to enable static link aggregation.	
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.	
Active	Select this option to activate a trunk group.	
Criteria	Select the outgoing traffic distribution type. Packets from the same source and/or to the same destination are sent over the same link within the trunk. By default, the Switch uses the sre-dst-mac distribution type. If the Switch is behind a router, the packet's destination or source MAC address will be changed. In this case, set the Switch to distribute traffic based on its IP address to make sure port trunking can work properly.	
	Select $\mathbf{src} \cdot \mathbf{mac}$ to distribute traffic based on the packet's source MAC address.	
	Select $dst-mac$ to distribute traffic based on the packet's destination MAC address.	
	Select <b>sre-dst-mac</b> to distribute traffic based on a combination of the packet's source and destination MAC addresses.	
	Select $\mathbf{src}$ - $\mathbf{ip}$ to distribute traffic based on the packet's source IP address.	
	Select $\mathbf{dst}$ -ip to distribute traffic based on the packet's destination IP address.	
	Select $sre \cdot dst \cdot ip$ to distribute traffic based on a combination of the packet's source and destination IP addresses.	
Port	This field displays the port number.	
Group	Select the trunk group to which a port belongs.	
	Note: When you enable the port security feature on the Switch and configure port security settings for a port, you cannot include the port in an active trunk group.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

Table 69 Advanced Application > Link Aggregation > Link Aggregation Setting

GS1350 Series User's Guide

### 17.3.1 Link Aggregation Control Protocol

Click Advanced Application > Link Aggregation > Link Aggregation Setting > LACP to display the screen shown next. See Dynamic Link Aggregation on page 156 for more information on dynamic link aggregation.

Figure 121 Advanced Application > Link Aggregation > Link Aggregation Setting > LACP

Link Apgregation Contro		Unk Aggregation Setting
822-8	11	
2ystem Priotity	85536	
,		
Group 10		LACP Active
1		
10		
L4		
Fat		LACP Resoul
		20 M second
;		DO WE see much
9		(80 Millionation)
1		20 Millionada
А		NO M SCOMMA
5		100 Million and
5		20 M Manager
	$\Delta \rho(k) = O(n-1)$	

IABEL	DESC RIPTIO N
Link Aggregation Control Protocol	Note: Do NOT configure this screen unless you want to enable dynamic link aggregation.
Active	Select this check box to enable Link Aggregation Control Protocol (LACP).
System Priority	LACP system priority is a number between 1 and 65535. The switch with the lowest system priority (and lowest port number if system priority is the same) becomes the LACP "server". The LACP "server" controls the operation of LACP setup. Enter a number to set the priority of an active port using Link Aggregation Control Protocol (LACP). The smaller the number, the higher the priority level.
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.
LACP Active	Select this option to enable LACP for a trunk.
Port	This field displays the port number.

LABEL	DESC RIPIIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
LACP Timeout	Timeout is the time interval between the individual port exchanges of LACP packets in order to check that the peer port in the trunk group is still up. If a port does not respond after three tries, then it is deemed to be "down" and is removed from the trunk. Set a short timeout (one second) for busy trunked links to ensure that disabled ports are removed from the trunk group as soon as possible.
	Select either 1 second or 30 seconds.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 70 Advanced Application > Link Aggregation > Link Aggregation Setting > LACP (continued)

## 17.4 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 17.4.1 Static Trunking Example

This example shows you how to create a static port trunk group for ports 2 – 5.

1 Make your physical connections - make sure that the ports that you want to belong to the trunk group are connected to the same destination. The following figure shows ports 2 – 5 on switch A connected to switch B.



Figure 122 Trunking Example – Physical Connections

2 Configure static trunking – Click Advanced Application > Link Aggregation > Link Aggregation Setting. In this screen activate trunk group TL, select the traffic distribution algorithm used by this group and select the ports that should belong to this group as shown in the figure below. Click Apply when you are done.

Link Aggregation Setting		Status LACP
Group ID	Active	Criteria
Сп	₹	sre dst mae 🗸 🔾
12		sro-dst-mae 💌
T3	_	sro-dsl-mad M
Port		Group
1		None 🗸
2		II V
- 3		TI 🗸
4		<u>11 × </u>
5		∏ ∨ /
6		None 🗸
	Apply Concel	

Figure 123 Trunking Example – Configuration Screen

Your trunk group 1 ( ${f n}$ ) configuration is now complete.

# C HAPTER 18 Port Security

This chapter shows you how to set up port security.

## 18.1 About Port Security

Port security allows only packets with dynamically learned MAC addresses and/or configured static MAC addresses to pass through a port on the Switch. The Switch can learn up to 32K MAC addresses in total with no limit on individual ports other than the sum cannot exceed 32K.

For maximum port security, enable this feature, disable MAC address learning and configure static MAC addresses for a port. It is not recommended you disable port security together with MAC address learning as this will result in many broadcasts. By default, MAC address learning is still enabled even though the port security is not activated.

## 18.2 Port Security Setup

Click Advanced Application > Port Security in the navigation panel to display the screen as shown.

ing une 124	/ aran	cea / pplicalit	
	i kao miliye		
AVC hannes			
President.			[3] C.M. Annual
And Secondly			
Asian			
ret	AC BOR	existent usaning	dimited number of bearved wave address
		Z	
1		Z	h.
11 N		Z	p.
×		Z	p.
1		Z	0
- A		Z	0
λ.		$\overline{Z}$	je.
		Austr	and the second s

Figure 124 Advanced Application > Port Security (Standalone Mode)

GS1350 Series User's Guide

LABEL	DESC RIPTIO N			
Port List	Enter the number of the ports (separated by a comma) on which you want to enable port security and disable MAC address learning. After you click <b>MAC freeze</b> , all previously learned MAC addresses on the specified ports will become static MAC addresses and display in the <b>Static MAC Forwarding</b> screen.			
MAC freeze	Click <b>MAC freeze</b> to have the Switch automatically select the <b>Active</b> check boxes and clear the <b>Address Learning</b> check boxes only for the ports specified in the <b>Port List</b> .			
Active	Select this option to enable port security on the Switch.			
Port	This field displays the port number.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Note: Changes in this row are copied to all the ports as soon as you make them.			
Active	Select this check box to enable the port security feature on this port. The Switch forwards packets whose MAC addresses is in the MAC address table on this port. Packets with no matching MAC addresses are dropped.			
	Clear this check box to disable the port security feature. The Switch forwards all packets on this port.			
Address Learning	MAC address learning reduces outgoing broadcast traffic. For MAC address learning to occur on a port, the port itself must be active with address learning enabled.			
Limited Number of Learned MAC Address	Use this field to limit the number of (dynamic) MAC addresses that may be learned on a port. For example, if you set this field to "5" on port 2, then only the devices with these five learned MAC addresses may access port 2 at any one time. A sixth device must wait until one of the five learned MAC addresses ages out. MAC address aging out time can be set in the <b>Switc h</b> <b>Se tup</b> screen. The valid range is from "0" to "32K". "0" means this feature is disabled.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

 Table 71
 Advanced Application > Port Security

# CHAPTER 19 Time Range

## 19.1 Time Range Overview

You can set up one-time and recurring schedules for time-oriented features, such as PoE and classifier. The UAG supports one-time and recurring schedules. One-time schedules are effective only once, while recurring schedules usually repeat. Both types of schedules are based on the current date and time in the Switch.

### 19.1.1 What You Can Do

Use the Time Range screen (Section 19.2 on page 165) to view or define a schedule on the Switch.

## 19.2 Configuring Time Range

Click Advanced Application > Time Range in the navigation panel to display the screen as shown.

line in	• P.			
Nome				
- Isone	🖉 Absolute 🔍 Pe	ited to		
Absolutie		1 × 01 × 00 × 1 1 × 01 × 00 × 1		
			te Mendey - 00 (c.0	
For the		The Wee The An area to 00	ini — Sat — Son — Weets ≥ [: 00 ×	keys 🗏 Weekend
		A 61 151	nd Chan	
Index	Nome	Гуре	Eonge	
		Dolorez	Same 1	

Figure 125 Advanced Application > Time Range

Table 72	Advanced	Application	> Time Range
TUDIE / Z	Auvunceu	Application	

IABEL	DESC RIPTIO N			
Name	Enter a descriptive name for this rule for identifying purposes.			
Туре	Select <b>Absolute</b> to create a one-time schedule. One-time schedules begin on a specific start date and time and end on a specific stop date and time. One-time schedules are useful for long holidays and vacation periods.			
	Alternatively, select <b>Periodic</b> to create a recurring schedule. Recurring schedules begin at a specific start time and end at a specific stop time on selected days of the week (Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, and Saturday). Recurring schedules are useful for defining the workday and off-work hours.			
Absolute	This section is available only when you set Type to Absolute.			
Start	Specify the year, month, day, hour and minute when the schedule begins.			
End	Specify the year, month, day, hour and minute when the schedule ends.			
Periodic	This section is available only when you set Type to Periodic.			
	Select the first option if you want to define a recurring schedule for a consecutive time period. You then select the day of the week, hour and minute when the schedule begins and ends respectively.			
	Select the second option if you want to define a recurring schedule for multiple non- consecutive time periods. You need to select each day of the week the recurring schedule is effective. You also need to specify the hour and minute when the schedule begins and ends each day. The schedule begins and ends in the same day.			
Add	Click Add to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to reset the fields to your previous configuration.			
Clear	Click Clear to clear the fields to the factory defaults.			
Index	This field displays the index number of the rule. Click an index number to change the settings.			
Name	This field displays the descriptive name for this rule. This is for identification purpose only.			
Туре	This field displays the type of the schedule.			
Range	This field displays the time period(s) to which this schedule applies.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Delete	Check the rules that you want to remove and then click the <b>Delete</b> button.			
Cancel	Click Cancel to clear the selected check boxes.			

# C HAPTER 20 Queuing Method

## 20.1 Queuing Method Overview

This chapter introduces the queuing methods supported.

Queuing is used to help solve performance degradation when there is network congestion. Use the **Queuing Method** screen to configure queuing algorithms for outgoing traffic. See also **Priority Queue Assignment** in **Switch Setup** and **802.1p Priority** in **Port Setup** for related information.

### 20.1.1 What You Can Do

Use the **Queuing Method** screen (Section 20.2 on page 168) set priorities for the queues of the Switch. This distributes bandwidth across the different traffic queues.

### 20.1.2 What You Need to Know

Queuing algorithms allow switches to maintain separate queues for packets from each individual source or flow and prevent a source from monopolizing the bandwidth.

### Stric tly Priority Queuing

Strictly Priority Queuing (SPQ) services queues based on priority only. As traffic comes into the Switch, traffic on the highest priority queue, Q7 is transmitted first. When that queue empties, traffic on the next highest-priority queue, Q6 is transmitted until Q6 empties, and then traffic is transmitted on Q5 and so on. If higher priority queues never empty, then traffic on lower priority queues never gets sent. SPQ does not automatically adapt to changing network requirements.

### Weighted Fair Queuing

Weighted Fair Queuing is used to guarantee each queue's minimum bandwidth based on its bandwidth weight (portion) (the number you configure in the Weight field) when there is traffic congestion. WFQ is activated only when a port has more traffic than it can handle. Queues with larger weights get more guaranteed bandwidth than queues with smaller weights. This queuing mechanism is highly efficient in that it divides any available bandwidth across the different traffic queues. By default, the weight for Q0 is 1, for Q1 is 2, for Q2 is 3, and so on.

### Weighted Round Robin Scheduling (WRR)

Round Robin Scheduling services queues on a rotating basis and is activated only when a port has more traffic than it can handle. A queue is a given an amount of bandwidth irrespective of the incoming traffic on that port. This queue then moves to the back of the list. The next queue is given an equal amount of bandwidth, and then moves to the end of the list; and so on, depending on the number of queues being used. This works in a looping fashion until a queue is empty.

Weighted Round Robin Scheduling (WRR) uses the same algorithm as round robin scheduling, but services queues based on their priority and queue weight (the number you configure in the queue **Weight** field) rather than a fixed amount of bandwidth. WRR is activated only when a port has more traffic than it can handle. Queues with larger weights get more service than queues with smaller weights. This queuing mechanism is highly efficient in that it divides any available bandwidth across the different traffic queues and returns to queues that have not yet emptied.

## 20.2 Configuring Queuing

Use this screen to set priorities for the queues of the Switch. This distributes bandwidth across the different traffic queues.

Click Advanced Application > Queuing Method in the navigation panel.

	Givening Wet	bod			We:	ng hi				liybrid-SPG
	Wathod	60	01	02	C13	ં લા	66	D6	67	Lowest-George
-	$   \sim    \cos \omega_{\rm e} $									None M
1	8 90 0 e-0 0 e-0	1	2	:1	4	<u>8</u>	1	2	5	Hone 🛩
2	978 क्षेत्र २ सन्द २ स्टर	1	2	<u></u>	4	<u>×</u>	<u>:</u>	<u>k</u>	<u>11</u>	Nore M
3	972 972 С өнц С өтс	1	<u>*</u>	<u>a</u>	A	5	e	7	<u>6</u>	None M
н	8 970 0 # 0 0 #33	h	•	a	а	5	ļ.	7	0	Note V
¢	8; O <b>≈ 0</b> O ett	ľ	0	a	a	5	4	7	6	Note V
÷	8.∞; 0.≈.a 0.≈	1	2	a	a	л	4	7	6	None w
					A96.7	Conte				

Figure 126 Advanced Application > Queuing Method

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Port	This label shows the port you are configuring.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

G\$1350 Series User's Guide

LABEL	DESC RIPTIO N
Method	Select <b>SPQ</b> (Strictly Priority Queuing), <b>WFQ</b> (Weighted Fair Queuing) or <b>WRR</b> (Weighted Round Robin).
	Strictly Priority Queuing services queues based on priority only. When the highest priority queue empties, traffic on the next highest-priority queue begins. Q7 has the highest priority and Q0 the lowest.
	Weighted Fair Queuing is used to guarantee each queue's minimum bandwidth based on their bandwidth portion (weight) (the number you configure in the <b>Weight</b> field). Queues with larger weights get more guaranteed bandwidth than queues with smaller weights.
	Weighted Round Robin Scheduling services queues on a rotating basis based on their queue weight (the number you configure in the queue <b>Weight</b> field). Queues with larger weights get more service than queues with smaller weights.
Weight	When you select <b>WFQ</b> or <b>WRR</b> enter the queue weight here. Bandwidth is divided across the different traffic queues according to their weights.
Hybrid-SPQ	This field is applicable only when you select <b>WFQ</b> or <b>WRR</b> .
Lowest- Queue	Select a queue (Q0 to Q7) to have the Switch use SPQ to service the subsequent queues after and including the specified queue for the port. For example, if you select Q5, the Switch services traffic on Q5, Q6 and Q7 using SPQ.
	Select <b>None</b> to always use <b>WFQ</b> or <b>WRR</b> for the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 73
 Advanced Application > Queuing Method (continued)

# C HAPTER 21 Multic a st

## 21.1 Multicast Overview

This chapter shows you how to configure various multicast features.

Traditionally, IP packets are transmitted in one of either two ways – Unicast (1 sender to 1 recipient) or Broadcast (1 sender to everybody on the network). Multicast delivers IP packets to just a group of hosts on the network.

IGMP (Internet Group Management Protocol) is a network-layer protocol used to establish membership in a multicast group – it is not used to carry user data. Refer to RFC 1112, RFC 2236 and RFC 3376 for information on IGMP versions 1, 2 and 3 respectively.

### 21.1.1 What You Can Do

- Use the **Multic a st Se tup** screen (Section 21.2 on page 171) to display the links to the configuration screens where you can configure IPv4 multicast settings.
- Use the IPv4 Multic ast Status screen (Section 21.3 on page 171) to view multicast group information.
- Use the IGMP Snooping screen (Section 21.3.1 on page 172) to enable IGMP snooping to forward group multicast traffic only to ports that are members of that group.

### 21.1.2 What You Need to Know

Read on for concepts on Multicasting that can help you configure the screens in this chapter.

### IP Multic a st Addre sse s

In IPv4, a multicast address allows a device to send packets to a specific group of hosts (multicast group) in a different subnetwork. A multicast IP address represents a traffic receiving group, not individual receiving devices. IP addresses in the Class D range (224.0.0.0 to 239.255.255.255.) are used for IP multicasting. Certain IP multicast numbers are reserved by IANA for special purposes (see the IANA website for more information).

### IG MP Snooping

A Switch can passively snoop on IGMP packets transferred between IP multicast routers/switches and IP multicast hosts to learn the IP multicast group membership. It checks IGMP packets passing through it, picks out the group registration information, and configures multicasting accordingly. IGMP snooping allows the Switch to learn multicast groups without you having to manually configure them.

The Switch forwards multicast traffic destined for multicast groups (that it has learned from IGMP

snooping or that you have manually configured) to ports that are members of that group. IGMP snooping generates no additional network traffic, allowing you to significantly reduce multicast traffic passing through your Switch.

#### IGMP Snooping and VIANs

The Switch can perform IGMP snooping on up to 16 VLANs. You can configure the Switch to automatically learn multicast group membership of any VLANs. The Switch then performs IGMP snooping on the first 16 VLANs that send IGMP packets. This is referred to as auto mode. Alternatively, you can specify the VLANs that IGMP snooping should be performed on. This is referred to as fixed mode. In fixed mode the Switch does not learn multicast group membership of any VLANs other than those explicitly added as an IGMP snooping VLAN.

## 21.2 Multic a st Se tup

Use this screen to configure IGMP for IPv4. Click Advanced Application > Multicast in the navigation panel.

Figure 127 Advanced Application > Multicast Setup

Nutlocal Setup		
Preside forest	2.52 Here	

The following table describes the labels in this screen.

 Table 74
 Advanced Application > Multicast Setup

IABEL	DESC RIPTIO N
IPv4 Multicast	Click the link to open screens where you can configure IGMP snooping for IPv4.

## 21.3 IPv4 Multic a st Sta tus

Click Advanced Application > Multicast > IPv4 Multicast to display the screen as shown. This screen shows the IPv4 multicast group information. See Section 21.1 on page 170 for more information on multicasting.

Figure 128 Advanced Application > Multicast > IPv4 Multicast

IPv4 Multicast Stat	us		Multicast Setup - IGMP Snooping
Index	VID	Port	Multicast Group

Table 75 Advanced Application > Multicast > IPv4 Multicast

IABEL	DESC RIPIIO N	
Index	This is the index number of the entry.	
VID	This field displays the multicast VLAN ID.	

Table 75 Advanced Application > Multicast > IPv4 Multicast (continued)

LABEL	DESC RIPTIO N
Port	This field displays the port number that belongs to the multicast group.
Multicast Group	This field displays IP multicast group addresses.

### 21.3.1 IGMP Snooping

Click the **IGMP Snooping** link in the **Advanced Application** > **Multicast** > **IPv4 Multicast** screen to display the screen as shown. See Section 21.1 on page 170 for more information on multicasting.

Figure 129	Advanced Application > Multicast > IPv4 Multicast > IGMP Snooping	
rigule 120	Advanced Application - Monedsi - II + Monedsi - IOMI Shooping	

IGWP Snooping		(Ref	Mullicast Status (SMR Sneeping V
	Active	E	
	Querer	L	
CMP Succepting	Report Provy	P	
	Host Timeval	260	
	to purp enjoyity	No Chango \vee	
Interview Molfic as Frances	(1) Flooding	O trop	
enserved an fideratic steep	O Providing	O Grap	
Fort .	Normai Leave	Fast Leave	IGMP Querier Mode
1	8	0	Auto v
· · · · · · · · · · · · · · · · · · ·	8	ŏ	Auto v
8	8	ŏ	Auto m
4	æ R	ŏ	Auto M
0	8	ŏ	Auto v
6	8	ŏ	Auto
	•	-	
	Apply	Conce	
	- opening		

Table 76 Advanced Application > Multicast > IPv4 Multicast > IGMP Snooping

IABEL	DESC RIPTIO N
IGMP Snooping Use these settings to configure IGMP snooping.	
Active	Select $\mathbf{Ac\ tive}$ to enable IGMP Snooping to forward group multicast traffic only to ports that are members of that group.
Querier	Select this option to allow the Switch to send IGMP General Query messages to the VLANs with the multicast hosts attached.

LABEL	DESC RIPTIO N
Report Proxy	Select this option to allow the Switch to act as the IGMP report proxy and leave proxy. It will report group changes to a connected multicast router.
	The Switch not only checks IGMP packets between multicast routers or switches and multicast hosts to learn the multicast group membership, but also replaces the source MAC address in an IGMP $v1/v2$ report with its own MAC address before forwarding to the multicast router or switch. When the Switch receives more than one IGMP $v1/v2$ join report that requests to join the same multicast group, it only sends a new join report with its MAC address. This helps reduce the number of multicast join reports passed to the multicast router or switch.
	The Switch sends a leave message with its MAC address to the multicast router or switch only when it receives the leave message from the last host in a multicast group.
Host Timeout	Specify the time (from 1 to 16711450) in seconds that elapses before the Switch removes an IGMP group membership entry if it does not receive report messages from the port.
802.1p Priority	Select a priority level $(0 - 7)$ to which the Switch changes the priority in outgoing IGMP control packets. Otherwise, select <b>No-Change</b> to not replace the priority.
Unknown Multicast Frame	Specify the action to perform when the Switch receives an unknown multicast frame. Select <b>Drop</b> to discard the frames. Select <b>Flooding</b> to send the frames to all ports.
Reserved Multicast Group	The IP address range of 224.0.0.0 to 224.0.0.255 are reserved for multicasting on the local network only. For example, 224.0.0.1 is for all hosts on a local network segment and 224.0.0.9 is used to send RIP routing information to all RIP v2 routers on the same network segment. A multicast router will not forward a packet with the destination IP address within this range to other networks. See the IANA web site for more information.
	The layer-2 multicast MAC addresses used by Cisco layer-2 protocols, 01:00:0C:CC:CC:CC and 01:00:0C:CC:CC:CD, are also included in this group.
	Specify the action to perform when the Switch receives a frame with a reserved multicast address. Select <b>Drop</b> to discard the frames. Select <b>Flooding</b> to send the frames to all ports.
Port This field displays the port number.	
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Normal Leave	In normal leave mode, when the Switch receives an IGMP leave message from a host on a port, it forwards the message to the multicast router. The multicast router then sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. The Switch forwards the query message to all hosts connected to the port and waits for IGMP reports from hosts to update the forwarding table.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.
Fast Leave	In fast leave mode, right after receiving an IGMP leave message from a host on a port, the Switch itself sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. This helps speed up the leave process.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.

Table 76	Advanced Application	> Multicast > IPv4 Multicast	IGMP Snooping (continued)

Table 76 Advanced Application > Multicast > IPv4 Multicast > IGMP Snooping (continued)

IABEL	DESC RIPTIO N	
IGMP Querier Mode	The Switch treats an IGMP query port as being connected to an IGMP multicast router (or server). The Switch forwards IGMP join or leave packets to an IGMP query port.	
	Select <b>Auto</b> to have the Switch use the port as an IGMP query port if the port receives IGMP query packets.	
Select <b>Fixed</b> to have the Switch always use the port as an IGMP query port. Select you connect an IGMP multicast server to the port.		
	Select <b>Edge</b> to stop the Switch from using the port as an IGMP query port. The Switch will not keep any record of an IGMP router being connected to this port. The Switch does not forward IGMP join or leave packets to this port.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

### 21.3.2 IGMP Snooping VIAN

Click Advanced Application > Multicast > IPv4 Multicast in the navigation panel. Click the IGMP Snooping link and then the IGMP Snooping VIAN link to display the screen as shown. See IGMP Snooping and VLANs on page 171 for more information on IGMP Snooping VLAN.

Figure 130 Advanced Application > Multicast > IPv4 Multicast > IGMP Snooping > IGMP Snooping VLAN

	IGHP Snooping VLVN		KANT Shooping
2000 B		8 s to 8 tou	
		April 6 Control	
WAN.			
Nano			
VD.			
		add Sance Clear	
Indes	: Kame	VID	
		bit to straight	

Cancel

IABEL	DESC RIPHO N
Mode	Select <b>auto</b> to have the Switch learn multicast group membership information of any VLANs automatically.
	Select $\mathbf{fixed}$ to have the Switch only learn multicast group membership information of the VLANs that you specify below.
	In either <b>auto</b> or <b>fixed</b> mode, the Switch can learn up to 16 VLANs.
	The Switch drops any IGMP control messages which do not belong to these 16 VLANs.
	You must also enable IGMP snooping in the <b>Multic ast &gt; IPv4 Multic ast &gt; IGMP Snooping</b> screet first.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.
VLAN	Use this section of the screen to add VLANs upon which the Switch is to perform IGMP snooping.
Name	Enter the descriptive name of the VLAN for identification purposes.
VID	Enter the ID of a static VLAN; the valid range is between 1 and 4094.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to your previous configuration.
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.
Index	This is the index number of the IGMP snooping VLAN entry in the table. Click on an index number to view more details or change the settings.
Name	This field displays the descriptive name for this VLAN group.
VID	This field displays the ID number of the VLAN group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove, then click the <b>Delete</b> button.

Click Cancel to clear the check boxes.

# C HAPTER 22 AAA

## 22.1 AAA Overview

This chapter describes how to configure authentication, authorization and accounting settings on the Switch.

The external servers that perform authentication, authorization and accounting functions are known as AAA servers. The Switch supports RADIUS (Remote Authentication Dial-In User Service, see RADIUS on page 177) as external authentication and authorization servers.





### 22.1.1 What You Can Do

- Use the **AAA** screen (Section 22.2 on page 177) to display the links to the screens where you can enable authentication and authorization or both of them on the Switch.
- use the **RADIUS Server Setup** screen (Section 22.3 on page 177) to configure your RADIUS server settings.
- Use the AAA Setup screen (Section 22.4 on page 179) to configure authentication, authorization and accounting settings, such as the methods used to authenticate users accessing the Switch and which database the Switch should use first.

### 22.1.2 What You Need to Know

Authentication is the process of determining who a user is and validating access to the Switch. The Switch can authenticate users who try to log in based on user accounts configured on the Switch itself. The Switch can also use an external authentication server to authenticate a large number of users.

Authorization is the process of determining what a user is allowed to do. Different user accounts may have higher or lower privilege levels associated with them. For example, user A may have the right to create new login accounts on the Switch but user B cannot. The Switch can authorize users based on user accounts configured on the Switch itself or it can use an external server to authorize a large number of users.

Accounting is the process of recording what a user is doing. The Switch can use an external server to track when users log in, log out, execute commands and so on. Accounting can also record system related actions such as boot up and shut down times of the Switch.

#### Local User Accounts

By storing user profiles locally on the Switch, your Switch is able to authenticate and authorize users without interacting with a network AAA server. However, there is a limit on the number of users you may authenticate in this way (See Section 34.4 on page 274).

#### RADIUS

RADIUS is a security protocol used to authenticate users by means of an external server instead of (or in addition to) an internal device user database that is limited to the memory capacity of the device. In essence, RADIUS authentication allows you to validate an unlimited number of users from a central location.

## 22.2 AAA Screens

The **AAA** screens allow you to enable authentication and authorization or both of them on the Switch. First, configure your authentication server settings and then set up the authentication priority, activate authorization.

Click Advanced Application > AAA in the navigation panel to display the screen as shown.

#### Figure 132 Advanced Application > AAA

AAA		
RADIUS Server Setup	Click Hore	
AAA Setup	Click Hore	

## 22.3 RADIUS Server Setup

Use this screen to configure your RADIUS server settings. See RADIUS on page 177 for more information on RADIUS servers and Section 22.5.2 on page 183 for RADIUS attributes utilized by the authentication features on the Switch. Click on the **RADIUS Server Setup** link in the **AAA** screen to view the screen as shown.

sati Authenticoti	itä Server Setup en Server					۵۵۵
Mode			index prior	ily ×		
Imeout			30			
Index	P Addres		UDP Port		Shared Secret	Delete
1	0.0000	<u>E</u>	1012			
9	0.0000		1012			=
Accounting	xorvor					
timeso)			90	seconds		
in dex:	P Addres	36	UDP Port		Shared Secret	Delete
1	0.0.0.0		1818			
2	0.0.0.0		1818			
Affricate						
TRANSIE AN	chross		0.0.0.0			
			Apoly De	neel		

Figure 133 Advanced Application > AAA > RADIUS Server Setup

Table 78	Advanced	Application > A	AAA >	RADIUS Server Setup
		,		

IABEL	DESC RIPTIO N
Authentication Server	Use this section to configure your RADIUS authentication settings.
Mode	This field is only valid if you configure multiple RADIUS servers.
	Select <b>index-priority</b> and the Switch tries to authenticate with the first configured RADIUS server, if the RADIUS server does not respond then the Switch tries to authenticate with the second RADIUS server.
	Select $\mathbf{mund}$ - $\mathbf{mbin}$ to alternate between the RADIUS servers that it sends authentication requests to.
Timeout	Specify the amount of time in seconds that the Switch waits for an authentication request response from the RADIUS server.
	If you are using <b>index-priority</b> for your authentication and you are using two RADIUS servers then the timeout value is divided between the two RADIUS servers. For example, if you set the timeout value to 30 seconds, then the Switch waits for a response from the first RADIUS server for 15 seconds and then tries the second RADIUS server.
Index	This is a read-only number representing a RADIUS server entry.
IP Address	Enter the IP address of an external RADIUS server in dotted decimal notation.
UDP Port	The default port of a RADIUS server for authentication is <b>1812</b> . You need not change this value unless your network administrator instructs you to do so.

LABEL	DESC RIPTIO N
Shared Secret	Specify a password (up to 32 alphanumeric characters) as the key to be shared between the external RADIUS server and the Switch. This key is not sent over the network. This key must be the same on the external RADIUS server and the Switch.
Delete	Check this box if you want to remove an existing RADIUS server entry from the Switch. This entry is deleted when you click <b>Apply</b> .
Accounting Server	Use this section to configure your RADIUS accounting server settings.
Timeout	Specify the amount of time in seconds that the Switch waits for an accounting request response from the RADIUS accounting server.
Index	This is a read-only number representing a RADIUS accounting server entry.
IP Address	Enter the IP address of an external RADIUS accounting server in dotted decimal notation.
UDP Port	The default port of a RADIUS accounting server for accounting is <b>1813</b> . You need not change this value unless your network administrator instructs you to do so.
Shared Secret	Specify a password (up to 32 alphanumeric characters) as the key to be shared between the external RADIUS accounting server and the Switch. This key is not sent over the network. This key must be the same on the external RADIUS accounting server and the Switch.
Delete	Check this box if you want to remove an existing RADIUS accounting server entry from the Switch. This entry is deleted when you click <b>Apply</b> .
Attribute	Use this section to define the RADIUS server attribute for its account.
NAS-IP-Address	Enter the IP address of the NAS (Network Access Server).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 78
 Advanced Application > AAA > RADIUS Server Setup (continued)

## 22.4 AAA Setup

Use this screen to configure authentication, authorization and accounting settings on the Switch. Click on the **AAA Se tup** link in the **AAA** screen to view the screen as shown.

AAA Se uthenfication	dub				AA	
Type Privilege Enoble Login		h	Nethod 1	Me	Method 2	
			lood V lood V		- *	
uthorization						
Туре		Active	Console		Method	
Exec		1	1		rodus	
update Period		0	minutes			
				Method	Privilege	
Ivne	Active	Broodcast	Mode			
Type System	Active	Broadcast	Mode			
Type System Exac	Active	Broadcast		radius radius	-	

Figure 134 Advanced Application > AAA > AAA Setup

Table 79	Advanc	ed Application > AAA > AAA Setup

IABEL	DESC RIPTIO N
Authentication	Use this section to specify the methods used to authenticate users accessing the Switch.
Privilege Enable	These fields specify which database the Switch should use (first, second and third) to authenticate access privilege level for administrator accounts (users for Switch management).
	Configure the access privilege of accounts via commands (See the CLI Reference Guide) for <b>local</b> authentication. The <b>RADIUS</b> is an external server. Before you specify the priority, make sure you have set up the corresponding database correctly first.
	You can specify up to two methods for the Switch to authenticate the access privilege level of administrators. The Switch checks the methods in the order you configure them (first <b>Method 1</b> , and then <b>Method 2</b> ). You must configure the settings in the <b>Method 1</b> field. If you want the Switch to check another source for access privilege level specify it in the <b>Method 2</b> field.
	Select $\mathbf{local}$ to have the Switch check the access privilege configured for local authentication.
	Select $\mathbf{radius}$ to have the Switch check the access privilege via the external server.

IABEL	DESC RIPIIO N
Login	These fields specify which database the Switch should use (first and second) to authenticate administrator accounts (users for Switch management).
	Configure the local user accounts in the Access Control > Logins screen. The RADIUS is an external server. Before you specify the priority, make sure you have set up the corresponding database correctly first.
	You can specify up to two methods for the Switch to authenticate administrator accounts. The Switch checks the methods in the order you configure them (first <b>Method 1</b> , and then <b>Method 2</b> ). You must configure the settings in the <b>Method 1</b> field. If you want the Switch to check another source for administrator accounts, specify them in the <b>Method 2</b> field.
	Select $local$ to have the Switch check the administrator accounts configured in the Access Control > Logins screen.
	Select ${\bf m}d{\bf i}{\bf u}{\bf s}$ to have the Switch check the administrator accounts configured via your RADIUS server.
Authorization	Use this section to configure authorization settings on the Switch.
Туре	Set whether the Switch provides the following services to a user.
	• Exec: Allow an administrator which logs into the Switch through Telnet or SSH to have a different access privilege level assigned via the external server.
Active	Select this to activate authorization for a specified event types.
Console	Select this to allow an administrator which logs in the Switch through the console port to have different access privilege level assigned via the external server.
Method	RADIUS is the only method for authorization of the $\mathbf{Exec}$ type of service.
Accounting	Use this section to configure accounting settings on the Switch.
Update Period	This is the amount of time in minutes before the Switch sends an update to the accounting server. This is only valid if you select the <b>start-stop</b> option for the <b>Exe c</b> entries.
Туре	The Switch supports the following types of events to be sent to the accounting servers:
	• $\mathbf{System}$ – Configure the Switch to send information when the following system events occur: system boots up, system shuts down, system accounting is enabled, system accounting is disabled.
	• Exe $c$ – Configure the Switch to send information when an administrator logs in and logs out via the console port, telnet or SSH.
Active	Select this to activate accounting for a specified event types.
Broadcast	Select this to have the Switch send accounting information to all configured accounting servers at the same time.
	If you do not select this and you have two accounting servers set up, then the Switch sends information to the first accounting server and if it does not get a response from the accounting server then it tries the second accounting server.
Mode	The Switch supports two modes of recording login events. Select:
	• <b>start-stop</b> – to have the Switch send information to the accounting server when a user begins a session, during a user's session (if it lasts past the <b>Update Period</b> ), and when a user ends a session.
	• <b>stop-only</b> – to have the Switch send information to the accounting server only when a user ends a session.
Method	RADIUS is the only method for recording $System$ or $Exec$ type of event.
Privilege	This field is not configurable for $\mathbf{System}$ and $\mathbf{Exec}$ types of events.

 Table 79
 Advanced Application > AAA > AAA Setup (continued)

IABEL	DESC RIPIIO N	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.	

 Table 79
 Advanced Application > AAA > AAA Setup (continued)

## 22.5 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 22.5.1 Vendor Specific Attribute

RFC 2865 standard specifies a method for sending vendor-specific information between a RADIUS server and a network access device (for example, the Switch). A company can create Vendor Specific Attributes (VSAs) to expand the functionality of a RADIUS server.

The Switch supports VSAs that allow you to perform the following actions based on user authentication:

- Limit bandwidth on incoming or outgoing traffic for the port the user connects to.
- Assign account privilege levels (See the CLI Reference Guide for more information on account privilege levels) for the authenticated user.

The VSAs are composed of the following:

- **Vendor ID**: An identification number assigned to the company by the IANA (Internet Assigned Numbers Authority). Zyxel's vendor ID is 890.
- Vendor Type: A vendor specified attribute, identifying the setting you want to modify.
- Vendor-data: A value you want to assign to the setting.

Note: Refer to the documentation that comes with your RADIUS server on how to configure VSAs for users authenticating via the RADIUS server.

The following table describes the VSAs supported on the Switch.

Table 80 Supported VSAs

FUNC TION	ATIRIBUIE
Ingress Bandwidth Assignment	Vendor-Id = <b>890</b> Vendor-Type = <b>1</b> Vendor-data = ingress rate (Kbps in decimal format)

Table 80 Supported VSAs (continued)

FUNC TIO N	ATIRIBUIE
Egress Bandwidth Assignment	Vendor-Id = 890 Vendor-Type = 2 Vendor-data = egress rate (Kbps in decimal format)
Privilege Assignment	<pre>Vendor-ID = 890 Vendor-Type = 3 Vendor-Data = "shell:priv-lvl=N" or Vendor-ID = 9 (CISCO)</pre>
	<ul> <li>Vendor Type = 1 (CISCO-AVPAIR)</li> <li>Vendor-Data = "shell:priv-lvl=N"</li> <li>where N is a privilege level (from 0 to 14).</li> <li>Note: If you set the privilege level of a login account differently on the RADIUS servers and the Switch, the user is assigned a privilege level from the database (RADIUS or local) the Switch uses first for user authentication.</li> </ul>

#### 22.5.1.1 Tunnel Protocol Attribute

You can configure tunnel protocol attributes on the RADIUS server (refer to your RADIUS server documentation) to assign a port on the Switch to a VLAN. The port VLAN settings are fixed and untagged. This will also set the port's VID. The following table describes the values you need to configure. Note that the bolded values in the table are fixed values as defined in RFC 3580.

Table 81 S	Supported Tunnel Protocol Attribute
------------	-------------------------------------

FUNC TIO N	ATRIBUTE
-	Tunnel-Type = VLAN(13) Tunnel-Medium-Type = 802(6) Tunnel-Private-Group-ID = VLAN ID
	Note: You must also create a VLAN with the specified VID on the Switch.

### 22.5.2 Supported RADIUS Attributes

Remote Authentication Dial-In User Service (RADIUS) attributes are data used to define specific authentication elements in a user profile, which is stored on the RADIUS server. This appendix lists the RADIUS attributes supported by the Switch.

Refer to RFC 2865 for more information about RADIUS attributes used for authentication.

This section lists the attributes used by authentication functions on the Switch. In cases where the attribute has a specific format associated with it, the format is specified.

### 22.5.3 Attributes Used for Authentication

The following sections list the attributes sent from the Switch to the RADIUS server when performing authentication.

#### 22.5.3.1 Attributes Used for Authenticating Privilege Access

User-Name

– The format of the User-Name attribute is **\$enab**#**\$**, where # is the privilege level (1 – 14). User-Password NAS-Identifier NAS-IP-Address

### 22.5.3.2 Attributes Used to Login Users

User-Name User-Password NAS-Identifier NAS-IP-Address

# C HAPTER 23 DHCP Snooping

## 23.1 Overview

With DHCP snooping, the Switch can build the binding table dynamically by snooping DHCP packets (dynamic bindings) and filter unauthorized DHCP packets in your network.

The Switch uses a binding table to distinguish between authorized and unauthorized DHCP packets in your network. A binding contains these key attributes:

- MAC address
- VLAN ID
- IP address
- Port number

When the Switch receives a DHCP packet, it looks up the appropriate MAC address, VLAN ID, IP address, and port number in the binding table. If there is a binding, the Switch forwards the packet. If there is not a binding, the Switch discards the packet.

### 23.1.1 What You Can Do

- Use the **DHCP Snooping** screen (Section 23.2 on page 185) to look at various statistics about the DHCP snooping database.
- Use this **DHCP Snooping Configure** screen (Section 23.3 on page 188) to enable DHCP snooping on the Switch (not on specific VLAN), specify the VLAN where the default DHCP server is located, and configure the DHCP snooping database.
- Use the **DHCP Snooping Port Configure** screen (Section 23.3.1 on page 190) to specify whether ports are trusted or untrusted ports for DHCP snooping.
- Use the **DHCP Snooping VIAN Configure** screen (Section 23.3.2 on page 191) to enable DHCP snooping on each VLAN and to specify whether or not the Switch adds DHCP relay agent option 82 information to DHCP requests that the Switch relays to a DHCP server for each VLAN.
- Use the **DHCP Snooping VIAN Port Configure** screen (Section 23.3.3 on page 192) to apply a different DHCP option 82 profile to certain ports in a VLAN.

# 23.2 DHCP Snooping

Use this screen to look at various statistics about the DHCP snooping database. To open this screen, click **Advanced Application** > **DHCP Snooping**.

Paper Likit     280     second P       Manufactor     280     second P       Appert second     Manufactor     second P       Debey line     Manufactor     P       Debey line     Manufactor     P       Debey line     P     P       Debey	DHCF Shooping Solutions - States		Configure
Control of a set	Description	Status	
Agent modes     285     second       Agent modes     None     Deleg lines wolly     None       Deleg lines wolly     None     None       Lead some control to the lines     O     None       Some control to the lines     O     None       Lead some control to the lines     O     None       Lead lines of the lines     O     None       None of the lines     O     None       Lines of the lines     O	Append 100		
Agent anolog     None       Delay finer wolty     None       Delay finer wolty     None       Led Lance and a finer     None       Lance and finer     None       Lanc	We have had a well some	200	Section 2
Decky filter wolky     Heritanning       Abort finances     Northering       Instrumentation     Northering	Almost and a	200	second.
Decky filter wolky     Heritanning       Abort finances     Northering       Instrumentation     Northering			
Attent interceptiv     Not Running       Indicate and all factor     Name       Indicate and factor     Name	Agenticipality	None	
Triel some sind at larger     None       Triel some sind at larger     None       Triel some sind     O       Very som	Deley Inter capity	Notige	
Institutions     Phone       Institution or some     Modentine constraint       Institution or some     Modentine constraint       Institution or some     0       Market Schwart Schwart     0       Vervees of namelies     0       Institution or some     0       Vervees of namelies     0       Institution or some     0       Vervees of namelies     0       Vervees of landing a counters     0       Nome     0       Vervees of landing a counters     0       Vervees of landing a counters     Nome	Maxari Innon enjalty	Notige	
Institutions     Phone       Institution or some     Modentine constraint       Institution or some     Modentine constraint       Institution or some     0       Market Schwart Schwart     0       Vervees of namelies     0       Institution or some     0       Vervees of namelies     0       Institution or some     0       Vervees of namelies     0       Vervees of landing a counters     0       Nome     0       Vervees of landing a counters     0       Vervees of landing a counters     Nome			
Institution own     Mathematication       Intro-       Table observation       Table observation       Very table observation	Last some control for or	Ohmer.	
Inno.       Table observes     0       Manual Interfaces     0	Last Labor Lance	Mana	
Total observed.     0       Vier op feilures     0       Verven of handlers     0       Talleet hendlers     0       Verven of nanclers     None       Verven of nanclers     0	Last Labor Costor	No. Indexes a conduct	
Very plating     0       Very notification     0       Faile frequency     0       Very notification     0       Very notification     0       Very notification     0       Paile frequency     Nome       Colorbone detail     Shrine       Paile frequency     Nome       Loof ignored bindings counteers     0       Pare for use     0       Prive for use		lines	
Ververa of inanciers 0 Tailee Frenciers 0 Ververa of reacts Ververa of reacts Frainman 1 Seconds of seconds Frainman 1 Seconds Frainman 1 Seconds of	To lo lo therapity	0	
Following0Accords of reads0Parlia from 10Parlia from 20Parlia from 20Parlia from 30Parlia from 3	Vier op lefteres	0	
Success directed     0       Endormonic     0       Success directed     0       Endormonic     Stocker       Endormonic     Nome       Least ignormonic bindings counters     Nome       Endormonic bindings counters     0       Endormonic bindings counters     Nome       Endormonic bindings counters     0       Endormonic bindings counters <t< td=""><td>Servers of hendlers</td><td>0</td><td></td></t<>	Servers of hendlers	0	
Parket music     0       Parket with with with with with with with wit	Falled handlard	0	
Zenomes also ins     0       Failed work is     0       Colobane detail     0       Description     Atrine       Failed work is converted acconverted acc	Secreta directo	0	
Protection     0       Detected in     State       Detected in sector     None       Fei sectorie distring a counters     None       Leaf ignored bindings counters     0       None is investigations     0       Parke is investigatis <td>Folia from 1.</td> <td></td> <td></td>	Folia from 1.		
Existence detail     Status       Description     Status       Period bindings counters     None       Leaf ignored bindings counters     0       Invest dinterioses     0       Parke is use     0       Parke is use     0       Parke is use     0       Unsupported state     0       Leaf ignored bindings counters     0       Parke is use     0       Descriptions     0       Leaf ignored bindings counters     0	Summary of waters		
Description     Atme       For successful access     None       Left ignored bindings counters     0       East reproduces     0       Parse is user     0	Failer (well as	11	
Description     Atme       For successful access     None       Left ignored bindings counters     0       East reproduces     0       Parse is user     0			
DescriptionAtmeFor successful sectoryNoneLeaf ignored bindings countersFor ignored bindings countersFor ignored bindings countersFor ignored bindings countersParse is userOParse is userOParse is userOParse is userOLeaf ignored bindings countersUser ignored bindings countersFor ignored bindings countersRead ignored bindings countersRead ignored bindings countersParse ignored bindings countersParse ignored bindings countersParse ignored bindingsOParse ignored bindingsParse ignored bindingsPa			
Heisbedeeteelui sedetee     None       Lest Ignoned bindings counters     8       Investellings doubles     8       Investellings doubles     9       Investellings doubles     9       Perseleitures     9       Investellings doubles     9       Perseleitures     9       Unsteppende vans     9       Leet Ignonert bindings doubles     9       Real republicans     9	Colobare detail		
Lost ignored bindings counters       Real top allows     0       Invoid interfaces     0       Porce is lows     0       Porce is lows     0       Porce is lows     0       Unsupported states     0       Unsupported states     0       Lost ignored bindings counters     0       Real top allows     0       Invoid interval into ings counters     0       Real top allows     0       Invoid interval     0       Real top allows     0       Real top allows     0       Porse in top allows     0		Alvilue.	
Number of the second		None	
Investidinteriorses 0 Porce is larger Porce is larger Porce is larger Porce is ans 0 Lost ignored bindings counters Porce it in formations 0 Investigations 0 Porce is ans 0	Lost ignored bindings counters		
Porce Iciuse:     0       Porce Iciuse:     0       Porce Iciuse:     0       Unsupported state     0       Used Ignored Intellings counters     None       Total Ignored Intellings counters     0       Intellige allowers     0	Kender profilsensy		
Figs red leases0Unsubported stans0Lost lynered timeNoneTotal lynered hindings counters0Red reg alisans0Reserved times0Parso la cos0		••	
Unsupported views     0       Last Ignored line     None       Total Ignored hindings counters     None       Reading of the last reas     0       Reading of the last reas     0       Press Immes     0			
Leef Ignored Inc. None Total Ignored Mindings counters Real Paper Bones 0 Inconductor Inc. 0 Parso Incos 0			
Total Ignored Mindings counters Next September 0 Investigations 0 Press Innex 0			
Kanal Angeladiwanov () In version fundadarianov () Prassa Internet ()		None	
have the hot mass 0. Presenter mass 0.			
Post la cost 0	Kender profilsensy	11	
	In such that has a	11	
Particular Sec. ()	Presente des	11	
	Eq. 10 the rate	11	
Una populated status in a	Unsupported states	0	

Figure 135	Advanced Application > DHCP Snooping
riguie 100	Advanced Application > Driet shooping

1 able 82	Advanced Application > DHCP Snoo	ping

LABEL	DESC RIPTIO N	
Database Status	This section displays the current settings for the DHCP snooping database. You can configure them in the <b>DHCP Snooping Configure</b> screen. See Section 23.3 on page 188.	
Agent URL	This field displays the location of the DHCP snooping database.	
Write delay timer	This field displays how long (in seconds) the Switch tries to complete a specific update in the DHCP snooping database before it gives up.	

T 111 00			/ I <sup>+</sup>
1 able 82	Advanced Application >	DHCP shooping	(continuea)

LABEL	DESC RIPTIO N
Abort timer	This field displays how long (in seconds) the Switch waits to update the DHCP snooping database after the current bindings change.
	This section displays information about the current update and the next update of the DHCP snooping database.
Agent running	This field displays the status of the current update or access of the DHCP snooping database.
	None: The Switch is not accessing the DHCP snooping database.
	${f Re}{f a}{f d}$ : The Switch is loading dynamic bindings from the DHCP snooping database.
	Write: The Switch is updating the DHCP snooping database.
Delay timer expiry	This field displays how much longer (in seconds) the Switch tries to complete the current update before it gives up. It displays <b>Not Running</b> if the Switch is not updating the DHCP snooping database right now.
Abort timer expiry	This field displays when (in seconds) the Switch is going to update the DHCP snooping database again. It displays <b>Not Running</b> if the current bindings have not changed since the last update.
	This section displays information about the last time the Switch updated the DHCP snooping database.
Last succeeded time	This field displays the last time the Switch updated the DHCP snooping database successfully.
Last failed time	This field displays the last time the Switch updated the DHCP snooping database unsuccessfully.
Last failed reason	This field displays the reason the Switch updated the DHCP snooping database unsuccessfully.
	This section displays historical information about the number of times the Switch successfully or unsuccessfully read or updated the DHCP snooping database.
Total attempts	This field displays the number of times the Switch has tried to access the DHCP snooping database for any reason.
Startup failures	This field displays the number of times the Switch could not create or read the DHCP snooping database when the Switch started up or a new URL is configured for the DHCP snooping database.
Successful transfers	This field displays the number of times the Switch read bindings from or updated the bindings in the DHCP snooping database successfully.
Failed transfers	This field displays the number of times the Switch was unable to read bindings from or update the bindings in the DHCP snooping database.
Successful reads	This field displays the number of times the Switch read bindings from the DHCP snooping database successfully.
Failed reads	This field displays the number of times the Switch was unable to read bindings from the DHCP snooping database.
Successful writes	This field displays the number of times the Switch updated the bindings in the DHCP snooping database successfully.
Failed writes	This field displays the number of times the Switch was unable to update the bindings ir the DHCP snooping database.
Database detail	
First successful access	This field displays the first time the Switch accessed the DHCP snooping database for any reason.
ast ignored bindings counters	This section displays the number of times and the reasons the Switch ignored bindings the last time it read bindings from the DHCP binding database. You can clear these counters by restarting the Switch or using CLI commands. See the CLI Reference Guide.

IABEL	DESC RIPTIO N
Binding collisions	This field displays the number of bindings the Switch ignored because the Switch already had a binding with the same MAC address and VLAN ID.
Invalid interfaces	This field displays the number of bindings the Switch ignored because the port number was a trusted interface or does not exist anymore.
Parse failures	This field displays the number of bindings the Switch ignored because the Switch was unable to understand the binding in the DHCP binding database.
Expired leases	This field displays the number of bindings the Switch ignored because the lease time had already expired.
Unsupported vlans	This field displays the number of bindings the Switch ignored because the VLAN ID does not exist anymore.
Last ignored time	This field displays the last time the Switch ignored any bindings for any reason from the DHCP binding database.
Total ignored bindings counters	This section displays the reasons the Switch has ignored bindings any time it read bindings from the DHCP binding database. You can clear these counters by restarting the Switch or using CLI commands. See the CLI Reference Guide.
Binding collisions	This field displays the number of bindings the Switch has ignored because the Switch already had a binding with the same MAC address and VLAN ID.
Invalid interfaces	This field displays the number of bindings the Switch has ignored because the port number was a trusted interface or does not exist anymore.
Parse failures	This field displays the number of bindings the Switch has ignored because the Switch was unable to understand the binding in the DHCP binding database.
Expired leases	This field displays the number of bindings the Switch has ignored because the lease time had already expired.
Unsupported vlans	This field displays the number of bindings the Switch has ignored because the VLAN ID does not exist anymore.

 Table 82
 Advanced Application > DHCP Snooping (continued)

# 23.3 DHCP Snooping Configure

Use this screen to enable DHCP snooping on the Switch (not on specific VLAN), specify the VLAN where the default DHCP server is located, and configure the DHCP snooping database. The DHCP snooping database stores the current bindings on a secure, external TFTP server so that they are still available after a restart. To open this screen, click **Advanced Application > DHCP Snooping > Configure**.

DITCP Shooping Configure			<b>BHCF Sheeping</b>	<u>Dec</u>	MAR
Active .	2				
DHOP view	🔍 🖉 🖉	N			
	(i) 100				
Database					
Append DRI					
for an extension of the sent	300	per parala			
We have had a send to see	300	per parda			
Render DHC / Showping U.S.			March	10	
	Apple C	and			

Figure 136 Advanced Application > DHCP Snooping > Configure

LABEL	DESC RIPTIO N	
Active	Select this to enable DHCP snooping on the Switch. You still have to enable DHCP snooping on specific VLAN and specify trusted ports.	
	Note: If DHCP is enabled and there are no trusted ports, DHCP requests will not succeed.	
DHCP Vlan	Select a VLAN ID if you want the Switch to forward DHCP packets to DHCP servers on a specific VLAN.	
	Note: You have to enable DHCP snooping on the DHCP VLAN too.	
	You can enable <b>Option82</b> in the <b>DHCP Snooping VIAN Configure</b> screen (Section 23.3.2 on page 191) to help the DHCP servers distinguish between DHCP requests from different VLAN.	
	Select <b>Disa b le</b> if you do not want the Switch to forward DHCP packets to a specific VLAN.	
Database	If <b>Timeout interval</b> is greater than <b>Write delay interval</b> , it is possible that the next update is scheduled to occur before the current update has finished successfully or timed out. In this case, the Switch waits to start the next update until it completes the current one.	
Agent URL	Enter the location of the DHCP snooping database. The location should be expressed like this: tftp:// {domain name or IP address}/ directory, if applicable/file name; for example, tftp:// 192.168.10.1/ database.txt.	
Timeout interval	Enter how long (10 – 65535 seconds) the Switch tries to complete a specific update i the DHCP snooping database before it gives up.	
Write delay interval	Enter how long (10 – 65535 seconds) the Switch waits to update the DHCP snooping database the first time the current bindings change after an update. Once the next update is scheduled, additional changes in current bindings are automatically included in the next update.	

Table 83 Advanced Application > DHCP Snooping > Configure

LABEL	DESC RIPTIO N
Renew DHCP Snooping URL	Enter the location of a DHCP snooping database, and click <b>Renew</b> if you want the Switch to load it. You can use this to load dynamic bindings from a different DHCP snooping database than the one specified in <b>Agent URL</b> .
	When the Switch loads dynamic bindings from a DHCP snooping database, it does not discard the current dynamic bindings first. If there is a conflict, the Switch keeps the dynamic binding in volatile memory and updates the <b>Binding collisions</b> counter in the <b>DHCP Snooping</b> screen (Section 23.2 on page 185).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

 Table 83
 Advanced Application > DHCP Snooping > Configure (continued)

### 23.3.1 DHCP Snooping Port Configure

Use this screen to specify whether ports are trusted or untrusted ports for DHCP snooping.

Note: If DHCP snooping is enabled but there are no trusted ports, DHCP requests cannot reach the DHCP server.

You can also specify the maximum number for DHCP packets that each port (trusted or untrusted) can receive each second. To open this screen, click **Advanced Application** > **DHCP Snooping** > **Configure** > **Port**.

100	27 Secondaria Paul Chestagoure	Gudapar
Fol	Server Instead state	Kale (pps)
	0 balad M	
1	Uninstad w	0
2	0 holed w	0
×	Insteid w	c .
2	Units died M	0
	Uninstant w	0
0	Unitsdied 🗠	0
	·	· · ·
	вору Слон	

Figure 137 Advanced Application > DHCP Snooping > Configure > Port

The following table describes the labels in this screen.

Table 84 Advanced Application > DHCP Snooping > Configure > Port

IABEL	DESC RIPTIO N
Port	This field displays the port number. If you configure the * port, the settings are applied to all of the ports.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

GS1350 Series User's Guide

LABEL	DESC RIPTIO N
Server Trusted state	Select whether this port is a trusted port (Thusted) or an untrusted port (Untrusted).
	Trusted ports are connected to DHCP servers or other switches, and the Switch discards DHCP packets from trusted ports only if the rate at which DHCP packets arrive is too high.
	Untrusted ports are connected to subscribers, and the Switch discards DHCP packets from untrusted ports in the following situations:
	<ul> <li>The packet is a DHCP server packet (for example, OFFER, ACK, or NACK).</li> <li>The source MAC address and source IP address in the packet do not match any of the current bindings.</li> <li>The packet is a RELEASE or DECLINE packet, and the source MAC address and source port do not match any of the current bindings.</li> <li>The rate at which DHCP packets arrive is too high.</li> </ul>
Rate (pps)	Specify the maximum number for DHCP packets (1-256) that the Switch receives from each port each second. The Switch discards any additional DHCP packets. Enter 0 to disable this limit, which is recommended for trusted ports.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 84	Advanced Application	> DHCP Snooping >	> Configure > Po	rt (continued)
----------	----------------------	-------------------	------------------	----------------

### 23.3.2 DHCP Snooping VIAN Configure

Use this screen to enable DHCP snooping on each VLAN and to specify whether or not the Switch adds DHCP relay agent option 82 information (Chapter 31 on page 241) to DHCP requests that the Switch relays to a DHCP server for each VLAN. To open this screen, click **Advanced Application > DHCP Snooping > Configure > VLAN**.

Figure 156	//uvuileeu//ppileuile		
BIICF	Snooping VLAH Conligue		<u>Configure</u> Part
V ANALS	h hy site		Sec. 1
The New Inc.	A VIAN D		
1 1	10	Enclosed	Option 82 Profile
	•	NV M	×
		App - Concel	
Change Pag	es herdoos	- And	

Figure 138 Advanced Application > DHCP Snooping > Configure > VLAN

The following table describes the labels in this screen.

Table 85	Advanced Application > DHCP	Snooping > Configure >	VLAN

LABEL	DESC RIPIIO N
VLAN Search by VID	Specify the VLANs you want to manage in the section below. Use a comma (,) to separate individual VLANs or a dash (–) to indicates a range of VLANs. For example, "3,4" or "3–9".
Search	Click this to display the specified range of VLANs in the section below.

G\$1350 Series User's Guide

LABEL	DESC RIPIIO N
VID	This field displays the VLAN ID of each VLAN in the range specified above. If you configure the * VLAN, the settings are applied to all VLANs.
Enabled	Select <b>Yes</b> to enable DHCP snooping on the VLAN. You still have to enable DHCP snooping on the Switch and specify trusted ports. Note: If DHCP is enabled and there are no trusted ports, DHCP requests will not
	succeed.
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to all ports in the specified VLANs. The Switch adds the information (such as slot number, port number, VLAN ID and/or system name) specified in the profile to DHCP requests that it broadcasts to the DHCP VLAN, if specified, or VLAN. You can specify the DHCP VLAN in the <b>DHCP Snooping Configure</b> screen (see Section 23.3 on page 188).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.
Change Pages	Click <b>Previous</b> or <b>Next</b> to show the previous/next screen if all status information cannot be seen in one screen.

Table 85	Advanced Application >	DHCP Snooping >	· Configure >	VLAN (continued)
----------	------------------------	-----------------	---------------	------------------

### 23.3.3 DHCP Snooping VIAN Port Configure

Use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN. To open this screen, click Advanced Application > DHCP Snooping > Configure > VLAN > Port.

Figure 139 Advanced Application > DHCP Snooping > Configure > VLAN > Port

ing une 100 /	(avancou /				
fart -				DHCF Shooping V.	IAN Configure
ND.					
Prof.					
Option 32 fr	of to:		$\sim$		-
		Add Da	nos Cleor		
Index.	VID	Port		Notic Name	Belete
		Do ete	Control		

The following table describes the labels in this screen.

Table 86 Advanced Application > DHCP Snooping > Configure > VLAN > Port

IABEL	DESC RIPIIO N
VID	Enter the ID number of the VLAN you want to configure here.
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.
	You can enter multiple ports separated by (no space) comma (,) or hyphen (–). For example, enter "3–5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.

LABEL	DESC RIPTIO N
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to the specified port(s) in this VLAN. The Switch adds the information (such as slot number, port number, VLAN ID and/or system name) specified in the profile to DHCP requests that it broadcasts to the DHCP VLAN, if specified, or VLAN. You can specify the DHCP VLAN in the <b>DHCP Snooping Configure</b> screen (see Section 23.3 on page 188).
	The profile you select here has priority over the one you select in the <b>DHCP Snooping</b> > <b>Configure</b> > <b>VIAN</b> screen.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values above based on the last selected entry or, if not applicable, to clear the fields above.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This field displays a sequential number for each entry. Click an index number to change the settings.
VID	This field displays the VLAN to which the ports belong.
Port	This field displays the ports to which the Switch applies the settings.
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports.
Delete	Select the entries that you want to remove in the <b>Delete</b> column, then click the <b>Delete</b> button to remove the selected entries from the table.
Cancel	Click this to clear the <b>Delete</b> check boxes above.

 Table 86
 Advanced Application > DHCP Snooping > Configure > VLAN > Port (continued)

# 23.4 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 23.4.1 DHCP Snooping Overview

Use DHCP snooping to filter unauthorized DHCP packets on the network and to build the binding table dynamically. This can prevent clients from getting IP addresses from unauthorized DHCP servers.

#### 23.4.1.1 Trusted vs. Untrusted Ports

Every port is either a trusted port or an untrusted port for DHCP snooping. This setting is independent of the trusted/untrusted setting for ARP inspection. You can also specify the maximum number for DHCP packets that each port (trusted or untrusted) can receive each second.

Trusted ports are connected to DHCP servers or other switches. The Switch discards DHCP packets from trusted ports only if the rate at which DHCP packets arrive is too high. The Switch learns dynamic bindings from trusted ports.

Note: If DHCP is enabled and there are no trusted ports, DHCP requests will not succeed.

Untrusted ports are connected to subscribers. The Switch discards DHCP packets from untrusted ports in the following situations:

- The packet is a DHCP server packet (for example, OFFER, ACK, or NACK).
- The source MAC address and source IP address in the packet do not match any of the current bindings.
- The packet is a RELEASE or DECLINE packet, and the source MAC address and source port do not match any of the current bindings.
- The rate at which DHCP packets arrive is too high.

#### 23.4.1.2 DHCP Snooping Database

The Switch stores the binding table in volatile memory. If the Switch restarts, it loads static bindings from permanent memory but loses the dynamic bindings, in which case the devices in the network have to send DHCP requests again. As a result, it is recommended you configure the DHCP snooping database.

The DHCP snooping database maintains the dynamic bindings for DHCP snooping and ARP inspection in a file on an external TFTP server. If you set up the DHCP snooping database, the Switch can reload the dynamic bindings from the DHCP snooping database after the Switch restarts.

You can configure the name and location of the file on the external TFTP server. The file has the following format:

Figure 140 DHCP Snooping Database File Format

```
<initial-checksum>
TYPE DHCP-SNOOPING
VERSION 1
BEGIN
<binding-1> <checksum-1>
<binding-2> <checksum-1-2>
...
<binding-n> <checksum-1-2-...n>
END
```

The <initial-checksum> helps distinguish between the bindings in the latest update and the bindings from previous updates. Each binding consists of 72 bytes, a space, and another checksum that is used to validate the binding when it is read. If the calculated checksum is not equal to the checksum in the file, that binding and all others after it are ignored.

#### 23.4.1.3 DHCP Relay Option 82 Information

The Switch can add information to DHCP requests that it does not discard. This provides the DHCP server more information about the source of the requests. The Switch can add the following information:

- Slot ID (1 byte), port ID (1 byte), and source VLAN ID (2 bytes)
- System name (up to 32 bytes)

This information is stored in an Agent Information field in the option 82 field of the DHCP headers of client DHCP request frames. See Chapter 31 on page 241 for more information about DHCP relay option 82.

When the DHCP server responds, the Switch removes the information in the Agent Information field before forwarding the response to the original source.

You can configure this setting for each source VLAN. This setting is independent of the DHCP relay settings (Chapter 31 on page 241).

#### 23.4.1.4 Configuring DHCP Snooping

Follow these steps to configure DHCP snooping on the Switch.


- 1 Enable DHCP snooping on the Switch.
- 2 Enable DHCP snooping on each VLAN, and configure DHCP relay option 82.
- 3 Configure trusted and untrusted ports, and specify the maximum number of DHCP packets that each port can receive per second.
- 4 Configure static bindings.

# CHAPTER 24 Loop Guard

# 24.1 Loop Guard Overview

This chapter shows you how to configure the Switch to guard against loops on the edge of your network.

Loop guard allows you to configure the Switch to shut down a port if it detects that packets sent out on that port loop back to the Switch. While you can use Spanning Tree Protocol (STP) to prevent loops in the core of your network. STP cannot prevent loops that occur on the edge of your network.



Refer to Section 24.1.2 on page 196 for more information.

### 24.1.1 What You Can Do

Use the Loop Guard screen (Section 24.2 on page 198) to enable loop guard on the Switch and in specific ports.


### 24.1.2 What You Need to Know

Loop guard is designed to handle loop problems on the edge of your network. This can occur when a port is connected to a Switch that is in a loop state. Loop state occurs as a result of human error. It happens when two ports on a switch are connected with the same cable. When a switch in loop state sends out broadcast messages the messages loop back to the switch and are re-broadcast again and again causing a broadcast storm.

If a switch (not in loop state) connects to a switch in loop state, then it will be affected by the switch in loop state in the following way:


- The switch (not in loop state) will receive broadcast messages sent out from the switch in loop state.
- The switch (not in loop state) will receive its own broadcast messages that it sends out as they loop back. It will then re-broadcast those messages again.


The following figure shows port  $\mathbf{N}$  on switch  $\mathbf{A}$  connected to switch  $\mathbf{B}$ . Switch  $\mathbf{B}$  has two ports,  $\mathbf{x}$  and  $\mathbf{y}$ , mistakenly connected to each other. It forms a loop. When broadcast or multicast packets leave port  $\mathbf{N}$  and reach switch  $\mathbf{B}$ , they are sent back to port  $\mathbf{N}$  on  $\mathbf{A}$  as they are rebroadcast from  $\mathbf{B}$ .



The loop guard feature checks to see if a loop guard enabled port is connected to a Switch in loop state. This is accomplished by periodically sending a probe packet and seeing if the packet returns on the same port. If this is the case, the Switch will shut down the port connected to the switch in loop state.

Loop guard can be enabled on both Ethernet ports. The following figure shows a loop guard enabled port **N** on switch **A** sending a probe packet **P** to switch **B**. Since switch **B** is in loop state, the probe packet **P** returns to port **N** on **A**. The Switch then shuts down port **N** to ensure that the rest of the network is not affected by the switch in loop state.






The Switch also shuts down port  $\mathbf{N}$  if the probe packet returns to switch  $\mathbf{A}$  on any other port. In other words loop guard also protects against standard network loops.

The following figure illustrates three switches forming a loop. A sample path of the loop guard probe packet is also shown. In this example, the probe packet is sent from port  $\mathbf{N}$  and returns on another port. As long as loop guard is enabled on port  $\mathbf{N}$ . The Switch will shut down port  $\mathbf{N}$  if it detects that the probe packet has returned to the Switch.





Note: After resolving the loop problem on your network you can re-activate the disabled port via the Web Configurator (see Section 8.7 on page 99) or via commands (See the CLI Reference Guide).

# 24.2 Loop Guard Setup

Click Advanced Application > Loop Guard in the navigation panel to display the screen as shown.

Note: The loop guard feature cannot be enabled on the ports that have Spanning Tree Protocol (RSTP) enabled.

Figure 145	Advanced Application >	Loop Guard
------------	------------------------	------------

Loop Guard	
Active	I
Port	Active
•	11
I. I.	II.
	11
5	
+	
5	11
ń.	11
	Support Comments

Table 87 Advanced	Application > Loop Guard
-------------------	--------------------------

IABEL	DESC RIPTIO N
Active	Select this option to enable loop guard on the Switch.
	The Switch generates syslog, internal log messages as well as SNMP traps when it shuts down a port via the loop guard feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the loop guard feature on this port. The Switch sends probe packets from this port to check if the switch it is connected to is in loop state. If the switch that this port is connected is in loop state the Switch will shut down this port.
	Clear this check box to disable the loop guard feature.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HA PTER 25 Error Disable

## 25.1 Error Disable Overview

This chapter shows you how to configure the rate limit for control packets on a port, and set the Switch to take an action (such as to shut down a port or stop sending packets) on a port when the Switch detects a pre-configured error. It also shows you how to configure the Switch to automatically undo the action after the error is gone.

### 25.1.1 CPU Protection Overview

Switches exchange protocol control packets in a network to get the latest networking information. If a switch receives large numbers of control packets, such as ARP, BPDU or IGMP packets, which are to be processed by the CPU, the CPU may become overloaded and be unable to handle regular tasks properly.

The CPU protection feature allows you to limit the rate of ARP, BPDU and IGMP packets to be delivered to the CPU on a port. This enhances the CPU efficiency and protects against potential DoS attacks or errors from other networks. You then can choose to drop control packets that exceed the specified rate limit or disable a port on which the packets are received.

### 25.1.2 Enor-Disable Recovery Overview

Some features, such as loop guard or CPU protection, allow the Switch to shut down a port or discard specific packets on a port when an error is detected on the port. For example, if the Switch detects that packets sent out the ports loop back to the Switch, the Switch can shut down the ports automatically. After that, you need to enable the ports or allow the packets on a port manually via the Web Configurator or the commands. With error-disable recovery, you can set the disabled ports to become active or start receiving the packets again after the time interval you specify.

### 25.1.3 What You Can Do

- Use the Endisable Status screen (Section 25.3 on page 200) to view whether the Switch detected that control packets exceeded the rate limit configured for a port or a port is disabled according to the feature requirements and what action you configure, and related information.
- Use the **CPU Protection** screen (Section 25.4 on page 202) to limit the maximum number of control packets (ARP, BPDU and/or IGMP) that the Switch can receive or transmit on a port.
- Use the Endisable Detect screen (Section 25.5 on page 203) to have the Switch detect whether the control packets exceed the rate limit configured for a port and configure the action to take once the limit is exceeded.
- Use the Endisable Recovery screen (Section 25.6 on page 204) to set the Switch to automatically undo an action after the error is gone.

## 25.2 Error Disable Settings

Use this screen to go to the screens where you can configure error disable related settings. Click **Advanced Application** > **Endisable** in the navigation panel to open the following screen.

Figure 146 Advanced Application > Errdisable

Encloses Mailes	C 08 1610	
CI Uprefection	Vick here	
Endbala a Derival	V SR 1615	
For Isail or Processing	Conference of the second	

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N		
Errdisable Status	Click this link to view whether the Switch detected that control packets exceeded the rate limit configured for a port or a port is disabled according to the feature requirements and what action you configure, and related information.		
CPU protection	Click this link to limit the maximum number of control packets (ARP, BPDU and/or IGMP) that the Switch can receive or transmit on a port.		

Table 88 Advanced Application > Errdisable

# 25.3 Error Disable Status

Errdisable Detect

Errdisable Recovery

Use this screen to view whether the Switch detected that control packets exceeded the rate limit configured for a port or a port is disabled according to the feature requirements and what action you configure, and related information. Click the **Click here** link next to **Endisable Status** in the **Advanced Applic ation** > **Endisable** screen to display the screen as shown.

Click this link to have the Switch detect whether the control packets exceed the rate limit configured for a port and configure the action to take once the limit is exceeded.

Click this link to set the Switch to automatically undo an action after the error is gone.

ctive.	Errdisable Statu reason mode re						Bridisab
ort IIs				Cau	se	ARP 🗸 🖡	aset
ilsabk	e Status						
Port	Cause	Active	Mode	Rate	Status	Recovery Time Left (secs)	Total Dropped
	Loop Guard	NO	inactive-port	-	Forwarding	-	-
1	ARP	NO	inactive-port	0	Forwarding	-	-
· ·	REDU	NO	inactive port	0	Forwarding		
	KGMP	NO	inactive port	0	Forwarding		
	Loop Cuard	NO	inactive port		Forwarding		
2	ARP	NO	inactive port	0	Forwarding		
1	BPDU	NO	inactive-port	0	Forwarding	-	-
	IGMP	NO	inactive-port	0	Forwarding	-	-
	Loop Guard	NO	inactive-port	-	Forwarding	-	-
	ARP	NO	Inactive port	0	Forwarding		
3	REDU	NO	Inactive port	0	Forwarding		
	IGMP	NO	inactive-port	0	Forwarding	-	-
	Loop Cuard	NO	Inactive port		Forwarding		
	ARP	NO	inactive-port	0	Forwarding	-	-
4	BPDU	NO	inactive-port	0	Forwarding	-	-
	KOMP	NO	inactive port	0	Forwarding		
	Loop Cuard	NO	Inactive port		Forwarding		
5	ARP	NO	Inactive port	0	Forwarding		
0	BPDU	NO	inactive-port	0	Forwarding	-	-
	IGMP	NO	inactive-port	0	Forwarding	-	-
	Loop Guard	NO	inactive-port	-	Ferwarding	-	-
	ARP	NO	inactive-port	0	Forwarding	-	-
6	REDU	NO	inactive port	0	Forwarding		
	KOMP	NO	inactive port	0	Forwarding		

Figure 147 Advanced Application > Errdisable > Errdisable Status

Table 89 Advanced Application > Errdisable > Errdisable Status

LABEL	DESC RIPIIO N
Inactive-reason mode reset	
Port List	Enter the number of the ports (separated by a comma) on which you want to reset inactive- reason status.
Cause	Select the cause of inactive-reason mode you want to reset here.
Reset	Press to reset the specified ports to handle ARP, BPDU or IGMP packets instead of ignoring them, if the ports is in inactive-reason mode.
Errdisable Status	
Port	This is the number of the port on which you want to configure Errdisable Status.
Cause	This displays the type of the control packet received on the port or the feature enabled on the port and causing the Switch to take the specified action.
Active	This field displays whether the control packets (ARP, BPDU, and/or IGMP) on the port is being detected or not. It also shows whether loop guard, anti-arp scanning, BPDU guard or ZULD is enabled on the port.

LABEL	DESC RIPTIO N		
Mode	This field shows the action that the Switch takes for the cause.		
	• <b>inactive-port</b> – The Switch disables the port.		
	<ul> <li>inactive-reason – The Switch drops all the specified control packets (such as BPDU) on the port.</li> </ul>		
	<ul> <li>na te - lim ita tion – The Switch drops the additional control packets the ports has to handle in every one second.</li> </ul>		
Rate	This field displays how many control packets this port can receive or transmit per second. It can be adjusted in <b>CPU Protection</b> . <b>0</b> means no rate limit.		
Status	This field displays the errdisable status		
	• <b>Forwarding</b> : The Switch is forwarding packets. Rate-limitation mode is always in <b>Forwarding</b> status.		
	• En disable: The Switch disables the port on which the control packets are received (inactive-port) or drops specified control packets on the port (inactive-reason).		
Recovery Time Left	This field displays the time (seconds) left before the port(s) becomes active of Errdisable Recovery.		
Total Dropped	This field displays the total packet number dropped by this port where the packet rate exceeds the rate of mode rate-limitation.		

 Table 89
 Advanced Application > Errdisable > Errdisable Status (continued)

# 25.4 CPU Protection Configuration

Use this screen to limit the maximum number of control packets (ARP, BPDU and/or IGMP) that the Switch can receive or transmit on a port. Click the **Click Here** link next to **CPU protection** in the **Advanced Application** > **Endisable** screen to display the screen as shown.

Note: After you configure this screen, make sure you also enable error detection for the specific control packets in the **Advanced Application** > **Endisable** > **Endisable** Detect screen.

CPU protection		Enclosible	
Decision: Ann. M			
Part	Rate Limit (pkt/s)		
	0		
2	0		
1 C	0		
-i	0		
5	<u>e</u>		
4	6-		
Apatz Contral			

Figure 148 Advanced Application > Errdisable > CPU protection

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Reason	Select the type of control packet you want to configure here.
Port	This field displays the port number.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.
	Changes in this row are copied to all the ports as soon as you make them.
Rate Limit (pkt/s)	Enter a number from 0 to 256 to specify how many control packets this port can receive or transmit per second.
	<b>0</b> means no rate limit.
	You can configure the action that the Switch takes when the limit is exceeded. See Section 25.5 on page 203 for detailed information.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 90 Advanced Application > Errdisable > CPU protection

## 25.5 Error Disable Detect Configuration

Use this screen to have the Switch detect whether the control packets exceed the rate limit configured for a port and configure the action to take once the limit is exceeded. Click the **Click Here** link next to **Endisable Detect** link in the **Advanced Application** > **Endisable** screen to display the screen as shown.

Endisable Detect			Enthoble
Coree	Anthea	Node	
		incid we peak	
A.9	1	inactive peak	-
KM100		innetike peri	
KAMP -		incertive-peak	-
	Apply Cano	a .	

Figure 149 Advanced Application > Errdisable > Errdisable Detect

Table 91	Advanced Application >	<ul> <li>Errdisable &gt; Errdisable Detect</li> </ul>
----------	------------------------	---

LABEL	DESC RIPTIO N	
Cause	This field displays the types of control packet that may cause CPU overload.	
*	Use this row to make the setting the same for all entries. Use this row first and then make adjustments to each entry if necessary.	
	Changes in this row are copied to all the entries as soon as you make them.	
Active	Select this option to have the Switch detect if the configured rate limit for a specific control packet is exceeded and take the action selected below.	

Table 91 Advanced Application > Errdisable > Errdisable Detect (continued)

IABEL	DESC RIPIIO N
Mode	Select the action that the Switch takes when the number of control packets exceed the rate limit on a port, set in the <b>Advanced Application</b> > <b>Endisable</b> > <b>CPU protection</b> screen.
	<ul> <li>inactive-port – The Switch disables the port on which the control packets are received.</li> <li>inactive-reason – The Switch drops all the specified control packets (such as BPDU) on the port.</li> <li>rate-limitation – The Switch drops the additional control packets the ports has to handle in every one second.</li> </ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 25.6 Error Disable Recovery Configuration

Use this screen to configure the Switch to automatically undo an action after the error is gone. Click the **Click Here** link next to **Endisable Recovery** in the **Advanced Application** > **Endisable** screen to display the screen as shown.

Enclosible Recove	ty	Enditable
Active	I	
10	Leave Mader	let
Keesen •	lima Sulva	Interval
ang panal	I	500
ARP		300
KED11	I	300
NS MP		200
	Pop y Cance	

Figure 150 Advanced Application > Errdisable > Errdisable Recovery

T-1-1- 00		Emplie adalla S. Emplie adall	- D
Table 92	Advanced Application	Erraisable > Erraisable	e Recovery

LABEL	DESC RIPIIO N
Active	Select this option to turn on the error-disable recovery function on the Switch.
Reason	This field displays the supported features that allow the Switch to shut down a port or discard packets on a port according to the feature requirements and what action you configure.
*	Use this row to make the setting the same for all entries. Use this row first and then make adjustments to each entry if necessary.
	Changes in this row are copied to all the entries as soon as you make them.
Timer Status	Select this check box to allow the Switch to wait for the specified time interval to activate a port or allow specific packets on a port, after the error was gone. Clear the check box to turn off this rule.
Interval	Enter the number of seconds (from 30 to 2592000) for the time interval.

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 92
 Advanced Application > Errdisable > Errdisable Recovery (continued)

# CHAPTER 26 Green Ethernet

This chapter shows you how to configure the Switch to reduce the power consumed by switch ports.

# 26.1 Green Ethernet Overview

Green Ethernet reduces switch port power consumption in the following ways.

#### IEEE 802.3az Energy Efficient Ethernet (EEE)

If EEE is enabled, both sides of a link support EEE and there is no traffic, the port enters Low Power Idle (LPI) mode. LPI mode turns off some functions of the physical layer (becomes quiet) to save power. Periodically the port transmits a REFRESH signal to allow the link partner to keep the link alive. When there is traffic to be sent, a WAKE signal is sent to the link partner to return the link to active mode.

#### Auto PowerDown

Auto Power Down turns off almost all functions of the port's physical layer functions when the link is down, so the port only uses power to check for a link up pulse from the link partner. After the link up pulse is detected, the port wakes up from Auto Power Down and operates normally.

#### Short Reach

Traditional Ethernet transmits all data with enough power to reach the maximum cable length. Shorter cables lose less power, so **Short Reach** saves power by adjusting the transmit power of each port according to the length of cable attached to that port.

# 26.2 Configuring Green Ethernet

Click Advanced Application > Green Ethemet in the navigation panel to display the screen as shown.

Note: EEE, Auto Power Down and Short Reach are NOT supported on an uplink port.

206

Figure 151 Advalle			
Green Ethernet			
HFF			
Auto Power Down		=	
Shorl Reach		-	
Port	EEE	Auto Power Down	Short Reach
*			
1			_
2			_
3		7	-
4			
6			-
6			
Apply Cancel			
	_		

Figure 151 Advanced Application > Green Ethernet

IABEL	DESC RIPIIO N	
EEE	Select this to activate Energy Efficient Ethernet globally.	
Auto Power Down	Select this to activate Auto Power Down globally.	
Short Reach	Select this to activate Short Reach globally.	
Port	This field displays the port number.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.	
	Changes in this row are copied to all the ports as soon as you make them.	
EEE	Select this to activate Energy Efficient Ethernet on this port.	
Auto Power Down	Select this to activate Auto Power Down on this port.	
Short Reach	Select this to activate Short Reach on this port.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

Table 93 Advanced Application > Green Ethernet

# C HAPTER 27 31 Link Layer Discovery Protocol (LLDP)

## 27.1 IIDP Overview

The LLDP (Link Layer Discovery Protocol) is a layer 2 protocol. It allows a network device to advertise its identity and capabilities on the local network. It also allows the device to maintain and store information from adjacent devices which are directly connected to the network device. This helps an administrator discover network changes and perform necessary network reconfiguration and management. The device information is encapsulated in the LLDPDUs (LLDP data units) in the form of TLV (Type, Length, Value). Device information carried in the received LLDPDUs is stored in the standard MIB.

The Switch supports these basic management TLVs.

- End of LLDPDU (mandatory)
- Chassis ID (mandatory)
- Port ID (mandatory)
- Time to Live (mandatory)
- Port Description (optional)
- System Name (optional)
- System Description (optional)
- System Capabilities (optional)
- Management Address (optional)

The Switch also supports the IEEE 802.1 and IEEE 802.3 organizationally-specific TLVs.

IEEE 802.1 specific TLVs:


- Port VLAN ID TLV (optional)
- Port and Protocol VLAN ID TLV (optional)

IEEE 802.3 specific TLVs:

- MAC/PHY Configuration/Status TLV (optional)
- Power via MDI TLV (optional, For PoE models only)
- Link Aggregation TLV (optional)
- Maximum Frame Size TLV (optional)

The optional TLVs are inserted between the Time To Live TLV and the End of LLDPDU TLV.

The next figure demonstrates that the network devices Switches and Routers (S and R) transmit and receive device information via LLDPDU and the network manager can query the information using Simple Network Management Protocol (SNMP).



# 27.2 LLDP-MED Overview


LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) is an extension to the standard LLDP developed by the Telecommunications Industry Association (TIA) TR-41.4 subcommittee which defines the enhanced discovery capabilities, such as VoIP applications, to enable network administrators manage their network topology application more efficiently. Unlike the traditional LLDP, which has some limitations when handling multiple application devices, the LLDP-MED offers display of accurate physical topology, interoperability of devices, and easy trouble shooting for mis-configured IP addresses. There are 3 classes of endpoint devices that the LLDP-MED supports:

Class I: IP Communications Controllers or other communication related servers

Class II: Voice Gateways, Conference Bridges or Media Servers

Class III: IP-Phones, PC-based Softphones, End user Communication Appliances supporting IP Media

The following figure shows that with the LLDP-MED, network connectivity devices (NCD) like Switches and Routers will transmit LLDP TLV to endpoint device (ED) like IP Phone first (1), to get its device type and capabilities information, then it will receive that information in LLDP-MED TLV back from endpoint devices (2), after that the network connectivity devices will transmit LLDP-MED TLV (3) to provision the endpoint device to such that the endpoint device's network policy and location identification information is updated. Since LLDPDU updates status and configuration information periodically, network managers may check the result of provision via remote status. The remote status is updated by receiving LLDP-MED TLVs from endpoint devices.



# 27.3 IIDP Settings

Click Advanced Application > IIIDP in the navigation panel to display the screen as shown next.

rigule 154 AUV			
un r			
	IDF Load States	Clickhare	
100 <del>0</del>	11% Republics may	Charles Inc. inc.	
	LEFF Configuration	Clickhere	
	IDE-MED Configuration	<u>Clickhaw</u>	
THE MED	THE MEDIN LANDS Prints	A Statistic const	
	LEFE MED Local for	Clickhere	

Figure 154 Advanced Application > LLDP

Table 94	Advanced Application > LLDP	
----------	-----------------------------	--

IABEL	DESC RIPIIO N	
LLDP		
LLDP Local Status	Click here to show a screen with the Switch's LLDP information.	
LLDP Remote Status	Click here to show a screen with LLDP information from the neighboring devices.	

LABEL	DESC RIPTIO N
LLDP Configuration	Click here to show a screen to configure LLDP parameters.
LLDP-MED	
LLDP-MED Configuration	Click here to show a screen to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) parameters.
LLDP-MED Network Policy	Click here to show a screen to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) network policy parameters.
LLDP-MED Location	Click here to show a screen to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) location parameters.

Table 94 Advanced Application > LLDP (continued)

# 27.4 IIDP Local Status

This screen displays a summary of LLDP status on this Switch. Click Advanced Application > ILDP > ILDP Local Status to display the screen as shown next.

UCP is out theirs. HTML Springer information		<u>uar</u>
voře ivy		
	chorik is subtype	max-addres
A REPORT OF	Marine B.	ta mitaka210.00
Dalla e Nories IV	Apple of the second	0.0000
system periodicinity	ystem usediption	verzejechtujos į vežiežoco
Darlant Charled atting 11V	$\lambda_{\rm g}$ where the probability $\lambda_{\rm eff}$ produces	Proto-
and a second second second second	$\mathcal{O}_{\mathcal{O}}$ is the Composite field of the second state $\mathcal{O}_{\mathcal{O}}$	E style
	v on ogeneen two draip sybbype	lper / alleus
Manager and Address 1.4	$\alpha$ -relation the rate of the gradient $\alpha$	e nine even
and a straight and a straight of the	n a bear Nemine	:
	May ref. and the	1
UDF had intermedian		
	D Sublype - Barl D	Part Description
	kabighed i	
	kalajared 2	
	Learning ( A	
	Leaves at 4	
	Longers ( S Longers ( S	

Figure 155 Advanced Application > LLDP > LLDP Local Status

The following table describes the labels in this screen.

Table 95	Advanced Application > LLDP > LLDP Local Status	

IABEL	DESC RIPIIO N
Basic TLV	
Chassis ID TLV	This displays the chassis ID of the local Switch, that is the Switch you are configuring. The chassis ID is identified by the chassis ID subtype.
	Chassis ID Subtype – this displays how the chassis of the Switch is identified.
	${f C}{f ha}{f ssis}{f I\!D}$ – This displays the chassis ID of the local Switch.
System Name TLV	This shows the host name of the Switch.
System Description TLV	This shows the firmware version of the Switch.
System Capabilities TLV	This shows the System Capabilities enabled and supported on the local Switch.
	System Capabilities Supported – Bridge
	System Capabilities Enabled – Bridge
Management Address TLV	The Management Address TLV identifies an address associated with the local LLDP agent that may be used to reach higher layer entities to assist discovery by network management. The TLV may also include the system interface number and an object identifier (OID) that are associated with this management address.
	This field displays the Management Address settings on the specified ports.
	• Management Address Subtype – ipv4 or all-802
	• Interface Number Subtype - Unknown
	• Interface Number – 0 (not supported)
	• Object Identifier - 0 (not supported)
LLDP Port Information	This displays the local port information.
Local Port	This displays the number of the Switch port which receives the LLDPDU from the remote device. Click a port number to view the detailed LLDP status on this port in the <b>LLDP Local Port Status De tail</b> screen.
Port ID Subtype	This indicates how the port ID field is identified.
Port ID	This is an alpha-numeric string that contains the specific identifier for the port from which this LLDPDU was transmitted.
Port Description	This shows the port description that the Switch will advertise from this port.

## 27.4.1 IIDP Local Port Status Detail

This screen displays detailed LLDP status for each port on this Switch. Click Advanced Application > ILDP > ILDP Local Status and then, click a port number, for example 1 in the local port column to display the screen as shown next.

LLDP Local PortSicius Detai	Silcation > LLDP > LLDP Local S	UCF Local Yolu
Local Fort 1		
Easter I Dy		
Port ID TIM	<ul> <li>El Esalelype</li> </ul>	hard suggest
	365 D	1
Port Description 1 V	Tom Department	path
Dell IDV		
For MARIE 112	<ul> <li>MEANID</li> </ul>	1
DeCUTIV		
	AN Supported	î va
MAC TIM Configuration A Status	4N Probled	Yes
ill'a	Ald Advards of Cospectations	105usel 105usel 10 1005usel 8 1005useT0T0 10005useT00
	Open MAU Type	20
	Aggregation Copatrilly	Yes
taik Ageng manufi 2	Apply a public Victor	No
	Aggregeled Perl ID	0
M as frame Size TIM	Mox Prome She	1510
мтрити		
	Machine & Pade y	his
	Localion	Yva
Copublities BV	Diend Power via MDIPIT	Ro
	education services and MD1PD	No
	r ver lete Wanegen vir f	No
Revice Type T V	Teoloa Typa	Retwork Connectivity
	stur.	
	Volge Styrieling	
	Jarest Violog	
	County Manual Appanents	
Ketwak Polity TV	Sellahone Valee	
	Video-Conferencina	
	Minister of Million	
	vittes Synality Secondaria base - 21	
	Spordingte-base (C)	
The control devictor charactery	Con 1-2	
	1.0	

#### Figure 156 Advanced Application > LLDP > LLDP Local Status > LLDP Local Port Status Detail

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Local Port	This displays the number of the Switch's port.
Basic TLV	These are the Basic TLV flags
Port ID TLV	The port ID TLV identifies the specific port that transmitted the LLDP frame.
	<ul> <li>Port ID Subtype: This shows how the port is identified.</li> <li>Port ID: This is the ID of the port.</li> </ul>
Port Description TLV	This displays the local port description.
Dot1 TLV	
Port VLAN ID TLV	This displays the VLAN ID sent by the IEEE 802.1 Port VLAN ID TLV.
Dot3 TLV	
MAC PHY Configuration & Status TLV	The MAC/PHY Configuration/Status TLV advertises the bit-rate and duplex capability of the sending 802.3 node. It also advertises the current duplex and bit-rating of the sending node. Lastly, it advertises whether these setting were the result of auto-negotiation during link initiation or manual override.
	<ul> <li>AN Supported – Displays if the port supports or does not support auto-negotiation.</li> <li>AN Enabled – The current auto-negotiation status of the port.</li> <li>AN Advertised Capability – The auto-negotiation capabilities of the port.</li> <li>OperMAU Type – The current Medium Attachment Unit (MAU) type of the port.</li> </ul>
Link Aggregation TLV	The Link Aggregation TLV indicates whether the link is capable of being aggregated, whether the link is currently in an aggregation, and if in an aggregation, the port identification of the aggregation.
	<ul> <li>Aggregation Capability – The current aggregation capability of the port.</li> <li>Aggregation Status – The current aggregation status of the port.</li> <li>Aggregation Port ID – The aggregation ID of the current port.</li> </ul>
Max Frame Size TLV	This displays the maximum supported frame size in octets.
MED TLV	LLDP Media Endpoint Discovery (MED) is an extension of LLDP that provides additional capabilities to support media endpoint devices. MED enables advertisement and discovery of network policies, device location discovery to allow creation of location databases, and information for troubleshooting.
Capabilities TLV	This field displays which LLDP-MED TLV are capable to transmit on the Switch.
	Ne two ik Policy
	Location     Extend Powervia MDIPSE
	Extend Power via MDI PSE     Extend Power via MDI PD
	<ul> <li>Inventory Management</li> </ul>
Device Type	This is the LLDP-MED device class. The Zyxel Switch device type is:
TLV	Network Connectivity

Table 96 Advanced Application > LLDP > LLDP Local Status > LLDP Local Port Status Detail

IABEL	DESC RIPIIO N	
Network Policy TLV	This displays a network policy for the specified application.	
	• Voice	
	• Voice-Signaling	
	• Guest-Voice	
	• Guest-Voice-Signaling	
	• Softphone-Voice	
	• Vide o - C onferencing	
	• Streaming-Video	
	Vide o - Sig na ling	
Location Identification TLV	This shows the location information of a caller by its ELIN (Emergency Location Identifier Number) or the IETF Geopriv Civic Address based Location Configuration Information (Civic Address LCI).	
	<ul> <li>Coordinate-based ICI – latitude, longitude and altitude coordinates of the location Configuration Information (LCI)</li> </ul>	
	Civic ICI-IETF Geopriv Civic Address based Location Configuration Information	
	ELIN – (Emergency Location Identifier Number)	

 Table 96
 Advanced Application > LLDP > LLDP Local Status > LLDP Local Port Status Detail (continued)

# 27.5 LLDP Remote Status

This screen displays a summary of LLDP status for each LLDP connection to a neighboring Switch. Click **Advanced Application > ILDP > ILDP Remote Status (Click Here**) to display the screen as shown next.

ше	LLDF for who 2 win.					
Index	Loc of Port	Chanh 13	PortID	Peri Description	Syrien: Harne	Non ogeneent Address
T		a baar a destart	0000000-00400 1000			
÷.,		Anna 6576 Alexand	01000045145. 0000			
×	1	de sector supre da <sup>r</sup>	dependencer all			
2	<u>, 1</u>	official (and).	24		DANGU	

Table 97	Advance	d Application :	> LLDP >	LLDP Remote Status	

IABEL	DESC RIPIIO N
Index	The index number shows the number of remote devices that are connected to the Switch. Click on an index number to view the detailed LLDP status for this remote device in the <b>IIDP</b> <b>Remote Port Status Detail</b> screen.
Local Port	This is the number of the Switch's port that received LLDPDU from the remote device.
Chassis ID	This displays the chassis ID of the remote device associated with the transmitting LLDP agent. The chassis ID is identified by the chassis ID subtype. For example, the MAC address of the remote device.
Port ID	This is an alpha-numeric string that contains the specific identifier for the port from which this LLDPDU was transmitted. The port ID is identified by the port ID subtype.
Port Description	This displays a description for the port from which this LLDPDU was transmitted.

IABEL	DESC RIPIIO N		
System Name	This displays the system name of the remote device.		
Management Address	This displays the management address of the remote device. It could be the MAC address or IP address.		

 Table 97
 Advanced Application > LLDP > LLDP Remote Status (continued)

#### 27.5.1 IIDP Remote Port Status Detail

This screen displays detailed LLDP status of the remote device connected to the Switch. Click Advanced Application > ILDP > ILDP Remote Status (Click Here) and then click an index number, for example 1, in the Index column in the ILDP Remote Status screen to display the screen as shown next.

Figure 158 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Basic TLV)

uue sensie antiticiu se sooi voit s	etc.	Luce comple status
Family .		
Classes #117	Marriel Bolids gas	e and a block of
	(The ray II)	CALLARD AND CONTRACTOR
No. INT V	roma: Jubrype	book only red
	An 10	ъ
free to diverse	time to the	20
remension (pilon rev	romunes tplion	
Applane Merice (198	Ayaka a kata a	1999.04
galan Durap an TV	System 1 Starting at the	м сулска ралости
system stoppid fleringe	$\mathcal{L}_{\mathbf{y}}$ where $\mathcal{L}_{\mathbf{y}}$ is defined by $\mathcal{L}_{\mathbf{y}}$ , where $\mathbf{f}$	traipe:
уулып суррантын түн	system crapabilities undoted	bildge
	$V_{\rm eff}$ and provide the state of a bid group $V_{\rm eff}$	ALC N
	маладелені Аралер	e-causobdy doccud
Verseptend Sector 3V	e educe Barda e Zalegar	entre exe
	n a bear Neider	:
	vojeci centifer	

The following table describes the labels in Basic TLV part of the screen.

Table 98 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Basic TLV)

LABEL	DESC RIPIIO N
Local Port	This displays the number of the Switch's port to which the remote device is connected.
Basic TLV	

IABEL	DESC RIPTIO N
Chassis ID TLV	<ul> <li>Chassis ID Subtype – this displays how the chassis of the remote device is identified.</li> <li>Chassis ID – this displays the chassis ID of the remote device. The chassis ID is identified by the chassis ID subtype.</li> </ul>
Port ID TLV	<ul> <li>Port ID Subtype – this displays how the port of the remote device is identified.</li> <li>Port ID – this displays the port ID of the remote device. The port ID is identified by the port ID subtype.</li> </ul>
Time To Live TLV	This displays the time-to-live (TTL) multiplier of LLDP frames. The device information on the neighboring devices ages out and is discarded when its corresponding TTL expires. The TTL value is to multiply the TTL multiplier by the LLDP frames transmitting interval.
Port Description TLV	This displays the remote port description.
System Name TLV	This displays the system name of the remote device.
System Description TLV	This displays the system description of the remote device.
System Capabilities TLV	<ul> <li>This displays whether the system capabilities are enabled and supported on the remote device.</li> <li>System Capabilities Supported</li> <li>System Capabilities Enabled</li> </ul>
Management Address TLV	<ul> <li>This displays the management address of the remote device.</li> <li>Management Address Subtype</li> <li>Management Address</li> <li>Interface Number Subtype</li> <li>Interface Number</li> <li>Object Identifier</li> </ul>

Table 98 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Basic TLV) (continued)

Figure 159	Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail> (Dot
1 and I	Dot3 TLV)

DOIT TI V		
TWEVEAND BY	EMENDARID	
	ParkIndiscol VI.Ah. ID	
Pod Pol Cool M SMI CHV	First Performants' Als II Supported	
	For Freidessi VLAN ID Larebled	
	VEANID	
Mon Nome (EV	VEAD No. or	
Indexel dently ID4	Tratecollo	
0. DO 10.		
	ANAquanted	<b>Ф</b> :
	AM southly 1	No
MAC F IN Configuration & Motor IEV	WM Schemenson Conjust - Ty	
	Oper 4600 type	a
	Appropriation Coordelity	200
took Age og an om 112	Approprie s Michael	No
	Aggroyeled for ID	d .
	Fort Class	
	M Respondent	
Provide Sim M. 8112	MDI Encolvel	
	Fair Controlable	
	Este Marson Proc.	
	Lower Claw	
Max Transe She TIM	Mos frame Site	

The following table describes the labels in the Dot1 and Dot3 parts of the screen.

Table 99 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Dot1	
and Dot3 TLV)	

IA BEL	DESC RIPTIO N
Dot1 TLV	
Port VLAN ID TLV	This displays the VLAN ID of this port on the remote device.
Port-Protocol VLAN ID TLV	This displays the IEEE 802.1 Port Protocol VLAN ID TLV, which indicates whether the VLAN ID and whether it is enabled and supported on the port of remote Switch which sent the LLDPDU.
	Port-Protocol VIAN ID
	Port-Protocol VIAN ID Supported
	Port-Protocol VIAN ID Enabled

G\$1350 Series User's Guide

LABEL	DESC RIPTIO N
Vlan Name TLV	This shows the VLAN ID and name for remote device port.
	<ul> <li>VIAN ID</li> <li>VIAN Name</li> </ul>
Protocol Identity TLV	The Protocol Identity TLV allows the Switch to advertise the particular protocols that are accessible through its port.
Dot3 TLV	
MAC PHY Configuration & Status TLV	The MAC/PHY Configuration/Status TLV advertises the bit-rate and duplex capability of the sending 802.3 node. It also advertises the current duplex and bit-rating of the sending node. Lastly, it advertises whether these setting were the result of auto-negotiation during link initiation or manual override.
	<ul> <li>AN Supported – Displays if the port supports or does not support auto-negotiation.</li> <li>AN Enabled – The current auto-negotiation status of the port.</li> <li>AN Advertised Capability – The auto-negotiation capabilities of the port.</li> <li>Oper MAU Type – The current Medium Attachment Unit (MAU) type of the port.</li> </ul>
Link Aggregation TLV	The Link Aggregation TLV indicates whether the link is capable of being aggregated, whether the link is currently in an aggregation, and if in an aggregation, the port identification of the aggregation.
	<ul> <li>Aggregation Capability – The current aggregation capability of the port.</li> <li>Aggregation Status – The current aggregation status of the port.</li> <li>Aggregation Port ID – The aggregation ID of the current port.</li> </ul>
Power Via MDI TLV	The Power Via MDI TLV allows network management to advertise and discover the MDI power support capabilities of the sending port on the remote device.
	<ul> <li>Port Class</li> <li>MDI Supported</li> <li>MDI Enabled</li> <li>Pair Controllable</li> <li>PSE Power Pairs</li> <li>Power Class</li> </ul>
Max Frame Size TLV	This displays the maximum supported frame size in octets.

Table 99 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Dot1 and Dot3 TLV) (continued)



Figure 160 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (MED TLV)

GS1350 Series User's Guide

The following table describes the labels in the MED TLV part of the screen.

Table 100 Advanced Application > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (MED TLV)

LABEL	DESC RIPIIO N
MED TLV	LLDP Media Endpoint Discovery (MED) is an extension of LLDP that provides additional capabilities to support media endpoint devices. MED enables advertisement and discovery of network policies, device location discovery to allow creation of location databases, and information for troubleshooting.
Capabilities TLV	This displays the MED capabilities the remote port supports.
	<ul> <li>Network Policy</li> <li>Location</li> <li>Extend Powervia MDI PSE</li> <li>Extend Powervia MDI PD</li> <li>Inventory Management</li> </ul>
Device Type TLV	LLDP-MED endpoint device classes: • Endpoint Class I • Endpoint Class II • Endpoint Class III • Network Connectivity
Network Policy TLV	This displays a network policy for the specified application.
	<ul> <li>Voic e</li> <li>Voic e - Sig na ling</li> <li>Guest-Voic e</li> <li>Guest-Voic e - Sig na ling</li> <li>Softphone - Voic e</li> <li>Vide o - Conferencing</li> <li>Streaming - Vide o</li> <li>Vide o - Sig na ling</li> </ul>
Location Identification TLV	<ul> <li>This shows the location information of a caller by its:</li> <li>Coordinate-base ICI – latitude and longitude coordinates of the Location Configuration Information (LCI)</li> <li>Civic ICI – IETF Geopriv Civic Address based Location Configuration Information</li> <li>EUN – (Emergency Location Identifier Number)</li> </ul>
Inventory TLV	The majority of IP Phones lack support of management protocols such as SNMP, so LLDP-MED inventory TLVs are used to provide their inventory information to the Network Connectivity Devices such as the Switch. The Inventory TLV may contain the following information. • Hardware Revision • Software Revision • Firmware Revision • Model Name • Manufacturer • Serial Number • Asset ID
Extended Power via MDI TLV	<ul> <li>Extended Power Via MDI Discovery enables detailed power information to be advertised by Media Endpoints, such as IP phones and Network Connectivity Devices such as the Switch.</li> <li>Power Type – whether it is currently operating from primary power or is on backup power (backup power may indicate to the Endpoint Device that it should move to a power conservation mode).</li> </ul>
	<ul> <li>Power Source – whether or not the Endpoint is currently operating from an external power source.</li> <li>Power Priority – the Endpoint Device's power priority (which the Network Connectivity Device may use to prioritize which devices will remain in service during power shortages).</li> <li>Power Value – power requirement, in fractions of Watts, in current configuration.</li> </ul>

GS1350 Series User's Guide

# 27.6 LLDPConfiguration

Use this screen to configure global LLDP settings on the Switch. Click Advanced Application > ILDP > ILDP Configuration (Click Here) to display the screen as shown next.

LIDP Configuration	LOF Basic 1.V Setting Org-specific 1.V S	ittin;
Active	м	
Denvrit nietvol	20 sectors in the	
herenit lold	4 ither	
Denvrift Peloy	2	
Keini falbe Delay	2 extends	
	Apply Centrel	
Pol	Administration Notification	
	Dirable w	
1	loke 👻	
2	La Kale 🗸 🖂 🗌	
×	To Roc 👽	
А	To Ro 😽	
	lette 🖂 🗌	
÷	LENG M	
	Apply Cancel	

Figure 161 Advanced Application > LLDP > LLDP Configuration

 Table 101
 Advanced Application > LLDP > LLDP Configuration

IABEL	DESC RIPTIO N			
Active	Select to enable LLDP on the Switch. It is enabled by default.			
Transmit Interval	Enter how many seconds the Switch waits before sending LLDP packets.			
Transmit Hold	Enter the time-to-live (TTL) multiplier of LLDP frames. The device information on the neighboring devices ages out and is discarded when its corresponding TTL expires. The TTL value is to multiply the TTL multiplier by the LLDP packets transmitting interval.			
Transmit Delay	Enter the delay (in seconds) between successive LLDPDU transmissions initiated by value or status changes in the Switch MIB.			
Reinitialize Delay	Enter the number of seconds for LLDP to wait before initializing on a port.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			
Port	This displays the Switch's port number. * means all ports.			
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.			
	Changes in this row are copied to all the ports as soon as you make them.			

IABEL	DESC RIPTIO N
Admin Status	<ul> <li>Select whether LLDP transmission and/or reception is allowed on this port.</li> <li>Disable - not allowed</li> <li>Tk-Only - transmit only</li> <li>Rx-Only - receive only</li> <li>Tk-Rx - transmit and receive</li> </ul>
Notification	Select whether LLDP notification is enabled on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

#### Table 101 Advanced Application > LLDP > LLDP Configuration (continued)

#### 27.6.1 LLDP Configuration Basic TLV Setting

Use this screen to configure Basic TLV settings. Click Advanced Application > ILDP > ILDP Configuration(Click Here) > Basic TLV Setting to display the screen as shown next.

No. 11	Nexas UV Selling UDP Condependent				
F sa i	Management Address	Fort Description	System Capabilities	System Description	System Name
1		I	11		
1 I	A.	M	М	A.	<b>~</b>
	v <sup>2</sup>	M	М	4	<b>V</b>
× .	Υ.	M	м	× .	×
-		R	<b>M</b>	<u>~</u>	2
>	$\mathbf{Z}$			₹	
0	4	M	M	-	✓
Apply Concel					

The following table describes the labels in this screen.

#### Table 102 Advanced Application > LLDP > LLDP Configuration > Basic TLV Setting

IABEL	DESC RIPIIO N	
Port	This displays the Switch's port number.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.	
	Changes in this row are copied to all the ports as soon as you make them.	
Management Address	Select the check boxes to enable or disable the sending of Management Address TLVs on the ports.	
Port Description	Select the check boxes to enable or disable the sending of Port Description TLVs on the ports.	
System Capabilities	Select the check boxes to enable or to disable the sending of System Capabilities TLVs on the ports.	
System Description	Select the check boxes to enable or to disable the sending of System Description TLVs on the ports.	
System Name	Select the check boxes to enable or to disable the sending of System Name TLVs on the ports.	

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 102 Advanced Application > LLDP > LLDP Configuration > Basic TLV Setting (continued)

## 27.6.2 LLDP Configuration Org-specific TLV Setting

Use this screen to configure organization-specific TLV settings. Click Advanced Application > IIDP > IIDP Configuration (Click Here) > Org-specific TLV Setting to display the screen as shown next.

Figure 163 Advanced Application > LLDP > LLDP Configuration > Org-specific TLV Setting

Dang apa	natur IIV Setting			LLOP Continguations
Post	Doll TV	Dell R.V		
1.041	Port VLAB ID	link Aggregistion	MACONIY	Wate from the State
	_	_	_	_
1	4	I	A	
2 V	4	1		
×		1	× .	
4	7	Г	7	-
>	Ŧ		Ŧ	=
0	*		±	_
		Apply Control		

LABEL	DESC RIPIIO N	
Port	This displays the Switch's port number.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.	
	Changes in this row are copied to all the ports as soon as you make them.	
Dot1 TLV		
Port VLAN ID	Select the check boxes to enable or disable the sending of IEEE 802.1 Port VLAN ID TLVs on the ports. All check boxes in this column are enabled by default.	
Dot3 TLV	·	
Link Aggregation	Select the check boxes to enable or disable the sending of IEEE 802.3 Link Aggregation TLVs on the ports.	
MAC/PHY	Select the check boxes to enable or disable the sending of IEEE 802.3 MAC/PHY Configuration/Status TLVs on the ports. All check boxes in this column are enabled by default.	
Max Frame Size	Select the check boxes to enable or disable the sending of IEEE 802.3 Max Frame Size TLVs on the ports.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

# 27.7 LLDP-MED Configuration

Click Advanced Application > IIDP > IIDP-MED Configuration to display the screen as shown next.

LLOF-MED	Configuration		LLDP
Pati	Netflection	WED TLV Setting	
1.20	Topology Change	toeuhen	Network folloy
		E	_
•	11	1	
2	11	1	
4	11		
5		E	<b>—</b>
4		E	_
	App	iy Cancel	

Figure 164 Advanced Application > LLDP > LLDP-MED Configuration

The following table describes the labels in this screen.

Table 101	Advanced Application > 1	IDD > UDD MED Configuration
	Advanced Application > L	LDP > LLDP-MED Configuration

LABEL	DESC RIPIIO N	
Port	This displays the Switch's port number. Select * to configure all ports simultaneously.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary. Changes in this row are copied to all the ports as soon as you make them.	
Notification		
NOTIFICATION		
Topology Change	Select to enable LLDP-MED topology change traps on this port.	
MED TLV Setting		
Location	Select to enable transmitting LLDP-MED location TLV.	
Network Policy	Select to enable transmitting LLDP-MED Network Policy TLV.	
Apply	Click <b>Apply</b> to save the changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the Save link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

# 27.8 LLDP-MED Network Policy

Click Advanced Application > IIDP > IIDP-MED Network Policy (Click Here) to display the screen as shown next.

ULEP-MID H	March Policy					use
Forf Application type Tag VLAN Tagas Force Force	ko tekségi talégi kogyardi –	<u> </u>				
	256	Const				
Index Parl	Apple as here Lypes	hq.	SLAN	Pearly	m.cz	
	T Se	And Second				

#### Figure 165 Advanced Application > LLDP > LLDP-MED Network Policy

IABEL	DESC RIPTIO N		
Port	Enter the port number to set up the LLDP-MED network policy.		
Application Type	Select the type of application used in the network policy.		
	<ul> <li>voice-signaling</li> <li>guest-voice</li> <li>guest-voice-signaling</li> <li>softphone-voice</li> <li>video-conferencing</li> <li>streaming-video</li> <li>video-signaling</li> </ul>		
Tag	Select to tag or untag in the network policy.		
	<ul><li>tagged</li><li>untagged</li></ul>		
VLAN	Enter the VLAN ID number. It should be from 1 to 4094. For priority tagged frames, enter "0".		
DSCP	Enter the DSCP value of the network policy. The value is defined from 0 through 63 with the 0 representing use of the default DSCP value.		
Priority	Enter the priority value for the network policy.		
Add	Click <b>Add</b> after finish entering the network policy information. A summary table will list all the Switch you have added.		
Cancel	Click Cancel to begin entering the information afresh.		
Index	This field displays the of index number of the network policy. Click an index number to edit the rule.		
Port	This field displays the port number of the network policy.		
Application Type	This field displays the application type of the network policy.		
Tag	This field displays the Tag Status of the network policy.		
VLAN	This field displays the VLANID of the network policy.		
Priority	This field displays the priority value of the network policy.		
DSCP	This field displays the DSCP value of the network policy.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		

Table 105 Advanced Application > LLDP > LLDP-MED Network Policy

Table 105	Advanced Application		Notwork Policy	(continued)
	Advanced Application	I / LLDF / LLDF-IMED	INEIWOIK FUILCY I	(commueu)

LABEL	DESC RIPIIO N
Delete	Check the rules that you want to remove, then click the $\mathbf{De}\mathbf{le}\mathbf{te}$ button.
Cancel	Click Cancel to clear the selected check boxes.

## 27.9 LLDP-MED Location

Click Advanced Application > IIDP > IIDP-MED Location (Click Here) to display the screen as shown next.

Figure 166 Advanced Application > LLDP > LLDP-MED Location	on
--	----

LIDP MED too	ration				LLOP
Part					
Locof on Coloridated	teritodo tengitodo Attitude Datom	wast r motors *	-		
	Country Country		Stote Chy		
	U 4/5m Shroot		Neighton Longuing Shoot Direction		
	Showl Solity		Inaling Shoul Solits		
CMc Address	likuseebiumber		House-Number- Suffa		
Contraction of the second stress	l e netro ark		A dolition al- Location		
	Some		Sp: Code		
	building		Unit		
	rie or		Room Number		
	Floce-Sype		Postal-Community- Name		
	Fost Office Box		Additional Ocide		
BUN Nombor					
			d Contol		
Index Port	Location Cos	ardinates	Civic Address	ELIN Number	
		Del	ere Cancel		

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Port	Enter the port number you want to set up the location within the LLDP-MED network.
Location Coordinates	The LLDP-MED uses geographical coordinates and Civic Address to set the location information of the remote device. Geographical based coordinates includes latitude, longitude, altitude and datum. Civic Address includes Country, State, County, City, Street and other related information.
Latitude	Enter the latitude information. The value should be from 0° to 90°. The negative value represents the South. <ul> <li>north</li> <li>south</li> </ul>
Longitude	Enter the longitude information. The value should be from 0° to 180°. The negative value represents the West.  • west • east
Altitude	Enter the altitude information. The value should be from -2097151 to 2097151 in meters or in floors.   meters floor
Datum	Select the appropriate geodetic datum used by GPS.   WG 584  NAD83-NAVD88  NAD83-MILW
Civic Address	Enter the Civic Address by providing information such as Country, State, County, City, Street Number, ZIP code and other additional information. Enter at least 2 fields in this configuration including the Country. The valid length of the Country field is 2 characters and all other field are up to 32 characters. • Country • State • Country • City • Division • Neighbor • Street • Leading-Street Direction • Street Suffix • House-Number • House-Number • House-Number • Additional-Location • Name • Zip-Code • Building • Unit • Floor • Room-Number • Post-Office-Box • Additional-Code
ELIN Number	Enter a numerical digit string, corresponding to the ELIN identifier which is used during emergency call setup to a traditional CAMA or ISDN trunk-based PSAP. The valid length is from 10 to 25 characters.

Table 106 Advanced Application > LLDP > LLDP-MED Location

G\$1350 Series User's Guide

LABEL	DESC RIPTIO N
Add	Click Add after finish entering the location information.
Cancel	Click Cancel to begin entering the location information afresh.
Index	This lists the index number of the location configuration. Click an index number to view or edit the location.
Port	This lists the port number of the location configuration.
Location Coordinates	This field displays the location configuration information based on geographical coordinates that includes longitude, latitude, altitude and datum.
Civic Address	This field displays the Civic Address for the remote device using information such as Country, State, County, City, Street, Number, ZIP code and additional information.
ELIN Number	This field shows the Emergency Location Identification Number (ELIN), which is used to identify endpoint devices when they issue emergency call services. The valid length is form 10 to 25 characters.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the locations that you want to remove, then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the selected check boxes.

Table 106 Advanced Application > LLDP > LLDP-MED Location (continued)

# C HAPTER 28 Auto PD Recovery

## 28.1 Overview

Things can go wrong with any network devices. A PD (for example, IP camera) may slow down or freeze and need to be restarted if it is overworked or a bug causes a memory leak. When a connected PD ceases to respond, Automatic PD Recovery allows the Switch to restart the PD by turning it off and on without the need for on-site troubleshooting.

## 28.1.1 What You Can Do

Use the Auto PD Recovery screen (Section 28.2 on page 230) to enable and configure automatic PD recovery on the Switch.

# 28.2 Auto PD Recovery

This screen lets you turn on automatic PD recovery on the Switch and its Ethernet ports. You can configure whether the Switch uses LLDP or ping to check the current status of a connected PD.

The ping is sent through the Switch's default management IP address to the designated port. To ping the PD, the port must share the same VLAN as the Switch's management VLAN.




Figure 167 Auto PD Recovery Application

The PD may stop responding to the Switch's detection overping or LLDP during firm ware upgrade. Disable the Auto PD Recovery function to prevent damage to the PD caused by a power cutoff during firm ware upgrade.

To open this screen, click Advanced Application > Auto PD Recovery.

oti t	0.8000	HV.		X(Det	Ŷ				
i.	Activ	-	Heightane	Traing attends Only	Turing) Court	Actua			Kenara Pour Chibreat (200
à.	П	N LUOP				Rebogl-Alam V			
1	2	€ uor O Ping	WAC(2000-1 172.14.20.14	20	а	Reboat Alarm V	600		0
1	82	● LLDP O mig		am.	1	Reboal Aam v	600	<u>r</u>	10
i.	2	<ul> <li>LOP</li> <li>O Rep</li> </ul>	-	20.	3	Reboot Alarm V	000	<u>i</u>	0
į.	10	€ upe O reg		20	5	Rebool-Alam Y	006		10
ŧ.	120	● illor □ Pep		20	3	Rebool Aam V	600		10

Figure 168 Advanced Application > Auto PD Recovery

IABEL	DESC RIPIIO N
Active	Select this option to enable Auto PD Recovery on the Switch.
Port	This field displays the index number of a port on the Switch.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Select Active to enable Auto PD Recovery on the ports.
Mode	Select <b>IIDP</b> to have the Switch passively monitor current status of the connected PD by reading LLDP packets from the PD on the port. The Switch also sends out LLDP packets to the PD to update the <b>Switch Neighbor</b> table on the PD (see Section 7.2.1 on page 84 for details).
	Select $\mathbf{Ping}$ to have the Switch ping the IP address of the connected PD to test whether the PD is reachable or not.
Neighbor	If <b>Mode</b> is set to <b>IIDP</b> , the system name of the connected PD displays automatically.
	If <b>Mode</b> is set to <b>Ping</b> and the PD supports LLDP, the connected PD's IPv4 or IPv6 address to which the Switch sends ping requests will display automatically. If not, enter the IP address manually.
Polling Interval	Specify the number of seconds the Switch waits for a response before sending another ping request.
	For example, the Switch will try to detect the PD status by performing ping requests every 20 seconds.
Polling Count	Specify how many times the Switch is to resend a ping request before considering the PD unreachable.
	For example, If there is no ping reply from the PD after the <b>Polling Interval</b> has elapsed, <b>Polling Count</b> starts from 1. After <b>Polling Count</b> reaches 3, the <b>PD He alth</b> status LED will turn to red in the <b>Status &gt; Neighbor</b> screen (see Section 7.2.1 on page 84 for details). The Switch will then perform your choice in the <b>Action</b> field.

Table 107 Advanced Application > Auto PD Recovery

IABEL	DESC RIPTIO N
Action	Set the action to take when the connected PD has stopped responding.
	Select <b>Reboot-Alam</b> to have the Switch turn OFF the power of the connected PD (the connecting port is detected as link-down) and turn it back ON again to restart the PD after sending an SNMP trap and generating a log message.
	When restarting, the PD entry disappears from the Switch's LLDP table and the <b>PD He a lth</b> status LED will turn to yellow in the <b>Status</b> > <b>Neighbor</b> screen (see Section 7.2.1 on page 84 for details).
	Select $\operatorname{Alam}$ to have the Switch send an SNMP trap and generate a log message.
Resume Polling Interval	Specify the number of seconds the Switch waits before monitoring the PD status again after it restarts the PD on the port.
PD Reboot Count	Specify how many times the Switch attempts to restart the PD on the port.
	The PD Reboot Count will reset
	as soon as a ping is successful,
	<ul> <li>or when any modification to the Auto PD Recovery screen is applied,</li> <li>or after restarting the Switch.</li> </ul>
Resume Power Interval	Specify the number of seconds the Switch waits before supplying power to the connected PD again after it restarts the PD on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 107 Advanced Application > Auto PD Recovery (continued)

#### 28.2.1 Activate the Automatic PD Recovery

Follow the steps below to activate the automatic PD recovery.

1 In the Advanced Application > Auto PD Recovery screen, activate the feature.

Figure 169 Auto PD Recovery (Ping Mode)

e Lantas Lind Namenan Marine	1.000	1.1.1 (F) 1.1.1				Anton	0				_
	1000	0	Nem I	) bequires	2		Later Card	in face	And And		
Weble I to many days		D	₩ubr Orve	1				Address Alleren (*)			
and the function	1	8	Duar Bria	(10) seasor	T	00	5	Recont-Karn (v)	(am. 1		16
de and Marine Constant Anna Angeneration	2		Billion Cirilio			300	3	Report-eren -	480		10
		B	Duor. ≢ining	10,014,45:05	1	200.		(mainware e)	[attent]	<u>6</u>	is
	43	D.	Philips Office			400	1.1	Defaction of	[im ]	5	<u>[ii]</u>
Constant Con	100	(0)	(Pale)	-		-		Reconstances +	660	1.	18

Figure 170	Auto PD Recovery (LLDP Mode)
------------	------------------------------

					0	- 0 0	ere O	Want	0	• 0	-
	-		Ç.	Artis	0						
1	0	-	-	And a state of	-						
	ū	· upp			10001	feecel fame =		1		<u>[]]</u>	Ē
1	B	• JIP O Hag	NAMES -	(a) (ii)		Period Among y	600	Ť.		In	1
F.		<ul> <li>ID*</li> <li>O.ma</li> </ul>		10.11	3	Needon Asses	600	- F		14	1
		t upi Öreş	everal)			Petrockiose >1	law ]	(r		1	
		P subr O fric		10.1	1	Perert Alere =	1000	ţ.		<u>(10</u>	1
1	0	(P sate		28.		Second Agent -		<u>k</u>		100	E
	1400 1 1 1 1 1				Autor PE Removes Acting	Add To Reserve Action Control of the	Anter VI: Remainer Anter	Ann PC former Ann PC former C C C C C C C C C C C C C C C C C C C	Ant C former Ant C former - 1 0 100 - 1 0	Act of Landowse Active Contract of Contrac	Act of Landowse Active Contract of Landowse Active Contrac

- 2 Select the desired ports in the Active column.
- 3 Select the Mode.

When you select **Ping**, the connected PD's IPv4 or IPv6 address to which the Switch sends ping requests will display automatically if the PD supports LLDP. If not, enter the IP address of the PDs in the **Neighbor** field.

The default setting for **Polling Interval** (20 secs) and **Polling Count** (3 times) will cause the Switch to ping the PD status every 20 seconds. If there is no ping reply from the PD, **Polling Count** starts to count from 1. Once **Polling Count** reaches 3, the Switch will cause a **Reboot-Alam** on the PD as selected in **Action**.

When you select **ILDP**, the Switch monitors the PD status by checking incoming LLDP packets every 30 seconds from the PD (default value of transmit interval for LLDP feature).

Likewise, the Switch sends out LLDP packets to the PD every 30 seconds to update the Status > Neighbor screen (see Section 7.2.1 on page 84 for details).

Once the LLDP table's counter reaches the default 120 seconds, the Switch will cause a **Reboot-Alam** on the PD as selected in **Action**.

4 After sending an SNMP trap and generating a log message, the connected PD will restart (the connecting port is detected as link-down).

When restarting, the PD entry disappears from the Switch's LLDP table and the **PD He a lth** status LED will turn to yellow in the **Status > Neighbor** screen.

The Switch will restore power to the PD based on your value for Resume Power Interval.

After the PD is powered on, the Switch resumes detection of the PD status by performing ping requests or checking the LLDP table based on your value for **Resume Polling Interval**.

When the **PD Reboot Count** value is reached, the Switch will no longer perform the PD recovery process. The **PD He a lth** status LED will turn to red in the **Status** > **Neighbor** screen.

- 5 Click Apply to save your changes back to the run-time memory.
- 6 Click the Save link in the upper right corner of the Web Configurator to save your configuration permanently.

Note: In the event of a PD performing firmware upgrade, the PD may stop responding to ping or fail to provide LLDP packets for an extended period of time. When the Switch resets power to the PD before firmware upgrade is finished, it may permanently damage the PD or require a hard reset to recover it. It is strongly advised to disable the Switch's Auto PD Recovery function before upgrading the PD's firmware. This will prevent damage caused by a power cutoff.

# C HAPTER 29 ONVIF

## 29.1 Overview

IP-based security products use a specific protocol for communication. One of the most common protocols is ONVIF (Open Network Video Interface Forum). ONVIF is a standard interface for interoperability of IP-based security products.

When ONVIF is enabled and configured, the Switch can obtain information from connected ONVIFcompatible devices, such as a device's system name and IP address. This lets you know which ONVIFcompatible devices, for example IP cameras and NVR (network video recorders), are connected to the Switch.

## 29.1.1 What You Can Do

Use the **ONVIF** screen (Section 29.2 on page 235) to enable the ONVIF protocol on the Switch.

## 29.2 ONVIFScreen

This screen lets you turn on the ONVIF protocol on the Switch and its Ethernet ports.

To open this screen, click **Advanced Application** > **ONVIF**.

Figure 171	Advanced Application > ONVIF
------------	------------------------------



LABEL	DESC RIPTIO N
Active	Select Active to allow this Switch to send ONVIF packets to discover or scan for ONVIF- compatible IP-based security devices connected to its ports. Make sure to enter the port numbers in <b>Port</b> to allow discovery of ONVIF-compatible devices.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.
VLAN	
VID	Enter the ID number of the VLAN to run ONVIF.
Port	Enter the port numbers to allow discovery of ONVIF-compatible devices. You can enter multiple ports separated by comma (,) or hyphen (–) without spaces. For example, enter "3–5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Add	Click this to create a new entry or to update an existing one. This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to reset the fields to your previous configuration.
Clear	Click Clear to reset the fields to the factory defaults.
Index	This is the index number of the ONVIF entry in the table.
VID	This field displays the VLAN to which the ports belong.
Port	This field displays the ports to which the Switch applies the settings.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove, then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the check boxes.

Table 108 Advanced Application > ONVIF

# C HAPTER 30 Differentia te d Servic e s

## 30.1 DiffServ Overview

This chapter shows you how to configure Differentiated Services (DiffServ) on the Switch.

Quality of Service (QoS) is used to prioritize source-to-destination traffic flows. All packets in the flow are given the same priority. You can use CoS (class of service) to give different priorities to different packet types.

DiffServ is a class of service (CoS) model that marks packets so that they receive specific per-hop treatment at DiffServ-compliant network devices along the route based on the application types and traffic flow. Packets are marked with DiffServ Code Points (DSCPs) indicating the level of service desired. This allows the intermediary DiffServ-compliant network devices to handle the packets differently depending on the code points without the need to negotiate paths or remember state information for every flow. In addition, applications do not have to request a particular service or give advanced notice of where the traffic is going.

#### 30.1.1 What You Can Do

- Use the **DiffServ** screen (Section 30.2 on page 238) to activate DiffServ to apply marking rules or IEEE 802.1p priority mapping on the Switch.
- Use the DSCP Setting screen (Section 30.3.1 on page 240) to change the DSCP-IEEE 802.1p mapping.

#### 30.1.2 What You Need to Know

Read on for concepts on Differentiated Services that can help you configure the screens in this chapter.

#### DSCP and Per Hop Behavior

DiffServ defines a new DS (Differentiated Services) field to replace the Type of Service (ToS) field in the IP header. The DS field contains a 6-bit DSCP field which can define up to 64 service levels and the remaining 2 bits are defined as currently unused (CU). The following figure illustrates the DS field.

Figure 172 DiffServ: Differentiated Service Field


DSCP (6 bits)	CU (2 bits)

DSCP is backward compatible with the three precedence bits in the ToS octet so that non-DiffServ compliant, ToS-enabled network device will not conflict with the DSCP mapping.

The DSCP value determines the PHB (Per-Hop Behavior), that each packet gets as it is forwarded across the DiffServ network. Based on the marking rule different kinds of traffic can be marked for different priorities of forwarding. Resources can then be allocated according to the DSCP values and the configured policies.

#### DiffServ Network Example

The following figure depicts a DiffServ network consisting of a group of directly connected DiffServcompliant network devices. The boundary node (A in Figure 173) in a DiffServ network classifies (marks with a DSCP value) the incoming packets into different traffic flows (**Platinum**, **Gold**, **Silver**, **Bronze**) based on the configured marking rules. A network administrator can then apply various traffic policies to the traffic flows. An example traffic policy, is to give higher drop precedence to one traffic flow over others. In our example, packets in the **Bronze** traffic flow are more likely to be dropped when congestion occurs than the packets in the **Platinum** traffic flow as they move across the DiffServ network.





# 30.2 Activating DiffServ

Activate DiffServ to apply marking rules or IEEE 802.1p priority mapping on the Switch.

Click IP Applic a tion > DiffServ in the navigation panel to display the screen as shown.

Diffserv				DSCP Setting
Active				
	Port		Active	
	*			
	1		Г	
	2			
	3		L	
	4			
	5		Г	
	ő			
		Apply Cancel		

Figure 174 IP Application > DiffServ

The following table describes the labels in this screen.

Table 109 IP Application > Diff	tServ
---------------------------------	-------

IABEL	DESC RIPTIO N
Active	Select this option to enable DiffServ on the Switch.
Port	This field displays the index number of a port on the Switch.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Select Active to enable Diffserv on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 30.3 DSCP Settings

You can configure the DSCP to IEEE 802.1p mapping to allow the Switch to prioritize all traffic based on the incoming DSCP value according to the DiffServ to IEEE 802.1p mapping table.

The following table shows the default DSCP-to-IEEE802.1p mapping.

				ř – – – – – – – – – – – – – – – – – – –		10 17	10 55	<i></i>
DSCP VALUE	0 – 7	8 – 15	16 – 23	24 – 31	32 – 39	40 – 47	48 – 55	56 – 63
IEEE 802.1p	0	1	2	3	4	5	6	7

Table 110 Default DSCP-IEEE 802.1p Mapping

## 30.3.1 Configuring DSCP Settings

To change the DSCP-IEEE 802.1p mapping click the **DSCP Setting** link in the **DiffServ** screen to display the screen as shown next.

Figure 175 IP Application > DiffServ > DSCP Setting

DSCP Sering Differ										
DSCP :	w 502.	ip Ma	pping.							
U.	0 <	1	2.1	2.01		0.5	4 3 1	5 0 4	6 Q H	2 0 M
×	1.5	Y.	1 7	10.1	•	1.1	2 1 7	IN L.F.	10 1 2	10 $1.5$
16	2.5	17	2.5	10 23	- 15	2.5	20 2.2	21 2 4	22.2.2	23 2 5
24	> r	25	3.1	25 25	- 22	S(r)	33 3 4	25 3 5	30 2 1	21 3 5
80	4.6	78	4 T	- 22 A 3	- 55	4.0	18 A.T.	88 A.F.		$-\infty < \pi$
10	20.5	- 41	5 1	12 A 3		20.5	41 5 1	- 🗇 🛛 🔊	in Art	-17 - 5 < r
48	$\varphi_{i}(r)$	- 42	\$ X.	- <b>30</b> - 611	e ol	$\Phi_{i}(\mathbf{r})$	52 5 1	- A - C	56 S.C.	55 (6 r.
1.0	$\overline{\mathcal{T}}(\mathbf{r})$	$-h_{i} r_{i}$	7 7	. as 7.	1.0	$\overline{T}$ $\overline{T}$	-0 7 T	AL 7.5	- W 7 *	- ex 🗵 🗉
						947	Chan I.			
L										

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
0 63	This is the DSCP classification identification number.
	To set the IEEE 802.1p priority mapping, select the priority level from the drop-down list box.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

#### Table 111 IP Application > DiffServ > DSCP Setting

# C HA PTER 31 DHC P

# 31.1 DHCPOverview

This chapter shows you how to configure the DHCP feature.

DHCP (Dynamic Host Configuration Protocol RFC 2131 and RFC 2132) allows individual computers to obtain TCP/IP configuration at start-up from a server. If you configure the Switch as a DHCP relay agent, then the Switch forwards DHCP requests to DHCP server on your network. If you do not configure the Switch as a DHCP relay agent then you must have a DHCP server in the broadcast domain of the client computers or else the client computers must be configured manually.

## 31.1.1 What You Can Do

- Use the DHC Pv4 Status screen (Section 31.3 on page 242) to display the relay mode.
- Use the DHCPv4 Relay screen (Section 31.4 on page 242) to enable and configure global DHCPv4 relay.
- Use the **VIAN Setting** screen (Section 31.4.6 on page 248) to configure your DHCPv4 settings based on the VLAN domain of the DHCPv4 clients.
- Use the DHCPv6 Relay screen (Section 31.5 on page 251) to enable and configure DHCPv6 relay.

## 31.1.2 What You Need to Know

Read on for concepts on DHCP that can help you configure the screens in this chapter.

#### DHC P Modes

If there is already a DHCP server on your network, then you can configure the Switch as a DHCP relay agent. When the Switch receives a request from a computer on your network, it contacts the DHCP server for the necessary IP information, and then relays the assigned information back to the computer.

#### DHC Pv4 Configuration Options


The DHCPv4 configuration on the Switch is divided into Global and VIAN screens. The screen you should use for configuration depends on the DHCP services you want to offer the DHCP clients on your network. Choose the configuration screen based on the following criteria:

- Global The Switch forwards all DHCP requests to the same DHCP server.
- VIAN The Switch is configured on a VLAN by VLAN basis. The Switch can be configured to relay DHCP requests to different DHCP servers for clients in different VLAN.

241

## 31.2 DHCPConfiguration

Click  $\mathbf{IPApplication} > \mathbf{DHCP}$  in the navigation panel to display the screen as shown. Click the link next to  $\mathbf{DHCPv4}$  to open screens where you can enable and configure  $\mathbf{DHCPv4}$  relay settings and create option 82 profiles. Click the link next to  $\mathbf{DHCPv6}$  to open a screen where you can configure  $\mathbf{DHCPv6}$  relay settings.



MULT		_
MILL C	Washington (1997)	
THORAE .	Cite Anna	

## 31.3 DHC Pv4 Status

Click IP Application > DHCP > DHCPv4 in the navigation panel. The DHCP Status screen displays.

Figure 177	IP Application > DHCP > DHCPv4 Status
------------	---------------------------------------

Clobal	VLAN

The following table describes the labels in this screen.

Table 112 IP Application > DHCP > DHCPv4 Status

LABEL	DESC RIPTIO N
Relay Status	This section displays configuration settings related to the Switch's DHCP relay mode.
Relay Mode	This field displays:
	<b>None</b> – if the Switch is not configured as a DHCP relay agent.
	$G \log a l$ – if the Switch is configured as a DHCP relay agent only.
	<b>VIAN</b> – followed by a VLAN ID or multiple VLAN IDs if it is configured as a relay agent for specific VLANs.

## 31.4 DHC Pv4 Re lay

Configure DHCP relay on the Switch if the DHCP clients and the DHCP server are not in the same broadcast domain. During the initial IP address leasing, the Switch helps to relay network information (such as the IP address and subnet mask) between a DHCP client and a DHCP server. Once the DHCP client obtains an IP address and can connect to the network, network information renewal is done between the DHCP client and the DHCP server without the help of the Switch.

The Switch can be configured as a global DHCP relay. This means that the Switch forwards all DHCP requests from all domains to the same DHCP server. You can also configure the Switch to relay DHCP information based on the VLAN membership of the DHCP clients.

242

### 31.4.1 DHC Pv4 Re lay Agent Information

The Switch can add information about the source of client DHCP requests that it relays to a DHCP server by adding **Relay Agent Information**. This helps provide authentication about the source of the requests. The DHCP server can then provide an IP address based on this information. Please refer to RFC 3046 for more details.

The DHCP **Relay Agent Information** feature adds an Agent Information field (also known as the **Option 82** field) to DHCP requests. The **Option 82** field is in the DHCP headers of client DHCP request frames that the Switch relays to a DHCP server.

**Relay Agent Information** can include the **System Name** of the Switch if you select this option. You can change the **System Name** in **Basic Settings** > **General Setup**.

The following describes the DHCP relay agent information that the Switch sends to the DHCP server:

FIELD IABELS	DESC RIPIIO N
Slot ID	(1 byte) This value is always 0 for stand-alone switches.
Port ID	(1 byte) This is the port that the DHCP client is connected to.
VLAN ID	(2 bytes) This is the VLAN that the port belongs to.
Information	(up to 64 bytes) This optional, read-only field is set according to system name set in <b>Basic</b> Settings > General Setup.

Table 113	Relay Agent Information
-----------	-------------------------

#### 31.4.1.1 DHC Pv4 Relay Agent Information Format

A DHCP Relay Agent Information option has the following format.

#### Table 114 DHCP Relay Agent Information Option Format

Code	Length	il	i2	iN
(82)	(N)			

i1, i2 and iN are DHCP relay agent sub-options, which contain additional information about the DHCP client. You need to define at least one sub-option.

#### 31.4.1.2 Sub-Option Format

There are 2 types of sub-option: "Agent Circuit ID Sub-option" and "Agent Remote ID Sub-option". They have the following formats.

 Table 115
 DHCP Relay Agent Circuit ID Sub-option Format

SubOpt Code	Length	Value
1	Ν	Slot ID, Port ID, VLAN ID, System Name or String
(1 byte)	(1 byte)	

 Table 116
 DHCP Relay Agent Remote ID Sub-option Format

SubOpt Code	Length	Value
2	Ν	MAC Address or String
(1 byte)	(1 byte)	

The 1 in the first field identifies this as an Agent Circuit ID sub-option and two identifies this as an Agent Remote ID sub-option. The next field specifies the length of the field.

## 31.4.2 DHC Pv4 Option 82 Profile

Use this screen to create DHCPv4 option 82 profiles. Click **IP** Applic ation > DHCP > DHCPv4 in the navigation panel and click the **Option 82 Profile** link to display the screen as shown.

Figure 178 IP Application > DHCP > DHCPv4 > Option 82 Profile

DHCP Option 62	Profile				DHCFSetti
otile Selup					
Nome					
		10 <b>G</b> o	UI-		
CREWIND)			port 🗌 vian 💷 h	(STICMB	
		4000			
		🗍 ten			
Perighe-III		H mo	•		
		-quint2			
		Ann Course			
	1.50		- C.C.B.L.L.		
Piofile Name		cut lit	Remi	ite III	
Contraction of the	(noher	( aread	Inside	Time	. 11
defcult	(Vec)	sichport, vien	5. <b>1</b> 465		
rieboul/2	174e	hostnomp	40	33	- 18
		Contraction of the second			
		postorena municipal			
		Deficier Courses			

Table 117 IP Application > DHCP > DHCPv4 > Option 82 Profile

LABEL	DESC RIPTIO N	
Name	Enter a descriptive name for the profile for identification purposes. You can use up to 32 ASC characters. Spaces are allowed.	
Circuit-ID	Use this section to configure the Circuit ID sub-option to include information that is specific to the relay agent (the Switch).	
Enable	Select this option to have the Switch add the Circuit ID sub-option to client DHCP requests that it relays to a DHCP server.	
slot-port	Select this option to have the Switch add the number of port that the DHCP client is connected to.	
vlan	Select this option to have the Switch add the ID of VLAN which the port belongs to.	
hostname	This is the system name you configure in the $Basic Setting > General Setup$ screen.	
	Select this option for the Switch to add the system name to the client DHCP requests that it relays to a DHCP server.	
string	Enter a string of up to 64 ASCII characters that the Switch adds into the client DHCP requests. Spaces are allowed.	
Remote-ID	Use this section to configure the Remote ID sub-option to include information that identifies the relay agent (the Switch).	
Enable	Select this option to have the Switch append the Remote ID sub-option to the option 82 field of DHCP requests.	
mac	Select this option to have the Switch add its MAC address to the client DHCP requests that it relays to a DHCP server.	

IABEL	DESC RIPIIO N
string	Enter a string of up to 64 ASCII characters for the remote ID information in this field. Spaces are allowed.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to their last saved values.
Profile Name	This field displays the descriptive name of the profile. Click the name to change the settings.
Circuit-ID	
Enable	This field displays whether the Circuit ID sub-option is added to client DHCP requests.
Field	This field displays the information that is included in the Circuit ID sub-option.
Remote-ID	
Enable	This field displays whether the Remote ID sub-option is added to client DHCP requests.
Field	This field displays the information that is included in the Remote ID sub-option.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove and then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the selected check boxes.

Table 117 IP Application > DHCP > DHCPv4 > Option 82 Profile (continued)

### 31.4.3 Configuring DHC Pv4 Global Relay

Use this screen to configure global DHCPv4 relay. Click IP Applic a tion > DHCP > DHCPv4 in the navigation panel and click the Global link to display the screen as shown.

DITC? Selay	Solar Fee
Active	1
Pernote D. KDrServer I	0.0000
Pernote D. KD Server 2	0.0000
Permote D. KDP Server 0	0.0000
Contract 27 Product	т
	spole Convel

 Table 118
 IP Application > DHCP > DHCPv4 > Global Relay

LABEL	DESC RIPTIO N
Active	Select this check box to enable DHCPv4 relay.
Remote DHCP Server 1 3	Enter the IP address of a DHCPv4 server in dotted decimal notation.
Option 82 Profile	Select a pre-defined DHCPv4 option 82 profile that the Switch applies to all ports. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 118 IP Application > DHCP > DHCPv4 > Global Relay (continued)

### 31.4.4 Configure DHC Pv4 Global Relay Port

Use this screen to apply a different DHCP option 82 profile to certain ports on the Switch. To open this screen, click **IP Applic ation > DHCP > DHCPv4 > Global > Port**.

Figure 180 IP Application > DHCP > DHCPv4 > Global > Port



Table 119	IP Application > DHCP > DHCPv4 > Global > Port
	in Application Brief Plant Brief Plant Brief Plant

IABEL	DESC RIPTIO N			
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.			
	You can enter multiple ports separated by (no space) comma (,) or hyphen (–). For example, enter "3–5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.			
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to the specified ports. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.			
	The profile you select here has priority over the one you select in the DHCP > DHCPv4 > Global screen.			
Add	Click this to create a new entry or to update an existing one.			
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click this to reset the values above based on the last selected entry or, if not applicable, to clear the fields above.			
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.			
Index	This field displays a sequential number for each entry. Click an index number to change the settings.			
Port	This field displays the ports to which the Switch applies the settings.			
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports.			


LABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Select the entries that you want to remove, then click the $\mathbf{De}  \mathbf{le}  \mathbf{te}$ button to remove the selected entries from the table.
Cancel	Click this to clear the check boxes above.

Table 119 IP Application > DHCP > DHCPv4 > Global > Port (continued)

### 31.4.5 Global DHCP Relay Configuration Example

The follow figure shows a network example where the Switch is used to relay DHCP requests for the **VIAN1** and **VIAN2** domains. There is only one DHCP server that services the DHCP clients in both domains.





Configure the **DHCP Relay** screen as shown. Make sure you select a DHCP option 82 profile (**default1** in this example) to set the Switch to send additional information (such as the VLAN ID) together with the DHCP requests to the DHCP server. This allows the DHCP server to assign the appropriate IP address according to the VLAN ID.

DECOR Bridary	Status, Par
Sets :	*
Presente DHOR Service 1	192 160 1 100
Presente D-CROMANNE V	0.000
Presente D-CRAmere X	0.000
Option/021holid	Uclaul I EXAMPLE
	April 8 Contract 1

Figure 182 DHCP Relay Configuration Example

#### 31.4.6 DHC Pv4 VIAN Setting

Use this screen to configure your DHCP settings based on the VLAN domain of the DHCP clients. Click IP Applic a tion > DHCP > DHCP v4 in the navigation panel, then click the VLAN link In the DHCP Status screen that displays.

Note: You must set up a management IP address for each VLAN that you want to configure DHCP settings for on the Switch. See Section 5.1.3 on page 71 for information on how to do this.

Figure 183	IP Application > DHCP > DHCPv4 > VLAN
------------	---------------------------------------

VLAN Setting		Status Dati
VID to tay		
Harmatic 1966 Warns in	0.000	
Harmatic 1968 Warms in St	0.000	
A construction DHE 24 years of 2	0.000	
Option/02Protic	P	
	ed Conest Visor	
VID	Type DHCP Status	-
	Delete Canee	

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N			
VID	Enter the ID number of the VLAN to which these DHCP settings apply.			
Remote DHCP Server 1 3	Enter the IP address of a DHCP server in dotted decimal notation.			
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to all ports in this VLAN. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.			
Add	Click this to create a new entry or to update an existing one.			
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.			
VID	This field displays the ID number of the VLAN group to which this DHCP settings apply.			
Туре	This field displays <b>Re la y</b> for the DHCP mode.			
DHCP Status	For DHCP server configuration, this field displays the starting IP address and the size of the IP address pool.			
	For DHCP relay configuration, this field displays the first remote DHCP server IP address.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			

Table 120 IP Application > DHCP > DHCPv4 > VLAN

GS1350 Series User's Guide

Table 120 IP Application > DHCP > DHCPv4 > VLAN (continued)

IABEL	DESC RIPIIO N
Delete	Select the configuration entries you want to remove and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove them.
Cancel	Click Cancel to clear the check boxes.

### 31.4.7 Configure DHC Pv4 VIAN Port

Use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN. To open this screen, click IP Applic a tion > DHCP > DHCPv4 > VIAN > Port.

Figure 184 IP Application > DHCP > DHCPv4 > VLAN > Port

l tari			VDA	N Selfing
ALC: NO				
Op for 62 No	0v	P		
		Add Tanke Clear		
hides	V D	Pal	Profile Name	-
		Detate Centred		

Table 121	IP Application > DHCP > DHCPv4 > VLAN > Port

IABEL	DESC RIPTIO N		
VID	Enter the ID number of the VLAN you want to configure here.		
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.		
	You can enter multiple ports separated by (no space) comma (,) or hyphen (–). For example, enter "3–5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.		
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to the specified ports in this VLAN. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.		
	The profile you select here has priority over the one you select in the DHC P > DHC Pv4 > VIAN screen.		
Add	Click this to create a new entry or to update an existing one.		
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click this to reset the values above based on the last selected entry or, if not applicable, to clear the fields above.		
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.		
Index	This field displays a sequential number for each entry. Click an index number to change the settings.		
VID	This field displays the VLAN to which the ports belongs.		
Port	This field displays the ports to which the Switch applies the settings.		

LABEL	DESC RIPTIO N
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports in this VLAN.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Select the entries that you want to remove, then click the $\mathbf{De}  \mathbf{le}  \mathbf{te}$ button to remove the selected entries from the table.
Cancel	Click this to clear the check boxes above.

Table 121 IP Application > DHCP > DHCPv4 > VLAN > Port (continued)

## 31.4.8 Example: DHCP Relay for Two VIANs

The following example displays two VLANs (VIDs 1 and 2) for a campus network. Two DHCP servers are installed to serve each VLAN. The system is set up to forward DHCP requests from the dormitory rooms (VLAN 1) to the DHCP server with an IP address of 192.168.1.100. Requests from the academic buildings (VLAN 2) are sent to the other DHCP server with an IP address of 172.16.10.100.




Figure 185 DHCP Relay for Two VLANs

For the example network, configure the VIAN Setting screen as shown.

MLAN Setting		~	·	alatar ter
ND Relay				
Protocio D+C P Scores	1	0000		
Protocio Del Pictura	Presente D-CROMAN V			
Protocia D-C Pitanaa	8	0000		
Option 60 Incite				
	And Ta	ee Clear	EXAM	PLE
VID	lype		BHCF Malvs	
1	4 - hry		147 TAX 1 1181	U
	Delate	Convel		

Figure 186 DHCP Relay for Two VLANs Configuration Example

## 31.5 DHC Pv6 Re lay

A DHCPv6 relay agent is on the same network as the DHCPv6 clients and helps forward messages between the DHCPv6 server and clients. When a client cannot use its link-local address and a wellknown multicast address to locate a DHCPv6 server on its network, it then needs a DHCPv6 relay agent to send a message to a DHCPv6 server that is not attached to the same network.

The DHCPv6 relay agent can add the remote identification (remote-ID) option and the interface-ID option to the Relay-Forward DHCPv6 messages. The remote-ID option carries a user-defined string, such as the system name. The interface-ID option provides slot number, port information and the VLAN ID to the DHCPv6 server. The remote-ID option (if any) is stripped from the Relay-Reply messages before the relay agent sends the packets to the clients. The DHCPv6 server copies the interface-ID option from the Relay-Forward message into the Relay-Reply message and sends it to the relay agent. The interface-ID should not change even after the relay agent restarts.

Use this screen to configure DHCPv6 relay settings for a specific VLAN on the Switch. Click **IP** Applic ation > **DHCP** > **DHCPv6** in the navigation panel to display the screen as shown.

Figure 187	IP Application > DHCP > DHCPv6 Relay
------------	--------------------------------------

DHCI'vé Relay	,	DHCP
M I		
Hoj na Addaw		
- Optime -	📄 Interiose D Remote ID	
	Add Concel Cent	
VID Helper Address	Interface ID Bernole ID	•
	Este e Cancel	

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
VID	Enter the ID number of the VLAN you want to configure here.
Helper Address	Enter the remote DHCPv6 server address for the specified VLAN.
Options	
Interface ID	Select this option to have the Switch add the interface-ID option in the DHCPv6 requests from the clients in the specified VLAN before the Switch forwards them to a DHCPv6 server.
Remote ID	Enter a string of up to 64 printable characters to be carried in the remote-ID option. The Switch adds the remote-ID option in the DHCPv6 requests from the clients in the specified VLAN before the Switch forwards them to a DHCPv6 server.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the $\mathbf{Save}$ link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to their last saved values.
Clear	Click Clear to reset the fields to the factory defaults.
VID	This field displays the VLAN ID number. Click the VLAN ID to change the settings.
Helper Address	This field displays the IPv6 address of the remote DHCPv6 server for this VLAN.
Interface ID	This field displays whether the interface-ID option is added to DHCPv6 requests from clients in this VLAN.
Remote ID	This field displays whether the remote-ID option is added to DHCPv6 requests from clients in this VLAN.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Check the entries that you want to remove and then click the <b>Delete</b> button.
Cancel	Click Cancel to clear the selected check boxes.

Table 122 IP Application > DHCP > DHCPv6 Relay

# C HAPTER 32 ARP Se tup

# 32.1 ARP Overview

Address Resolution Protocol (ARP) is a protocol for mapping an Internet Protocol address (IP address) to a physical machine address, also known as a Media Access Control or MAC address, on the local area network.

An IP (version 4) address is 32 bits long. In an Ethernet LAN, MAC addresses are 48 bits long. The ARP table maintains an association between each MAC address and its corresponding IP address.

## 32.1.1 What You Can Do

Use the **ARP Leaming** screen (Section 32.2.1 on page 255) to configure ARP learning mode on a per-port basis.

## 32.1.2 What You Need to Know

Read on for concepts on ARP that can help you configure the screen in this chapter.

#### 32.1.2.1 How ARP Works

When an incoming packet destined for a host device on a local area network arrives at the Switch, the Switch looks in the ARP Table and if it finds the address, it sends it to the device.

### 32.1.2.2 ARP Learning Mode


The Switch supports three ARP learning modes: ARP-Reply, Gratuitous-ARP, and ARP-Request.

#### ARP-Reply

The Switch in ARP-Reply learning mode updates the ARP table only with the ARP replies to the ARP requests sent by the Switch. This can help prevent ARP spoofing.

In the following example, the Switch does not have IP address and MAC address mapping information for hosts **A** and **B** in its ARP table, and host **A** wants to ping host **B**. Host **A** sends an ARP request to the

Switch and then sends an ICMP request after getting the ARP reply from the Switch. The Switch finds no matched entry for host **B** in the ARP table and broadcasts the ARP request to all the devices on the LAN. When the Switch receives the ARP reply from host **B**, it updates its ARP table and also forwards host **A**'s ICMP request to host **B**. After the Switch gets the ICMP reply from host **B**, it sends out an ARP request to get host **A**'s MAC address and updates the ARP table with host **A**'s ARP reply. The Switch then can forward host **B**'s ICMP reply to host **A**.



#### G ra tuito us-ARP

A gratuitous ARP is an ARP request in which both the source and destination IP address fields are set to the IP address of the device that sends this request and the destination MAC address field is set to the broadcast address. There will be no reply to a gratuitous ARP request.


A device may send a gratuitous ARP packet to detect IP collisions. If a device restarts or its MAC address is changed, it can also use gratuitous ARP to inform other devices in the same network to update their ARP table with the new mapping information.

In Gratuitous-ARP learning mode, the Switch updates its ARP table with either an ARP reply or a gratuitous ARP request.

#### ARP-Request

When the Switch is in ARP-Request learning mode, it updates the ARP table with both ARP replies, gratuitous ARP requests and ARP requests.

Therefore in the following example, the Switch can learn host  $\mathbf{A}$ 's MAC address from the ARP request sent by host  $\mathbf{A}$ . The Switch then forwards host  $\mathbf{B}$ 's ICMP reply to host  $\mathbf{A}$  right after getting host  $\mathbf{B}$ 's MAC



# 32.2 ARP Setup

Click IP Applic a tion > ARP Setup in the navigation panel to display the screen as shown. Click the link next to ARP Ie a ming to open a screen where you can set the ARP learning mode for each port.



ARP Setup		
ARP Learning	ClickHare	

## 32.2.1 ARP Learning

Use this screen to configure each port's ARP learning mode. Click the link next to **ARP Le a ming** in the **IP Applic a tion** > **ARP Se tup** screen to display the screen as shown next.

4KWI musing	ABY Schop
Port	ARP bearing Mode
	ABC Donly 😽
1	AR 1-Metaly
2	ARE socily in M
A	ART Dolaky 🔜
4	ART Dooly 🛛 💌
5	AR 's lie cycles i 🛛 🗠
5	ARE socially in Million
Aprelo	Cancel

Figure 189 IP Application > ARP Setup > ARP Learning

Table 123 IP Application > ARP Setup > ARP Learning

IABEL	DESC RIPIIO N		
Port	This field displays the port number.		
*	Settings in this row apply to all ports.		
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.		
	Changes in this row are copied to all the ports as soon as you make them.		
ARP Learning	Select the ARP learning mode the Switch uses on the port.		
Mode	Select $\mathbf{ARP}$ - $\mathbf{Re} \mathbf{p} \mathbf{ly}$ to have the Switch update the ARP table only with the ARP replies to the ARP requests sent by the Switch.		
	Select <b>G</b> m tuitous-ARP to have the Switch update its ARP table with either an ARP reply or a gratuitous ARP request.		
	Select <b>ARP-Request</b> to have the Switch update the ARP table with both ARP replies, gratuitous ARP requests and ARP requests.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click Cancel to begin configuring this screen afresh.		

# C HAPTER 33 Maintenance

# 33.1 Overview

This chapter explains how to configure the screens that let you maintain the firmware and configuration files.

## 33.1.1 What You Can Do

- Use the **Maintenance** screen (Section 33.2 on page 257) to manage firmware and your configuration files.
- Use the Firm ware Upgrade screen (Section 33.3 on page 260) to upload the latest firmware.
- Use the **Restore Configuration** screen (Section 33.4 on page 261) to upload a stored device configuration file.
- Use the **Backup Configuration** screen (Section 33.5 on page 262) to save your configurations for later use.
- Use the **Erase Running-Configuration** screen (Section 33.2.1 on page 258) to reset the configuration to the Zyxel default configuration settings.
- Use the **Save Configuration** screen (Section 33.2.2 on page 259) to save the current configuration settings to a specific configuration file on the Switch.
- Use the **Reboot System** screen (Section 33.2.3 on page 259) to restart the Switch without physically turning the power off and load a specific configuration file.
- Use the Tech-Support screen (Section 33.6 on page 262) to create reports for customer support if there are problems with the Switch.
- Use the Certificates screen (Section 33.7 on page 264) to see the Certificate screen and import the Switch's CA-signed certificates.

# 33.2 Maintenance Settings

Use this screen to manage firmware and your configuration files. Click **Management** > **Maintenance** in the navigation panel to open the following screen.

257

Figure 1	190	Management >	Maintenance
----------	-----	--------------	-------------

Limmwore Upgrade	Districtione
Restore Configuration	Citch Hone
Rockup Contiguration	Click Hww
<b>Erave Ranning Configuration</b>	Click Here
Save Configuration	Config 1 Config 2 Castom Detaut
Rebeel System Concil: Configuration 1	Config 1 Config 2 Licetory Decoult Contorn Default
lech-Support	Datk Here
Certificates	Citck Hore

Table 124	Management > Maintenance

IABEL	DESC RIPIIO N
Firmware Upgrade	Click Click Here to go to the Firmware Upgrade screen.
Restore Configuration	Click Click Here to go to the Restore Configuration screen.
Backup Configuration	Click Click Here to go to the Backup Configuration screen.
Erase Running- Configuration	Click Click Here to reset the configuration to the Zyxel default configuration settings.
Save	Click <b>Config 1</b> to save the current configuration settings to <b>Configuration 1</b> on the Switch.
Configuration	Click <b>Config 2</b> to save the current configuration settings to <b>Configuration 2</b> on the Switch.
	Click <b>Custom Default</b> to save the current configuration settings to a customized default file on the Switch. This file can be used instead of the Zyxel factory default configuration file.
Reboot System	Click <b>Config 1</b> to reboot the Switch and load <b>Configuration 1</b> on the Switch.
	Click <b>Config 2</b> to reboot the Switch and load <b>Configuration 2</b> on the Switch.
	Click Factory Default to reboot the Switch and load the Zyxel factory default configuration settings on the Switch.
	Click $Custom$ Default to reboot the Switch and load a saved customized default file on the Switch.
	Note: Make sure to click the <b>Save</b> button in any screen to save your settings to the current configuration on the Switch.
Current	This field displays which configuration ( <b>Configuration 1</b> or <b>Configuration 2</b> ) is currently operating on the Switch.
Tech-Support	Click <b>Click Here</b> to see the Tech-Support screen. You can set CPU and memory thresholds for log reports and download related log reports for issue analysis. Log reports include CPU history and utilization, crash and memory.
Certificates	Click Click Here to see the Certificate screen and import the Switch's CA-signed certificates.

## 33.2.1 Erase Running-Configuration

Follow the steps below to reset the Switch back to the Zyxel default configuration settings.

- 1 In the **Maintenance** screen, click the **Click Here** button next to **Erase Running-Configuration** to clear all Switch configuration information you configured and return to the Zyxel default configuration settings.
- 2 Click **OK** to reset all Switch configurations to the Zyxel default configuration settings.

Figure 191 Erase Running-Configuration: Confirmation



3 In the Web Configurator, click the Save button in the top of the screen to make the changes take effect. If you want to access the Switch Web Configurator again, you may need to change the IP address of your computer to be in the same subnet as that of the default Switch IP address (192.168.1.1).

### 33.2.2 Save Configuration

Click **Config 1** to save the current configuration settings permanently to **Configuration 1** on the Switch. These configurations are set up according to your network environment.

Click **Config 2** to save the current configuration settings permanently to **Configuration 2** on the Switch. These configurations are set up according to your network environment.

Click **Custom Default** to save the current configuration settings permanently to a customized default file on the Switch.

Note: If a customized default file was not saved, clicking **Custom Default** loads the factory default configuration on the Switch.

Alternatively, click **Save** on the top right-hand corner in any screen to save the configuration changes to the current configuration.

Note: Clicking the **Apply** or **Add** button does NOT save the changes permanently. All unsaved changes are erased after you reboot the Switch.

#### 33.2.3 Reboot System

**Reboot System** allows you to restart the Switch without physically turning the power off. It also allows you to load configuration one (**Config 1**), configuration two (**Config 2**), a **Custom Default** or the factory default configuration when you reboot. Follow the steps below to reboot the Switch.

1 In the **Maintenance** screen, click a configuration button next to **Reboot System** to reboot and load that configuration file. The following screen displays.

Figure 192 Reboot System: Confirmation



2 Click **OK** again and then wait for the Switch to restart. This takes up to 2 minutes. This does not affect the Switch's configuration.

Click Config 1 and follow steps 1 to 2 to reboot and load configuration one on the Switch.

Click Config 2 and follow steps 1 to 2 to reboot and load configuration two on the Switch.

Click Factory Default and follow steps 1 to 2 to reboot and load Zyxel factory default configuration settings on the Switch.

Click **Custom Default** and follow steps 1 to 2 to reboot and load a customized default file on the Switch. This will save the custom default configuration settings to both **Configuration 1** and **Configuration 2**.

# 33.3 Firmware Upgrade

Use the following screen to upgrade your Switch to the latest firmware. The Switch supports dual firmware images, **Firm ware 1** and **Firm ware 2**. Use this screen to specify which image is updated when firmware is uploaded using the Web Configurator and to specify which image is loaded when the Switch starts up.

Make sure you have downloaded (and unzipped) the correct model firmware and version to your computer before uploading to the device.

# Be sure to upload the correct model firm ware as uploading the wrong model firm ware may damage your device.

Click Management > Maintenance > Firm ware Upgrade to view the screen as shown next.

Pirmware Upgrade		Nsisterso
lite rom		Weinstein
	Transie 2	144,705/1879,0104 ( 1847,247,3520
G\$1355-2 IP	Terrivore 1	-Weite (Applicies - Give traces
	fameers 2	VALO ADMICILA OS/07/2019
Curren Boel truge Carly Scollar aya	Dittivury Pertivate	1 1 ~
	August States	
Emergine [1 -]	re broese the location o Rie Poin Brouse	The amony (JiN) it's and a at lograde button. ] No file selected.
	Inancia	

Figure 193 Management > Maintenance > Firmware Upgrade

Type the path and file name of the firmware file you wish to upload to the Switch in the **File Path** text box or click **Choose File** to locate it. Upgrades are only applied after a reboot. Click **Upgrade** to load the new firmware.

After the process is complete, see the System Info screen to verify your current firmware version number.

Table 125 Management > Maintenance > Firmware Upgrade

IABEL	DESC RIPIIO N		
Name	This is the name of the Switch that you are configuring.		
Version	The Switch has 2 firmware sets, Firmware 1 and Firmware 2, residing in flash.		
	<ul> <li>Running shows the version number (and model code) and MM/DD/YYYY creation date of the firmware currently in use on the Switch (Fimware 1 or Fimware 2). The firmware information is also displayed at System Information in Basic Settings.</li> </ul>		
	• Firm ware 1 shows its version number (and model code) and MM/DD/YYYY creation date.		
	• Firm ware 2 shows its version number (and model code) and MM/DD/YYYY creation date.		
Current Boot Image	This displays which firmware is currently in use on the Switch (Firmware 1 or Firmware 2).		
Config Boot Image	Select which firmware (Firmware 1 or Firmware 2) should load, click Apply and reboot the Switch to see changes, you will also see changes in the Current Boot Image field above as well.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.		
Firmware	Choose to upload the new firmware to (Firmware) 1 or (Firmware) 2.		
File Path	Type the path and file name of the firmware file you wish to upload to the Switch in the File <b>Path</b> text box or click <b>Choose File</b> or <b>Browse</b> to locate it.		
Upgrade	Click Upgrade to load the new firmware. s are only applied after a reboot. To reboot, go to Management > Maintenance > Reboot System and click Config 1, Config 2 or Factory Default (Config 1, Config 2 and Factory Default are the configuration files you want the Switch to use when it restarts).		

# 33.4 Restore Configuration

Use this screen to restore a previously saved configuration from your computer to the Switch.

Figure 194	Management > Maintenance > Restore Conf	iguration
------------	---	-----------

Restore Configuration		Maintenance
To restore the device's e elick Restore bottom	enfiguration he	mailie, browse the location of the configuration file and
Lie Prits Innwes No Be selected		No file selected.
		Roles

Type the path and file name of the configuration file you wish to restore in the **File Path** text box or click **Choose File/Browse** to locate it. After you have specified the file, click **Restore**. "config" is the name of the configuration file on the Switch, so your backup configuration file is automatically renamed when you restore using this screen.

# 33.5 Backup Configuration

Backing up your Switch configurations allows you to create various "snap shots" of your device from which you may restore at a later date.

Back up your current Switch configuration to a computer using the Backup Configuration screen.

Figure 195 Management > Maintenance > Backup Configuration

Bookup Configure	allen	Waintenance
	okup the device's owned w	only action to your contention. Now
Configuration Burning Config M		
	Starting -	

Follow the steps below to back up the current Switch configuration to your computer in this screen.

- 1 Select which Switch configuration file you want to download to your computer.
- 2 Click Backup.
- 3 If the current configuration file is open and/or downloaded to your computer automatically, you can click File > Save As to save the file to a specific place.

If a dialog box pops up asking whether you want to open or save the file, click **Save** or **Save File** to download it to the default downloads folder on your computer. If a **Save As** screen displays after you click **Save** or **Save File**, choose a location to save the file on your computer from the **Save in** drop-down list box and type a descriptive name for it in the **File name** list box. Click **Save** to save the configuration file to your computer.

# 33.6 Tech-Support

The Tech-Support feature is a log enhancement tool that logs useful information such as CPU utilization history, memory and Mbuf (Memory Buffer) log and crash reports for issue analysis by customer support should you have difficulty with your Switch. The Tech Support menu eases your effort in obtaining reports and it is also available in CLI command by typing "Show tech-support" command.

Click Management > Maintenance > Tech-Support to see the following screen.

Reck-Support		Maintenana
сч. -	Incesture 100 Accur 2 Sectores	
Adam I	the state (A) - A	
	Apply Cause	
/4	Eswalept	
Cansh	Consultant.	
CTU Nevery	Lownis nd	
Alemany ave fan	Elowedd ad	
Villes I	Conversion of	
80.W	Lownload	

Figure 196 Management > Maintenance > Tech-Support

You may need WordPad or similar software to see the log report correctly. The table below describes the fields in the above screen.

LABEL	DESC RIPIIO N	
CPU	Type a number ranging from 50 to 100 in the CPU threshold box, and type another number ranging from 5 to 60 in the seconds box then click $Apply$ .	
	For example, 80 for CPU threshold and 5 for seconds means a log will be created when CPU utilization reaches over 80% and lasts for 5 seconds.	
	The log report holds 7 days of CPU log data and is stored in volatile memory (RAM). The data is lost if the Switch is turned off or in event of power outage. After 7 days, the logs wrap around and new ones and replace the earliest ones.	
	The higher the CPU threshold number, the fewer logs will be created, and the less data technical support will have to analyze and vice versa.	
Mbuf	Type a number ranging from 50 to 100 in the Mbuf (Memory Buffer) threshold box. The Mbuf log report is stored in flash (permanent) memory.	
	For example, Mbuf 50 means a log will be created when the Mbuf utilization is over 50%.	
	The higher the Mbuf threshold number, the fewer logs will be created, and the less data technical support will have to analyze and vice versa.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	
All	Click <b>Download</b> to see all the log report and system status. This log report is stored in flash memory. If the <b>All</b> log report is too large, you can download the log reports separately below.	
Crash	Click <b>Download</b> to see the crash log report. The log will include information of the last crash and is stored in flash memory.	
CPU history	Click <b>Download</b> to see the CPU history log report. The 7-days log is stored in RAM and you will need to save it, otherwise it will be lost when the Switch is shutdown or during power outage.	
Memory Section	Click <b>Download</b> to see the memory section log report. This log report is stored in flash memory.	

Table 126 Management > Maintenance > Tech-Support

IABEL	DESC RIPTIO N
Mbuf	Click <b>Download</b> to see the Mbuf log report. The log includes Mbuf over threshold information. This log report is stored in flash memory.
ROM	Click <b>Download</b> to see the Read Only Memory (ROM) log report. This report is stored in flash memory.

Table 126 Management > Maintenance > Tech-Support (continued)

## 33.7 Certificates

The Switch can use HTTPS certificates that are verified by a third party to create secure HTTPS connections between your computer and the Switch. This way, you may securely access the Switch using the Web Configurator. See Section 34.7.3 on page 286 for more information about HTTPS.

Certificates are based on public-private key pairs. A certificate contains the certificate owner's identity and public key. Certificates provide a way to exchange public keys for use in authentication.

Click **Management** > **Maintenance** > **Certificates** to open the following screen. Use this screen to import the Switch's CA-signed certificates.

	inter	e il de le la le agole il		Man)	
e fet		Burnan Avil		A REAL PROPERTY AND AND	
assword .		++++	5		
60. 000		20020			
		11 der	1		
			-		
	La subscription of the	and the second	Welling Procession	and the second	
	2 January 2 a Lyded	the state of the second st			
		COLLOSSO CONTRACTOR	Are 100 kite 20 et Mi	We have the second second	

Figure 197 Management > Maintenance > Certificates

Table 127	Management > Maintenance > Certificates

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
File Path	Click Choose File or Browse to find the certificate file you want to upload.
Password	Type the certificate file's password that was created when the PKCS #12 file was exported. The password consists of up to 32 ASCII characters.
Import	Click this button to save the certificate that you have enrolled from a certification authority from your computer to the Switch.
Service	This field displays the service type that this certificate is for.
Subject	This field displays identifying information about the certificate's owner, such as CN (Common Name), OU (Organizational Unit or department), O (Organization or company) and C (Country). It is recommended that each certificate have unique subject information.
Issuer	This field displays identifying information about the certificate's issuing certification authority, such as a common name, organizational unit or department, organization or company and country.

GS1350 Series User's Guide

IABEL	DESC RIPTIO N	
Valid From	This field displays the date that the certificate becomes applicable.	
Valid To	This field displays the date that the certificate expires.	
	Select an entry's check box to select a specific entry.	
Delete	Click this button to delete the certificate (or certification request). You cannot delete a certificate that one or more features is configured to use.	

Table 127 Management > Maintenance > Certificates (continued)

## 33.7.1 HTIPS Certific a tes

Use this screen to view the HTTPS certificate details. Click a hyperlink in the **Service** column in the **Management > Maintenance > Certificates** screen to open the following screen.

Figure 198 Management > Maintenance > Certificates > HTTPS

11 ID 4 millionim	Section as inst
Confederation (Confederation)	-
Taking the second se	
Manufactor 2, 2007	
Control Harvetone -	
No Alfa 11 Alfadesee A	
Segment and Alexandrican site of Section 24 Alexandrican	
le and the Change Market Back 24 (11) should be	
V- MP	
Not Rectary Los 1 (2010)004 2017 (2017)	
Had when North 27 (1991) 25 (1993)	
California de la California de California de California de California de California de California de California	
Californi Malala Cay sho	
Public kas hippetites and respiles	
A MERCE AND A MERCE	
Mandah e	
an e a file de febre de fealeche de Selence des	
A predict print de DAN also habere en des direction De Dan	
na CP3-marks-sife an Orbits 1 marks and a construction	
2.000 kC 4.002 kC 000 4.000 kG 400 kG 400 kG	
Undefinite States and Advantation and States 1974	
an eading a that is a factor of the second states and	
and a first state of the second state is defined as the	
and a state of the	
contract of the backbook of the	
all finded and the device it is not a matching for	
aitel Asternetics (a Paula Cardellade II (1973)	
2 K - 1 George 2, 2 February 12 (2008)	
An Ar Aldaha Barna Ar An Aldaha An	
and a state of the second state	
And the second	
Note in the second s	
Kalendar (n. 1997). 1997 - Alexandri Maria, an Alexandri (n. 1997). 1997 - Alexandri Alexandri, an Alexandri (n. 1997).	
рания Геренали Н (1897) (Эн) (1001)	
All the second	
VSDA Barle Conductor	
A A A B A A A A A A A A A A A A A A A A	
VOXA Coultage	
Fighed Menachury, Cry Technologue et alle diference Segn	
Legent an Alexalizer des 200400 MATerreceiter	
and a start of the function of the start of	
e med ANC have a TATA detaile an Charle 17 official a Charles	
de réfective des 11 Che Sthahe (Franklik) de ser Majori (Franklik)	
a MANISA POLISA ANA ANA ANA ANA ANA ANA ANA ANA ANA A	
a Salis IS dive by Trial Share Share Share Share Shiri 22	-
April for Comparison Statistical Sector (1) for all reflectively the	
	1

# 33.8 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 33.8.1 FIP Command Line

This section shows some examples of uploading to or downloading files from the Switch using FTP commands. First, understand the filename conventions.

## 33.8.2 Filename Conventions

The configuration file (also known as the romfile or ROM) contains the Zyxel factory default configuration settings in the screens such as password, Switch setup, IP Setup, and so on. Once you have customized the Switch's settings, they can be saved back to your computer under a filename of your choosing.

ZyNOS (Zyxel Network Operating System sometimes referred to as the "ras" file) is the system firmware and has a "bin" filename extension.

FILE TYPE	INTERNALNAME	EXTERNALNAME	DESC RIPTIO N
Configuration File	config	*.cfg	This is the configuration filename on the Switch. Uploading the config file replaces the specified configuration file system, including your Switch configurations, system-related data (including the default password), the error log and the trace log.
Firmware	ras	*.bin	This is the generic name for the ZyNOS firmware on the Switch.

Table 128 Filename Conventions

#### 33.8.2.1 Example FIP Commands

ftp> put firmware.bin ras

This is a sample FTP session showing the transfer of the computer file "firmware.bin" to the Switch.

ftp> get config config.cfg

This is a sample FTP session saving the current configuration to a file called "config.cfg" on your computer.

If your (T)FTP client does not allow you to have a destination filename different than the source, you will need to rename them as the Switch only recognizes "config" and "ras". Be sure you keep unaltered copies of both files for later use.

Be sure to upload the correct model firm ware as uploading the wrong model firm ware may damage your device.

## 33.8.3 FIP Command Line Procedure

- **1** Launch the FTP client on your computer.
- 2 Enter open, followed by a space and the IP address of your Switch.

- **3** Press [ENTER] when prompted for a username.
- 4 Enter your password as requested (the default is "1234").
- 5 Enter bin to set transfer mode to binary.
- 6 Use put to transfer files from the computer to the Switch, for example, put firmware.bin ras transfers the firmware on your computer (firmware.bin) to the Switch and renames it to "ras". Similarly, put config.cfg config transfers the configuration file on your computer (config.cfg) to the Switch and renames it to "config". Likewise get config config.cfg transfers the configuration file on the Switch to your computer and renames it to "config.cfg". See Table 128 on page 266 for more information on filename conventions.
- 7 Enter quit to exit the ftp prompt.

## 33.8.4 GUI-based FIP Clients

The following table describes some of the commands that you may see in GUI-based FTP clients.

COMMAND	DESC RIPTIO N
Host Address	Enter the address of the host server.
Login Type	Anonymous.
	This is when a user I.D. and password is automatically supplied to the server for anonymous access. Anonymous logins will work only if your ISP or service administrator has enabled this option.
	Normal.
	The server requires a unique User ID and Password to login.
Transfer Type	Transfer files in either ASCII (plain text format) or in binary mode. Configuration and firmware files should be transferred in binary mode.
Initial Remote Directory	Specify the default remote directory (path).
Initial Local Directory	Specify the default local directory (path).

Table 129 General Commands for GUI-based FTP Clients

## 33.8.5 FIP Restrictions

FTP will not work when:

- FTP service is disabled in the Service Access Control screen.
- The IP addresses in the **Remote Management** screen does not match the client IP address. If it does not match, the Switch will disconnect the FTP session immediately.

# C HAPTER 34 Access Control

# 34.1 Access Control Overview

This chapter describes how to control access to the Switch.

A console port and FTP are allowed one session each, Telnet and SSH share nine sessions, up to five Web sessions (five different user names and passwords) and/or limitless SNMP access control sessions are allowed.

Table 130 Access Control Overview

Console Port	SSH	Telnet	FTP	Web	SNMP
One session	Share up to 9 s	sessions	One session	Up to 5 accounts	No limit

A console port access control session and Telnet access control session cannot coexist when multi-login is disabled. See the CLI Reference Guide for more information on disabling multi-login.

## 34.1.1 What You Can Do

- Use the Access Control screen (Section 34.2 on page 268) to display the main screen.
- Use the SNMP screen (Section 34.3 on page 269) to configure your SNMP settings.
- Use the Thap Group screen (Section 34.3.1 on page 270) to specify the types of SNMP traps that should be sent to each SNMP manager.
- Use the Use r Inform a tion screen (Section 34.3.3 on page 272) to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups.
- Use the Logins screens (Section 34.4 on page 274) to assign which users can access the Switch via Web Configurator at any one time.
- Use the Service Access Control screen (Section 34.5 on page 276) to decide what services you may use to access the Switch.
- Use the **Remote Management** screen (Section 34.6 on page 277) to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

# 34.2 Access Control Main Settings

Use this screen to display the main screen.

Click **Management** > Access Control in the navigation panel to display the main screen as shown.

Figure 199 M	anagement > Access Control
--------------	----------------------------

Access Control		
AK MP	Conf. House	
egina -	<u>Alizk Here</u>	
Service Access Control	Vick likes	
A set is Management	Cold House	

Table 131 Management > Access Connor		
LABEL	DESC RIPTIO N	
SNMP	Click this link to configure your SNMP settings.	
Logins	Click this link to assign which users can access the Switch via Web Configurator at any one time.	
Service Access Control	Click this link to decide what services you may use to access the Switch.	
Remote Management	Click this link to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.	

Table 131 Management > Access Control

# 34.3 Configure SNMP

Use this screen to configure your SNMP settings.

Click Management > Access Control > SNMP to view the screen as shown.

Figure 200 Management > Access Control > SNMP

SNWP General Setting		2664	u Control Tran Group Unit
Vertion		+2:: <b>-</b>	
Conf. Concerning		nual s	
An effertune and		nual s	
Increase and a second s		public	
hop Destendore Verdan	17	Fort	U
	0000	1.47	Uremorne
- 222 F	0000	1.97	
	0.000	1.97	
-221 5	0.000	1.87	
			1
		Apply Cance	

LABEL	DESC RIPTIO N
General Setting	Use this section to specify the SNMP version and community (password) values.
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .
	SNMP version 2c is backwards compatible with SNMP version 1.
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNext- requests from the management station.
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the <b>Set Community</b> , which is the password for incoming Set- requests from the management station.
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.
Trap Destination	Use this section to configure where to send SNMP traps from the Switch.
Version	Specify the version of the SNMP trap messages.
IP	Enter the IP addresses of up to four managers to send your SNMP traps to.
Port	Enter the port number upon which the manager listens for SNMP traps.
Username	Enter the username to be sent to the SNMP manager along with the SNMP v3 trap.
	This username must match an existing account on the Switch (configured in the $Management > Access Control > SNMP > User screen)$ .
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 132 Management > Access Control > SNMP

## 34.3.1 Configure SNMP Trap Group

From the **SNMP** screen, click **Tiap Group** to view the screen as shown. Use the **Tiap Group** screen to specify the types of SNMP traps that should be sent to each SNMP manager.

Thap Gri ap Devilopitor				SKWI Selfins
lypv			Option	
Statem	Ξ.	eared.	E veniciat L'insigne	☐ temperature Hoopgward
hterfoce			E poe E lini viewe	☐ logine cord I logy
			E store control Li sufficiente	Lassening
F		j ma nje	L su mute	
Selfich	1.1	dip.	mostsple	l mren

Figure 201 Management > Access Control > SNMP > Trap Group

IABEL	DESC RIPTIO N
Trap Destination IP	Select one of your configured trap destination IP addresses. These are the IP addresses of the SNMP managers. You must first configure a trap destination IP address in the <b>SNMP Setting</b> screen.
	Use the rest of the screen to select which traps the Switch sends to that SNMP manager.
Туре	Select the categories of SNMP traps that the Switch is to send to the SNMP manager.
Options	Select the individual SNMP traps that the Switch is to send to the SNMP station. See SNMP Traps on page 280 for individual trap descriptions.
	The traps are grouped by category. Selecting a category automatically selects all of the category's traps. Clear the check boxes for individual traps that you do not want the Switch to send to the SNMP station. Clearing a category's check box automatically clears all of the category's trap check boxes (the Switch only sends traps from selected categories).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 133 Management > Access Control > SNMP > Trap Group

## 34.3.2 Enable or Disable Sending of SNMP Traps on a Port

From the **SNMP** > The p Group screen, click **Port** to view the screen as shown. Use this screen to set whether a trap received on the ports would be sent to the SNMP manager.

Irap Group Port Ophen: Ionpguon I 🔍		Imp Group
Port	Active	
-	11	
1	м	
2	м	
3	м	
4	м	
5	м	
6	м	
	Apply Cancel	

Figure 202 Management > Access Control > SNMP > Trap Group > Port

IABEL	DESC RIPTIO N
Option	Select the trap type you want to configure here.
Port	This field displays a port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the trap type of SNMP traps on this port.
	Clear this check box to disable the sending of SNMP traps on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 34.3.3 Configure SNMP User

From the **SNMP** screen, click **User** to view the screen as shown. Use the **User** screen to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups. An SNMP user is an SNMP manager.

User Informa	tion .				54	WP Setting
Descention						
Secondly Level	nocoth -					
Authentication	KNDA P	Texture 1	d -			
Privacy.	00.0	Pourse	1			
1 Second	o dimini un m	•				
		$\Delta t = 100$	nal d'Anne			
Index	lisemome	SecurityLevel	Authentication	Privacy	Group	
		1 Sector Inc.	• Second			

#### Figure 203 Management > Access Control > SNMP > User

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
User Information	Note: Use the username and password of the login accounts you specify in this screen to create accounts on the SNMP v3 manager.
Username	Specify the username of a login account on the Switch.
Security Level	<ul> <li>Select whether you want to implement authentication and/or encryption for SNMP communication from this user. Choose:</li> <li>noauth – to use the username as the password string to send to the SNMP manager. This is equivalent to the Get, Set and Trap Community in SNMP v2c. This is the lowest security level.</li> <li>auth – to implement an authentication algorithm for SNMP messages sent by this user.</li> <li>priv – to implement authentication and encryption for SNMP messages sent by this user. This is the highest security level.</li> <li>Note: The settings on the SNMP manager must be set at the same security level or</li> </ul>
	higher than the security level settings on the Switch.
Authentication	Select an authentication algorithm. <b>MD5</b> (Message Digest 5) and <b>SHA</b> (Secure Hash Algorithm) are hash algorithms used to authenticate SNMP data. SHA authentication is generally considered stronger than MD5, but is slower.
Password	Enter the password of up to 32 ASCII characters for SNMP user authentication.
Privacy	<ul> <li>Specify the encryption method for SNMP communication from this user. You can choose one of the following:</li> <li>DES – Data Encryption Standard is a widely used (but breakable) method of data encryption. It applies a 56-bit key to each 64-bit block of data.</li> <li>AES – Advanced Encryption Standard is another method for data encryption that also uses a secret key. AES applies a 128-bit key to 128-bit blocks of data.</li> </ul>
Password	Enter the password of up to 32 ASCII characters for encrypting SNMP packets.

Table 135 Management > Access Control > SNMP > User

LABEL	DESC RIPTIO N
Group	SNMP v3 adopts the concept of View-based Access Control Model (VACM) group. SNMP managers in one group are assigned common access rights to MIBs. Specify in which SNMP group this user is.
	a dm in – Members of this group can perform all types of system configuration, including the management of administrator accounts.
	<b>re a d write</b> – Members of this group have read and write rights, meaning that the user can create and edit the MIBs on the Switch, except the user account and AAA configuration.
	$\mathbf{readonly}$ – Members of this group have read rights only, meaning the user can collect information from the Switch.
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to reset the fields to your previous configuration.
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.
Index	This is a read-only number identifying a login account on the Switch. Click on an index number to view more details and edit an existing account.
Username	This field displays the username of a login account on the Switch.
Security Level	This field displays whether you want to implement authentication and/or encryption for SNMP communication with this user.
Authentication	This field displays the authentication algorithm used for SNMP communication with this user.
Privacy	This field displays the encryption method used for SNMP communication with this user.
Group	This field displays the SNMP group to which this user belongs.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click <b>De le te</b> to remove the selected entry from the summary table.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

Table 135 Management > Access Control > SNMP > User (continued)

# 34.4 Set Up Login Accounts

Up to five people (one administrator and four non-administrators) may access the Switch via Web Configurator at any one time.

• An administrator is someone who can both view and configure Switch changes. The username for the Administrator is always **a dmin**. The default administrator password is **1234**.

Note: It is highly recommended that you change the default administrator password (1234).

• A non-administrator (username is something other than **admin**) is someone who can view and/or configure Switch settings. The configuration right varies depending on the user's privilege level.

Click **Management > Access Control > Logins** to view the screen as shown.

Figure 204	Management > Access Control > Logins
Ing unc avi	

وما Administratio				Access Control
10 Dorse	or t			
New Your	ward			
Robins	no shen			
Hernsenerum Inspellen vor Fahl Logens	-	enever yna obrenge it H	ne sy streen wall fan is yn a raaf it yn	u kove
Login	User Harne	Fourword	Bailype to confirm	Millioge
I				
2				
3				
4				
		Apply Const		

#### Table 136 Management > Access Control > Logins

IABEL	DESC RIPTIO N				
Administrator	Administrator				
This is the default ad user name.	ministrator account with the "admin" user name. You cannot change the default administrator				
Old Password	Type the existing system password (1234 is the default password when shipped).				
New Password	Enter your new system password.				
Retype to confirm	Retype your new system password for confirmation.				
Edit Logins					
give users higher priv	passwords for up to four users. These users can have read-only or read/write access. You can vileges via the Web Configurator or the CLI. For more information on assigning privileges via the Switch CLI Reference Guide.				
User Name	Set a user name (up to 32 ASCII characters long).				
Password	Enter your new system password.				
Retype to confirm	Retype your new system password for confirmation.				

IABEL	DESC RIPTIO N
Privilege	Type the privilege level for this user. At the time of writing, users may have a privilege level of 0, 3, 13, or 14 representing different configuration rights as shown below.
	• 0 – Display basic system information.
	3 – Display configuration or status.
	<ul> <li>13 – Configure features except for login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, administrator and enable passwords, and configuration information display.</li> </ul>
	<ul> <li>14 – Configure login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, and administrator and enable passwords, and display configuration information.</li> </ul>
	Users can run command lines if the session's privilege level is greater than or equal to the command's privilege level. The session privilege initially comes from the privilege of the login account. For example, if the user has a privilege of 5, he/she can run commands that requires privilege level of 5 or less but not more.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 136 Management > Access Control > Logins (continued)

# 34.5 Service Access Control

Service Access Control allows you to decide what services you may use to access the Switch. You may also change the default service port and configure "trusted computers" for each service in the **Remote Management** screen (discussed later). Click **Access Control** to go back to the main **Access Control** screen.

Second Succession	a kandezi			Access Control
E-molecule (	d e fine	Construction Posts	Transat	Lorgin, Developed
Consuler-			A Market and	
Laborat	ы	28	a kana an	14 C 2 10 million
2011	м	2.2	-	
11 °	н	21	A Markan	
0.02	н	1.1	A Dension	
111.5	м	4.42	-	
0.00		•		
STHE"	н			
		Access the		

Figure 205 Management > Access Control > Service Access Control

The following table describes the fields in this screen.

IABEL	DESC RIPTIO N
Services	Services you may use to access the Switch are listed here.
Active	Select this option for the corresponding services that you want to allow to access the Switch.
Service Port	For Telnet, SSH, FTP, HTTP or HTTPS services, you may change the default service port by typing the new port number in the <b>Service Port</b> field. If you change the default port number then you will have to let people (who wish to use the service) know the new port number for that service.

GS1350 Series User's Guide

IABEL	DESC RIPTIO N
Timeout	Enter how many minutes (from 1 to 255) a management session can be left idle before the session times out. After it times out you have to log in with your password again. Very long idle timeouts may have security risks.
Login Timeout	The Telnet or SSH server do not allow multiple user logins at the same time. Enter how many seconds (from 30 to 300 seconds) a login session times out. After it times out you have to start the login session again. Very long login session timeouts may have security risks.
	For example, if User A attempts to connect to the Switch (via SSH), but during the login stage, do not enter the user name and/or password, User B cannot connect to the Switch (via SSH) before the Login Time out for User A expires (default 150 seconds).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

T     107		
Table 13/	Management > Access Control > Service Access Control (con-	tinued)

# 34.6 Remote Management

Use this screen to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

Click Management > Access Control > Remote Management to view the screen as shown next.

You can specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch. Click Access Control to return to the Access Control screen.

Remote Management Secured Client Setup						Access Control				
Entry	Active	Start Address	End Address	Teinet	FTP	HTTP	ICMP	SNMP	SSH	HTTPS
1	1	0.0.0.0	0.0.00	×	×	×	×.	×		×
2		0.0.0.0	0.0.00							
3		0.0.00	0.0.00							
4		0.0.00	0.0.00							
5		0.0.0.0	0.0.0.0							
6		0.0.0.0	0.0.0.0							
7		0.0.0.0	0.0.0.0							
8		0.0.0.0	0.0.0.0							
9		0.0.0.0	0.0.0.0							
10		0.0.0.0	0.0.0.0							
11		0.0.0.0	0.0.0.0							
12		0.0.0.0	0.0.0.0							
10		0.0.0.0	0.0.0.0							
14		0.0.0.0	0.0.0.0							
1.5		0.0.0.0	0.0.0.0							
16		0.0.0.0	0.0.0.0							
Apply Concel										

Figure 206 Management > Access Control > Remote Management

Table 138	Management > Access Control > Remote Management
	Munugement > Access Control > Remote Munugement

LABEL	DESC RIPIIO N
Entry	This is the client set index number. A "client set" is a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
Active	Select this check box to activate this secured client set. Clear the check box if you wish to temporarily disable the set without deleting it.
Start Address	Configure the IP address range of trusted computers from which you can manage this Switch.
End Address	The Switch checks if the client IP address of a computer requesting a service or protocol matches the range set here. The Switch immediately disconnects the session if it does not match.
Telnet/FTP/ HTTP/ICMP/ SNMP/SSH/ HTTPS	Select services that may be used for managing the Switch from the specified trusted computers.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.


# 34.7 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 34.7.1 About SNMP

Simple Network Management Protocol (SNMP) is an application layer protocol used to manage and monitor TCP/IP-based devices. SNMP is used to exchange management information between the network management system (NMS) and a network element (NE). A manager station can manage and monitor the Switch through the network via SNMP version 1 (SNMPv1), SNMP version 2c or SNMP version 3. The next figure illustrates an SNMP management operation. SNMP is only available if TCP/IP is configured.





An SNMP managed network consists of two main components: agents and a manager.

An agent is a management software module that resides in a managed Switch (the Switch). An agent translates the local management information from the managed Switch into a form compatible with SNMP. The manager is the console through which network administrators perform network management functions. It executes applications that control and monitor managed devices.

The managed devices contain object variables/managed objects that define each piece of information to be collected about a Switch. Examples of variables include number of packets received, node port status and so on. A Management Information Base (MIB) is a collection of managed objects. SNMP allows a manager and agents to communicate for the purpose of accessing these objects.

SNMP itself is a simple request or response protocol based on the manager or agent model. The manager issues a request and the agent returns responses using the following protocol operations:

LABEL	DESC RIPIIO N
Get	Allows the manager to retrieve an object variable from the agent.
GetNext	Allows the manager to retrieve the next object variable from a table or list within an agent. In SNMPv1, when a manager wants to retrieve all elements of a table from an agent, it initiates a Get operation, followed by a series of GetNext operations.
Set	Allows the manager to set values for object variables within an agent.
Trap	Used by the agent to inform the manager of some events.

Table 139 SNMP Commands

#### $SNMP\,v3$ and $Se\,c\,urity$

SNMP v3 enhances security for SNMP management. SNMP managers can be required to authenticate with agents before conducting SNMP management sessions.

Security can be further enhanced by encrypting the SNMP messages sent from the managers.

Encryption protects the contents of the SNMP messages. When the contents of the SNMP messages are encrypted, only the intended recipients can read them.

#### Supported MIBs

MIBs let administrators collect statistics and monitor status and performance.

The Switch supports the following MIBs:

- SNMP MIB II (RFC 1213)
- RFC 1157 SNMP v1
- RFC 1493 Bridge MIBs
- RFC 1643 Ethernet MIBs
- RFC 1155 SMI
- RFC 2674 SNMPv2, SNMPv2c
- RFC 1757 RMON
- SNMPv2, SNMPv2c or later version, compliant with RFC 2011 SNMPv2 MIB for IP, RFC 2012 SNMPv2 MIB for TCP, RFC 2013 SNMPv2 MIB for UDP

#### SNMP Traps

The Switch sends traps to an SNMP manager when an event occurs. The following tables outline the SNMP traps by category.

An OID (Object ID) that begins with "1.3.6.1.4.1.890.1.15" is defined in private MIBs. Otherwise, it is a standard MIB OID.

O PIIO N	O BJEC T LA BEL	O BJEC TID	DESC RIPIIO N
coldstart	coldStart	1.3.6.1.6.3.1.1.5.1	This trap is sent when the Switch is turned on.
warmstart	warmStart	1.3.6.1.6.3.1.1.5.2	This trap is sent when the Switch restarts.
fanspeed	zyHwMonitorFanSpeedOutO fRange	1.3.6.1.4.1.890.1.15.3.26.2.1	This trap is sent when the fan speed goes above or below the normal operating range.
	zyHwMonitorFANSpeedOut OfRangeRecovered	1.3.6.1.4.1.890.1.15.3.26.2.6	This trap is sent when the fan speed is recovered from the out of range to normal operating range.
temperature	zyHwMonitorTemperatureOu tOfRange	1.3.6.1.4.1.890.1.15.3.26.2.2	This trap is sent when the temperature goes above or below the normal operating range.
	zyHwMonitorTemperatureOu tOfRangeRecovered	1.3.6.1.4.1.890.1.15.3.26.2.7	This trap is sent when the temperature is recovered from the out of range to normal operating range.

O PIIO N	O BJEC TIABEL	O BJEC TID	DESC RIPTIO N
reset	zySysMgmtUncontrolledSyste mReset	1.3.6.1.4.1.890.1.15.3.49.2.1	This trap is sent when the Switch automatically resets.
	zySysMgmtControlledSystem Reset	1.3.6.1.4.1.890.1.15.3.49.2.2	This trap is sent when the Switch resets by an administrator through a management interface.
	zySysMgmtBootImageIncons istence	1.3.6.1.4.1.890.1.15.3.49.2.3	This trap is sent when the index number of image which is loaded when the Switch starts up is different from what is specified via the CLI.
	RebootEvent	1.3.6.1.4.1.890.1.5.1.1.2	This trap is sent when the Switch reboots by an administrator through a management interface.
timesync	zyDateTimeTrapTimeServerN otReachable	1.3.6.1.4.1.890.1.15.3.82.3.1	This trap is sent when the Switch's date and time is not manually entered or the specified time server is not reachable.
	zyDateTimeTrapTimeServerN otReachableRecovered	1.3.6.1.4.1.890.1.15.3.82.3.2	This trap is sent when the Switch's real time clock is up to date.
intrusionlock	zyPortIntrusionLock	1.3.6.1.4.1.890.1.15.3.61.3.2	This trap is sent when intrusion lock occurs on a port.
loopguard	zyLoopGuardLoopDetect	1.3.6.1.4.1.890.1.15.3.45.2.1	This trap is sent when loopguard shuts down a port.
errdisable	zyErrdisableDetect	1.3.6.1.4.1.890.1.15.3.24.4.1	This trap is sent when an error is detected on a port, such as a loop occurs or the rate limit for specific control packets is exceeded.
	zyErrdisableRecovery	1.3.6.1.4.1.890.1.15.3.24.4.2	This trap is sent when the Switch ceases the action taken on a port, such as shutting down the port or discarding packets on the port, after the specified recovery interval.
poe	zyPoePowerPortOverload	1.3.6.1.4.1.890.1.15.3.59.4.1	This trap is sent when the port is turned off to supply power due to overloading.
(For PoE models only)	zyPoePowerPortShortCircuit	1.3.6.1.4.1.890.1.15.3.59.4.2	This trap is sent when the port is turned off to supply power due to short circuit.
	zyPoePowerPortOverSystem Budget	1.3.6.1.4.1.890.1.15.3.59.4.3	This trap is sent when the port is turned off to supply power because the requested power exceeds the total PoE power budget on the Switch.
	zyPoePowerPortOverloadRe covered	1.3.6.1.4.1.890.1.15.3.59.4.5	This trap is sent when the port is turned on to recover from an overloaded state.
	zyPoePowerPortShortCircuitR ecovered	1.3.6.1.4.1.890.1.15.3.59.4.6	This trap is sent when the port is turned on to recover from a short circuit.
	zyPoePowerPortOverSystem BudgetRecovered	1.3.6.1.4.1.890.1.15.3.59.4.7	This trap is sent when the port is turned on to recover from an over system budget.
loginrecord	zyAccessControlLoginRecor d	1.3.6.1.4.1.890.1.15.3.9.4.1	This trap is sent when users log in.
	zyAccessControlLogoutRec ord	1.3.6.1.4.1.890.1.15.3.9.4.2	This trap is sent when users log out.
	zyAccessControlLoginFail	1.3.6.1.4.1.890.1.15.3.9.4.3	This trap is sent when users fail in login.

Table 141 SNMP Interface Traps

O PIIO N	OBJECTIABEL	OBJECTID	DESC RIPIIO N
linkup	linkUp	1.3.6.1.6.3.1.1.5.4	This trap is sent when the Ethernet link is up.
linkdown	linkDown	1.3.6.1.6.3.1.1.5.3	This trap is sent when the Ethernet link is down.
lldp	lldpRemTablesChange	1.0.8802.1.1.2.0.0.1	The trap is sent when entries in the remote database have any updates.
			Link Layer Discovery Protocol (LLDP), defined as IEEE 802.1 ab, enables LAN devices that support LLDP to exchange their configured settings. This helps eliminate configuration mismatch issues.
transceiver-ddm	zyTransceiverDdmiTemperature OutOfRange	1.3.6.1.4.1.890.1.15.3.84.3.1	This trap is sent when the transceiver temperature is above or below the normal operating range.
	zyTransceiverDdmiTxPowerOutO fRange	1.3.6.1.4.1.890.1.15.3.84.3.2	This trap is sent when the transmitted optical power is above or below the normal operating range.
	zyTransceiverDdmiRxPowerOutO fRange	1.3.6.1.4.1.890.1.15.3.84.3.3	This trap is sent when the received optical power is above or below the normal operating range.
	zyTransceiverDdmiVoltageOutO fRange	1.3.6.1.4.1.890.1.15.3.84.3.4	This trap is sent when the transceiver supply voltage is above or below the normal operating range.
	zyTransceiverDdmiTxBiasOutOfR ange	1.3.6.1.4.1.890.1.15.3.84.3.5	This trap is sent when the transmitter laser bias current is above or below the normal operating range.
	zyTransceiverDdmiTemperature OutOfRangeRecovered	1.3.6.1.4.1.890.1.15.3.84.3.6	This trap is sent when the transceiver temperature is recovered from the out of normal operating range.
	zyTransceiverDdmiTxPowerOutO fRangeRecovered	1.3.6.1.4.1.890.1.15.3.84.3.7	This trap is sent when the transmitted optical power is recovered from the out of normal operating range.
	zyTransceiverDdmiRxPowerOutO fRangeRecovered	1.3.6.1.4.1.890.1.15.3.84.3.8	This trap is sent when the received optical power is recovered from the out of normal operating range.
	zyTransceiverDdmiVoltageOutO fRangeRecovered	1.3.6.1.4.1.890.1.15.3.84.3.9	This trap is sent when the transceiver supply voltage is recovered from the out of normal operating range.
	zyTransceiverDdmiTxBiasOutOfR angeRecovered	1.3.6.1.4.1.890.1.15.3.84.3.10	This trap is sent when the transmitter laser bias current is recovered from the out of normal operating range.
Storm-control	zyPortStormControlTrap	1.3.6.1.4.1.890.1.15.3.78.2.1	This trap is sent when storm control is detected on a specific port. A packet filter action has been applied on the interface.

Table 142	SNMP AAA Traps
-----------	----------------

O PIIO N	O BJEC TLABEL	O BJEC TID	DESC RIPIIO N
authentication	authenticationFailure	1.3.6.1.6.3.1.1.5.5	This trap is sent when authentication fails due to incorrect user name and/or password.
	zyAaaAuthenticationFailure	1.3.6.1.4.1.890.1.15.3.8.3.1	This trap is sent when authentication fails due to incorrect user name and/or password.
	zyRadiusServerAuthenticationSer verNotReachable	1.3.6.1.4.1.890.1.15.3.71.2.1	This trap is sent when there is no response message from the RADIUS authentication server.
	zyRadiusServerAuthenticationSer verNotReachableRecovered	1.3.6.1.4.1.890.1.15.3.71.2.3	This trap is sent when there is a response message from the previously unreachable RADIUS authentication server.
authorization	zyAaaAuthorizationFailure	1.3.6.1.4.1.890.1.15.3.8.3.2	This trap is sent when management connection authorization failed.
accounting	zyRadiusServerAccountingServer NotReachable	1.3.6.1.4.1.890.1.15.3.71.2.2	This trap is sent when there is no response message from the RADIUS accounting server.
	zyRadiusServerAccountingServer NotReachableRecovered	1.3.6.1.4.1.890.1.15.3.71.2.4	This trap is sent when there is a response message from the previously unreachable RADIUS accounting server.

#### Table 143 SNMP IP Traps

O PIIO N	O BJEC TIABEL	O BJEC T ID	DESC RIPTIO N
ping	pingProbeFailed	1.3.6.1.2.1.80.0.1	This trap is sent when a single ping probe fails.
	pingTestFailed	1.3.6.1.2.1.80.0.2	This trap is sent when a ping test (consisting of a series of ping probes) fails.
	pingTestCompleted	1.3.6.1.2.1.80.0.3	This trap is sent when a ping test is completed.
traceroute	traceRouteTestFailed	1.3.6.1.2.1.81.0.2	This trap is sent when a traceroute test fails.
	traceRouteTestCompleted	1.3.6.1.2.1.81.0.3	This trap is sent when a traceroute test is completed.

#### Table 144 SNMP Switch Traps

O PIIO N	OBJECTIABEL	OBJECTID	DESC RIPIIO N
stp	STPNewRoot	1.3.6.1.2.1.17.0.1	This trap is sent when the STP root Switch changes.
	STPTopologyChange	1.3.6.1.2.1.17.0.2	This trap is sent when the STP topology changes.
mactable	zyMacForwardingTableFull	1.3.6.1.4.1.890.1.15.3.4 8.2.1	This trap is sent when more than 99% of the MAC table is used.
	zyMacForwardingTableFullReco vered	1.3.6.1.4.1.890.1.15.3.4 8.2.2	This trap is sent when the MAC address switching table has become normal from full.

O PIIO N	OBJECTIABEL	OBJECTID	DESC RIPTIO N
rmon	RmonRisingAlarm	1.3.6.1.2.1.16.0.1	This trap is sent when a variable goes over the RMON "rising" threshold.
	RmonFallingAlarm	1.3.6.1.2.1.16.0.2	This trap is sent when the variable falls below the RMON "falling" threshold.

Table 144 SNMP Switch Traps (continued)

### 34.7.2 SSH Overview


Unlike Telnet or FTP, which transmit data in clear text, SSH (Secure Shell) is a secure communication protocol that combines authentication and data encryption to provide secure encrypted communication between two hosts over an unsecured network.





#### 34.7.2.1 How SSH Works

The following table summarizes how a secure connection is established between two remote hosts.



1 Host Identification

The SSH client sends a connection request to the SSH server. The server identifies itself with a host key. The client encrypts a randomly generated session key with the host key and server key and sends the result back to the server.

The client automatically saves any new server public keys. In subsequent connections, the server public key is checked against the saved version on the client computer.

2 Encryption Method

Once the identification is verified, both the client and server must agree on the type of encryption method to use.

**3** Authentication and Data Transmission

After the identification is verified and data encryption activated, a secure tunnel is established between the client and the server. The client then sends its authentication information (user name and password) to the server to log in to the server.

#### 34.7.2.2 SSH Implementation on the Switch

Your Switch supports SSH version 2 using RSA authentication and three encryption methods (DES, 3DES and Blowfish). The SSH server is implemented on the Switch for remote management and file transfer on port 22. Only one SSH connection is allowed at a time.

285

#### 34.7.2.3 Requirements for Using SSH

You must install an SSH client program on a client computer (Windows or Linux operating system) that is used to connect to the Switch over SSH.

## 34.7.3 Introduction to HTIPS

HTTPS (HyperText Transfer Protocol over Secure Socket Layer, or HTTP over SSL) is a web protocol that encrypts and decrypts web pages. Secure Socket Layer (SSL) is an application-level protocol that enables secure transactions of data by ensuring confidentiality (an unauthorized party cannot read the transferred data), authentication (one party can identify the other party) and data integrity (you know if data has been changed).

It relies upon certificates, public keys, and private keys.

HTTPS on the Switch is used so that you may securely access the Switch using the Web Configurator. The SSL protocol specifies that the SSL server (the Switch) must always authenticate itself to the SSL client (the computer which requests the HTTPS connection with the Switch), whereas the SSL client only should authenticate itself when the SSL server requires it to do so. Authenticating client certificates is optional and if selected means the SSL-client must send the Switch a certificate. You must apply for a certificate for the browser from a Certificate Authority (CA) that is a trusted CA on the Switch.

Please refer to the following figure.

- 1 HTTPS connection requests from an SSL-aware web browser go to port 443 (by default) on the Switch's WS (web server).
- 2 HTTP connection requests from a web browser go to port 80 (by default) on the Switch's WS (web server).




Figure 210 HTTPS Implementation

Note: If you disable HTTP in the Service Access Control screen, then the Switch blocks all HTTP connection attempts.

#### 34.7.3.1 HTIPS Example

If you have not changed the default HTTPS port on the Switch, then in your browser enter "https://Switch IP Address/" as the web site address where "Switch IP Address" is the IP address or domain name of the Switch you wish to access.

#### Internet Explorer Warning Messages

#### Internet Explorer6

When you attempt to access the Switch HTTPS server, a Windows dialog box pops up asking if you trust the server certificate.

You see the following **Security Alert** screen in Internet Explorer. Select **Yes** to proceed to the Web Configurator login screen; if you select **No**, then Web Configurator access is blocked.

Figure 211 Security Alert Dialog Box (Internet Explorer 6)



#### Internet Explorer 7 or 8

When you attempt to access the Switch HTTPS server, a screen with the message "There is a problem with this website's security certificate." may display. If that is the case, click **Continue to this website** (not recommended) to proceed to the Web Configurator login screen.

Figure 212 Security Certificate Warning (Internet Explorer 7 or 8)

security particles begin obtained indicate an estempt to lock yes, or interception yes large	
235	ou send to M
We recommend that you close this welepage and the not continue to this website	2
👹 Childri here invidense fin strandstade	

After you log in, you will see the red address bar with the message **Certificate Error**. Click on **Certificate Error** next to the address bar and click **View certificates**.




Figure 213 Certificate Error (Internet Explorer 7 or 8)

Click Install Certificate... and follow the on-screen instructions to install the certificate in your browser.

Figure 214 Certificate (Internet Explorer 7 or 8)

6	📮 Lendicata Laternation	
1.1	tis CA Root op ritikasio is not brusted. To one lic stal this op thiotic in the Trusted Root Certific atlearthic stars.	inast. Ation
	EXAMPLE	
	wild from $(z'_i)'_{ij}(z)$ is $(z'_i)'_{ij}(z)$ and	
ski Share	brail Cat tara.	Granes

#### Mozilla Fire fox Warning Messages

When you attempt to access the Switch HTTPS server, a **Yourconnection is not secure** screen may display. If that is the case, click **I Understand the Risks** and then the **Add Exception...** button.

Figure 215	Security Alert	(Mozilla Firefox)
------------	----------------	-------------------

re	of the South	in trace and the ⊗ o	19 I 194
re		n frem forng ale kr	1996
		83	
is prover	yoo momaaa	83	
	Č	deben som s	
	(	· states reaction	
acua aika			

Confirm the HTTPS server URL matches. Click **Confirm Security Exception** to proceed to the Web Configurator login screen.


Figure 216 Security Alert (Mozilla Firefox)

Add Security Ecception	han the
Yn wer an d'hernen ik fersk eksister ik der i de in de in de ferske in de in de in de in de in de in de in de Gener	tash yeu to da tha.
Lodeloo https://3018/dl	2st Cell sets
Could a state states This size access points identify room with investiging much as	Terms 8
WringSite	powerson.
The cardificate belongs to a different site, which could meet that an observe the site	eoracia la trying la
Halanawa kiraliy The cardionale are margined as <b>EXAMPLE</b> , a subjectly as you need a signalay.	an tya nanc
18 Januarily with might	_
Sastar Sanatylesa	oten Circul

### 34.7.4 Google Chrome Warning Messages

When you attempt to access the Switch HTTPS server, a **Yourconnection is not private** screen may display. If that is the case, click **Advanced** and then **Proceed to x.x.x.x (unsafe)** to proceed to the Web Configurator login screen.

Figure 217 Security Alert (Google Chrome 58.0.3029.110)



#### 34.7.4.1 Main Settings

After you accept the certificate and enter the login username and password, the Switch main screen appears. The lock displayed in the bottom right of the browser status bar or next to the website address denotes a secure connection.

ano contrator						1-1-10
• ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (			12.2M.10	1.4	018 4	
ZYXEL GROM			0	0		
HMAL Los De De Des contractionses Los Contractionses Antonio Contractionses	The Second Secon	Lumo Mail II System Lancation Failer The Version Lancation Lancation Biochemistry Constrained Constraint Second Biochemistry Second Biochemistry Sec	Control Contro			
	In the second			ć.		

Figure 218 Example: Lock Denoting a Secure Connection

# C HAPTER 35 Diagnostic

## 35.1 Overview

This chapter explains the Diagnostic screen. You can use this screen to help you identify problems.

## 35.2 Diagnostic

Click **Management** > **Diagnostic** in the navigation panel to open this screen. Use this screen to ping IP addresses, run a traceroute, perform port tests or show the Switch's location between devices.

Biognostic - Into -	I			
				.4
Ping Test	00 IPv6	• •		
	IP Address/Host Name Count	3		E Fig
	00 II va O IPva	×.		
Iroce Koute Jest	IP Address/Heal Name			Trace Rocks
	10	30		
	Weil Time	2 Secondy		
	Rueses.	3		
Ethernel Perl Teal	Port		Port Test	
Cable Disposition 🚹	Port		Disgoose	
Localor LED	30	Minutes	Bink Slop	

Figure 219 Management > Diagnostic

IABEL	DESC RIPTIO N
Ping Test	
IPv4	Select this option if you want to ping an IPv4 address, and select <b>vlan</b> to specify the ID number of the VLAN to which the Switch is to send ping requests. Otherwise, select – to send ping requests to all VLANs on the Switch.
IPv6	Select this option if you want to ping an IPv6 address. You can also select $vlan$ and specify the ID number of the VLAN to which the Switch is to send ping requests. Otherwise, select – to send ping requests to all VLANs on the Switch.
IP Address/Host Name	Type the IP address or host name of a device that you want to ping in order to test a connection.
	Click <b>Ping</b> to have the Switch ping the IP address.
Count	Enter the number of ICMP Echo Request (ping) messages the Switch continuously sends.
Trace Route Test	
IPv4	Select this option if you want to trace the route packets take to a device with an IPv4 address, and select $vlan$ to specify the ID number of the VLAN on which the Switch traces the path. Otherwise, select – to trace the path on any VLAN.
	Note: The device to which you want to run a traceroute must belong to the VLAN you specify here.
IPv6	Select this option if you want to trace the route packets take to a device with an IPv6 address.
IP Address/Host Name	Enter the IP address or host name of a device to which you want to perform a traceroute.
Nome	Click Thace Route to have the Switch perform the traceroute function. This determines the path a packet takes to the specified device.
TTL	Enter the Time To Live (TTL) value for the ICMP Echo Request packets. This is to set the maximum number of the hops (routers) a packet can travel through. Each router along the path will decrement the TTL value by one and forward the packets. When the TTL value becomes zero and the destination is not found, the router drops the packets and informs the sender.
Wait Time	Specify how many seconds the Switch waits for a response to a probe before running another traceroute.
Queries	Specify how many times the Switch performs the traceroute function.
Ethernet Port Test	Enter a port number and click <b>Port Test</b> to perform an internal loopback test.
Port	This is the number of the physical Ethernet port on the Switch.
Cable Diagnostics	Enter a port number and click <b>Diagnose</b> to perform a physical wire-pair test of the Ethernet connections on the specified ports. The following fields display when you diagnose a port.
	Note: This feature is limited to within 100 meters only.
Port	This is the number of the physical Ethernet port on the Switch.
Channel	An Ethernet cable usually has 4 pairs of wires. A 10BASE-T or 100BASE-TX port only use and test 2 pairs, while a 1000BASE-T port requires all 4 pairs.
	This displays the descriptive name of the wire-pair in the cable.

Table 145	Management >	> Diagnostic
	management	Diagnostic

Table 145 Management > Diagnostic (continued)

IABEL	DESC RIPHO N
Pair status	<b>Ok</b> : The physical connection between the wire-pair is okay.
	$\mathbf{Open}$ : There is no physical connection (an open circuit detected) between the wire-pair.
	$\mathbf{Short}$ : There is an short circuit detected between the wire-pair.
	<b>Unknown</b> : The Switch failed to run cable diagnostics on the cable connected this port.
	<b>Unsupported</b> : The port is a fiber port or it is not active.
Cable length	This displays the total length of the Ethernet cable that is connected to the port when the $Pa$ ir status is $Ok$ and the Switch chipset supports this feature.
	This shows N/A if the Pair status is Open or Short. Check the Distance to fault.
	This shows <b>Unsupported</b> if the Switch chipset does not support to show the cable length.
Distance to fault	This displays the distance between the port and the location where the cable is open or shorted.
	This shows <b>N/A</b> if the <b>Pair status</b> is <b>Ok</b> .
	This shows <b>Unsupported</b> if the Switch chipset does not support to show the distance.
Locator LED	Enter a time interval (in minutes) and click <b>Blink</b> to show the actual location of the Switch between several devices in a rack.
	The default time interval is 30 minutes.
	Click $\mathbf{Stop}$ to have the Switch terminate the blinking locater LED.

# C HAPTER 36 System Log

### 36.1 Overview


A log message stores the information for viewing.

## 36.2 System Log

Click **Management** > **System Log** in the navigation panel to open this screen. Use this screen to check current system logs.

Note: When a log reaches the maximum number of log messages, new log messages automatically overwrite existing log messages, starting with the oldest existing log message first.

Figure 220 Management > System Log



The summary table shows the time the log message was recorded and the reason the log message was generated. Click **Refresh** to update this screen. Click **Clear** to clear the whole log, regardless of what is currently displayed on the screen. Click **Download** to save the log to your computer.

# C HAPTER 37 Syslog Setup

## 37.1 Syslog Overview

This chapter explains the syslog screens.

The syslog protocol allows devices to send event notification messages across an IP network to syslog servers that collect the event messages. A syslog-enabled device can generate a syslog message and send it to a syslog server.

Syslog is defined in RFC 3164. The RFC defines the packet format, content and system log related information of syslog messages. Each syslog message has a facility and severity level. The syslog facility identifies a file in the syslog server. Refer to the documentation of your syslog program for details. The following table describes the syslog severity levels.

CODE	SEVERIIY
0	Emergency: The system is unusable.
1	Alert: Action must be taken immediately.
2	Critical: The system condition is critical.
3	Error: There is an error condition on the system.
4	Warning: There is a warning condition on the system.
5	Notice: There is a normal but significant condition on the system.
6	Informational: The syslog contains an informational message.
7	Debug: The message is intended for debug-level purposes.

Table 146 Syslog Severity Levels

### 37.1.1 What You Can Do

Use the **Syslog Setup** screen (Section 37.2 on page 296) to configure the device's system logging settings and configure a list of external syslog servers.

## 37.2 Syslog Setup

The syslog feature sends logs to an external syslog server. Use this screen to configure the device's system logging settings and configure a list of external syslog servers.

Click **Management** > **Syslog Setup** in the navigation panel to display this screen.

94	Protect U	
	A DIVE D	
Logging type	Active	Encisty
System		loca use a *
Interlace	10	laca _se 0 *
Sedule	0	kentise 0.7
2,4,2	10	labai Uso () 🔹
F	0	loco Usaŭ T
	Such Consel	hand a second
log Server Setup	Partie Caree	
	Partie Caree	
log Server Selup	Paretes Career	
log Server Setup ortwe erver Address	Paretes Career	
ilog Server Setup ontwe erver Accorece 1941 frot	Ell 514	
log Server Setup ortwe erver Address	El	
ilog Server Setup ontwe erver Accorece 1941 frot	Ell 514	
log Jerver Setup othe erver Actories Withel	El S14 Lever (1 *	

	<b>Fig ure</b>	221	Management >	> 5	Syslog	Setup
--	----------------	-----	--------------	-----	--------	-------

Table 147	Management > Syslog Setup
	munugement - systeg setup

LABEL	DESC RIPTIO N	
Syslog	Select Active to turn on syslog (system logging) and then configure the syslog setting.	
Logging Type	This column displays the names of the categories of logs that the device can generate.	
Active	Select this option to set the device to generate logs for the corresponding category.	
Facility	The log facility allows you to send logs to different files in the syslog server. Refer to the documentation of your syslog program for more details.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	
Syslog Server Setup		
Active	Select this check box to have the device send logs to this syslog server. Clear the check box if you want to create a syslog server entry but not have the device send logs to it (you car edit the entry later).	
Server Address	Enter the IPv4 or IPv6 address of the syslog server.	
UDP Port	The default syslog server port is 514. If your syslog server uses a different port, configure the one it uses here.	

LABEL	DESC RIPTIO N	
Log Level	Select the severity levels of the logs that you want the device to send to this syslog server. The lower the number, the more critical the logs are.	
Add	Click <b>Add</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel t save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	
Clear	Click <b>Clear</b> to return the fields to the factory defaults.	
Index	This is the index number of a syslog server entry. Click this number to edit the entry.	
Active	This field displays <b>Yes</b> if the device is to send logs to the syslog server. <b>No</b> displays if the device is not to send logs to the syslog server.	
IP Address	This field displays the IP address of the syslog server.	
UDP Port	This field displays the port of the syslog server.	
Log Level	This field displays the severity level of the logs that the device is to send to this syslog server.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Delete	Click <b>De le te</b> to remove the selected entries.	
Cancel	Click Cancel to begin configuring this screen afresh.	

 Table 147
 Management > Syslog Setup (continued)

# C HAPTER 38 Cluster Management

## 38.1 Cluster Management Overview

This chapter introduces cluster management.


Cluster Management allows you to manage switches through one Switch, called the cluster manager. The switches must be directly connected and be in the same VLAN group so as to be able to communicate with one another.

Table 148 Zyxel Clustering Management Specifications

Maximum number of cluster members	24
Cluster Member Models	Must be compatible with Zyxel cluster management implementation.
Cluster Manager	The Switch through which you manage the cluster member switches.
Cluster Members	The switches being managed by the cluster manager Switch.

In the following example, switch **A** in the basement is the cluster manager and the other switches on the upper floors of the building are cluster members.

#### Figure 222 Clustering Application Example



### 38.1.1 What You Can Do

• Use the Cluster Management Status screen (Section 38.2 on page 300) to view the role of the Switch within the cluster and to access a cluster member Switch's Web Configurator.

• Use the Clustering Management Configuration screen (Section 38.1 on page 299) to configure clustering management.

## 38.2 Cluster Management Status

Use this screen to view the role of the Switch within the cluster and to access a cluster member Switch's Web Configurator.

Click **Management** > **Cluster Management** in the navigation panel to display the following screen.

Note: A cluster can only have one manager.

Clurter	ring Wansgement St	atus		Configuration
Station		None		
Managere		00000000000000000		
The Number Of <i>i</i>				
Index	MacAddi	None	Model	Shrine

Figure 223 Management > Cluster Management Status

The following table describes the labels in this screen.

Table 149 Management > Clust	ter Manaaement Status
------------------------------	-----------------------

IABEL	DESC RIPTIO N
Status	This field displays the role of this Switch within the cluster.
	Manager
	Member (you see this if you access this screen in the cluster member Switch directly and not via the cluster manager)
	None (neither a manager nor a member of a cluster)
Manager	This field displays the cluster manager Switch's hardware MAC address.
The Number of Member	This field displays the number of switches that make up this cluster. The following fields describe the cluster member switches.
Index	You can manage cluster member switches via the cluster manager Switch. Each number in the <b>Index</b> column is a hyperlink leading to the cluster member Switch's Web Configurator (see Figure 225 on page 303).
MacAddr	This is the cluster member Switch's hardware MAC address.
Name	This is the cluster member Switch's System Name.
Model	This field displays the model name.
Status	This field displays:
	<b>Online</b> (the cluster member Switch is accessible)
	<b>Enor</b> (for example the cluster member Switch password was changed or the Switch was set as the manager and so left the member list, and so on)
	<b>Offline</b> (the Switch is disconnected – <b>Offline</b> shows approximately 1.5 minutes after the link between cluster member and manager goes down)

GS1350 Series User's Guide

## 38.3 Clustering Management Configuration

Use this screen to configure clustering management. Click **Management** > **Cluster Management** > **Configuration** to display the next screen.

_		
	nay Manageround Claudage advan	Malas
Classificanty Manuary		
A Los	11	
Name		
M B	1	
	Jappy Control	
Clustering Candia	date.	
		-
1k <sup>2</sup>		
		-
Frankword		
	Add Conset Isleah	
index.	MacAddr Hame Model	
11985		_
	Records Andrews	

Figure 224 Management > Cluster Management > Configuration

The following table describes the labels in this screen.

Table 150	Management >	Cluster Management >	Configuration

LABEL	DESC RIPHO N
Clustering Manager	The following fields relate to configuring the cluster manager.
Active	Select <b>Ac tive</b> to have this Switch become the cluster manager switch. A cluster can only have one manager. Other (directly connected) switches that are set to be cluster managers will not be visible in the <b>Clustering Candidates</b> list. If a switch that was previously a cluster member is later set to become a cluster manager, then its <b>Status</b> is displayed as <b>Error</b> in the <b>Cluster Management Status</b> screen and a warning icon ( 📩 ) appears in the member summary list below.
Name	Type a name to identify the <b>Clustering Manager</b> . You may use up to 32 printable characters (spaces are allowed).
VID	This is the VLAN ID and is only applicable if the Switch is set to <b>802.1Q</b> VLAN. All switches must be directly connected and in the same VLAN group to belong to the same cluster. Switches that are not in the same VLAN group are not visible in the <b>Clustering Candidates</b> list. This field is ignored if the <b>Clustering Manager</b> is using <b>Port-based</b> VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.

GS1350 Series User's Guide

LABEL	DESC RIPTIO N		
Cancel	Click Cancel to begin configuring this screen afresh.		
Clustering Candidate	The following fields relate to the switches that are potential cluster members.		
List	A list of suitable candidates found by auto-discovery is shown here. The switches must be directly connected. Directly connected switches that are set to be cluster managers will not be visible in the <b>Clustering Candidate</b> list. Switches that are not in the same management VLAN group will not be visible in the <b>Clustering Candidate</b> list.		
Password	Each cluster member's password is its Web Configurator password. Select a member in the <b>Clustering Candidate</b> list and then enter its Web Configurator password. If that switch administrator changes the Web Configurator password afterwards, then it cannot be managed from the <b>Cluster Manager</b> . Its <b>Status</b> is displayed as <b>Enor</b> in the <b>Cluster Management Status</b> screen.		
	If multiple devices have the same password then hold [SHIFT] and click those switches to select them. Then enter their common Web Configurator password.		
Add	Click <b>Add</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click Cancel to begin configuring this screen afresh.		
Refresh	Click <b>Re fre sh</b> to perform auto-discovery again to list potential cluster members.		
The next summary tab	le shows the information for the clustering members configured.		
Index	This is the index number of a cluster member switch.		
MacAddr	This is the cluster member switch's hardware MAC address.		
Name	This is the cluster member switch's System Name.		
Model	This is the cluster member switch's model name.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
Remove	Click the <b>Remove</b> button to remove the selected cluster member switches from the cluster.		
Cancel	Click Cancel to begin configuring this screen afresh.		

#### Table 150 Management > Cluster Management > Configuration (continued)

### 38.4 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 38.4.1 Cluster Member Switch Management

Go to the **Clustering Management Status** screen of the cluster manager switch and then select an **Index** hyperlink from the list of members to go to that cluster member switch's Web Configurator home page. This cluster member Web Configurator home page and the home page that you would see if you accessed it directly are different.




Figure 225 Cluster Management: Cluster Member Web Configurator Screen

#### 38.4.1.1 Uploading Firmware to a Cluster Member Switch

You can use FTP to upload firmware to a cluster member switch through the cluster manager switch as shown in the following example.

Figure 226 Example: Uploading Firmware to a Cluster Member Switch

```
C:\>ftp 192.168.1.1
Connected to 192.168.1.1.
220 Switch FTP version 1.0 ready at Thu Jan 1 00:58:46 1970
User (192.168.0.1: (none)): admin
331 Enter PASS command
Password:
230 Logged in
ftp> ls
200 Port command okay
150 Opening data connection for LIST
--w--w-- 1 owner group 3042210 Jul 01 12:00 ras
-rw-rw-rw-1 ownergroup393216 Jul 01 12:00 config-w--w--w-1 ownergroup0 Jul 01 12:00 fw-00-a
                                       0 Jul 01 12:00 fw-00-a0-c5-01-23-46
                                            0 Jul 01 12:00 config-00-a0-c5-01-23-46
-rw-rw-rw- 1 owner group
226 File sent OK
ftp: 297 bytes received in 0.00Seconds 297000.00Kbytes/sec.
ftp> bin
200 Type I OK
ftp> put 460ABPI0.bin fw-00-a0-c5-01-23-46
200 Port command okay
150 Opening data connection for STOR fw-00-a0-c5-01-23-46
226 File received OK
ftp: 262144 bytes sent in 0.63Seconds 415.44Kbytes/sec.
ftp>
```

The following table explains some of the FTP parameters.

FIP PARAMEIER	DESC RIPIIO N
User	Enter "admin".
Password	The Web Configurator password default is 1234.
ls	Enter this command to list the name of cluster member switch's firmware and configuration file.
460ABPI0.bin	This is the name of the firmware file you want to upload to the cluster member switch.
fw-00-a0-c5-01-23-46	This is the cluster member switch's firmware name as seen in the cluster manager switch.
config-00-a0-c5-01-23-46	This is the cluster member switch's configuration file name as seen in the cluster manager switch.

Table 151	FTP Upload to Cluster Member Example
-----------	--------------------------------------

## C HAPTER 39 MAC Table

## 39.1 MAC Table Overview

This chapter introduces the MAC Table screen.

The **MAC Table** screen (a MAC table is also known as a filtering database) shows how frames are forwarded or filtered across the Switch's ports. It shows what device MAC address, belonging to what VLAN group (if any) is forwarded to which port(s) and whether the MAC address is dynamic (learned by the Switch) or static (manually entered in the **Static MAC Forwarding** screen).


#### 39.1.1 What You Can Do

Use the **MAC Table** screen (Section 39.2 on page 306) to check whether the MAC address is dynamic or static.

#### 39.1.2 What You Need to Know

The Switch uses the MAC table to determine how to forward frames. See the following figure.

- 1 The Switch examines a received frame and learns the port on which this source MAC address came.
- 2 The Switch checks to see if the frame's destination MAC address matches a source MAC address already learned in the MAC table.
  - If the Switch has already learned the port for this MAC address, then it forwards the frame to that port.
  - If the Switch has not already learned the port for this MAC address, then the frame is flooded to all ports. Too much port flooding leads to network congestion.
  - If the Switch has already learned the port for this MAC address, but the destination port is the same as the port it came in on, then it filters the frame.



GS1350 Series User's Guide

## 39.2 Viewing the MAC Table

Use this screen to check whether the MAC address is dynamic or static.

Click Management > MAC Table in the navigation panel to display the following screen.

Figure 228 Management > MAC Table

MAC toble				
Consilion Sort by Incoder type		o MAC forwarding	· · · · · · · · · · · · · · · · · · ·	
	Securit Incruder			
Indea	MAC Address	VID	Port	Гурн
1	00:00:56:00:01:02	1	3	Dynamia
2	00:03:21:10:be:00	1	3	Dynomic
3	00:08:21:10:77:7c	1	8	Dynomic
A	00:02:21:10:02:24	1	3	Dynomic
5	00:03:21:11:02:01	1	3	Dynamic
6	00:08:54:72:od:bc	1	3	Dynomic
7	00:00:03:00:3d:0d	1	8	Dynamic
Л	0000ene0600001ctod/k	1	3	Dynamic
9	00:0ene3:01:75:e2	1	3	Dynamic
10	00:0ere3:03:e6:e6	1	3	Dynamic

Table 152 Mar	naaement >	MAC	Table
---------------	------------	-----	-------

IABEL	DESC RIPIIO N
Condition	Select one of the buttons and click $\mathbf{Seacch}$ to only display the data which matches the criteria you specified.
	Select All to display any entry in the MAC table of the Switch.
	Select Static to display the MAC entries manually configured on the Switch.
	Select <b>MAC</b> and enter a MAC address in the field provided to display a specified MAC entry.
	Select <b>VID</b> and enter a VLAN ID in the field provided to display the MAC entries belonging to the specified VLAN.
	Select <b>Port</b> and enter a port number in the field provided to display the MAC addresses which are forwarded on the specified port.
	Select <b>Thunk</b> and type the ID of a trunk group to display all MAC addresses learned from the port(s) in the trunk group.
Sort by	Define how the Switch displays and arranges the data in the summary table below.
	Select $\mathbf{MAC}$ to display and arrange the data according to MAC address.
	Select $\mathbf{VID}$ to display and arrange the data according to VLAN group.
	Select <b>PORT</b> to display and arrange the data according to port number.
Transfer Type	Select <b>Dynamic to MAC forwarding</b> and click the <b>Transfer</b> button to change all dynamically learned MAC address entries in the summary table below into static entries. They also display in the <b>Static MAC Forwarding</b> screen.
	Select <b>Dynamic to MAC filtering</b> and click the <b>Transfer</b> button to change all dynamically learned MAC address entries in the summary table below into MAC filtering entries. These entries will then display only in the <b>Filtering</b> screen and the default filtering action is <b>Disc ard source</b> .
Search	Click this to search data in the MAC table according to your input criteria.
Transfer	Click this to perform the MAC address transferring you selected in the Tiansfer Type field.
Cancel	Click Cancel to change the fields back to their last saved values.
Index	This is the incoming frame index number.
MAC Address	This is the MAC address of the device from which this incoming frame came.
VID	This is the VLAN group to which this frame belongs.
Port	This is the port where the above MAC address is forwarded.
Туре	This shows whether the MAC address is <b>dynamic</b> (learned by the Switch) or <b>static</b> (manually entered in the <b>Static MAC Forwarding</b> screen).

## C HAPTER 40 ARP Table

## 40.1 Overview

This chapter introduces ARP Table.

Address Resolution Protocol (ARP) is a protocol for mapping an Internet Protocol address (IP address) to a physical machine address, also known as a Media Access Control or MAC address, on the local area network.

An IP (version 4) address is 32 bits long. In an Ethernet LAN, MAC addresses are 48 bits long. The ARP Table maintains an association between each MAC address and its corresponding IP address.

### 40.1.1 What You Can Do

Use the ARP Table screen (Section 40.2 on page 308) to view IP-to-MAC address mappings.

### 40.1.2 What You Need to Know

When an incoming packet destined for a host device on a local area network arrives at the Switch, the Switch's ARP program looks in the ARP Table and if it finds the address, it sends it to the device.

## 40.2 Viewing the ARP Table

Use the ARP table to view IP-to-MAC address mappings and remove specific dynamic ARP entries.

Click Management > ARP Table in the navigation panel to open the following screen.

308

	Rife Torriske					
Conditio	'n	8 A 9 P 9 N	Address 😡	1900	_	
		-	shi theo	1		
Index	IP Address	MAC Address	VID	Port	Aq <b>e</b> (0)	Type
I	10714 NO44	the first of the M	I		<b>**</b> 3	1.91.21

#### Figure 229 Management > ARP Table

Table 153	Management > ARP Table

IABEL	DESC RIPTIO N
Condition	Specify how you want the Switch to remove ARP entries when you click <b>Flush</b> .
	Select All to remove all of the dynamic entries from the ARP table.
	Select <b>IP Address</b> and enter an IP address to remove the dynamic entries learned with the specified IP address.
	Select <b>Port</b> and enter a port number to remove the dynamic entries learned on the specified port.
Flush	Click <b>Flush</b> to remove the ARP entries according to the condition you specified.
Cancel	Click Cancel to return the fields to the factory defaults.
Index	This is the ARP table entry number.
IP Address	This is the IP address of a device connected to a Switch port with the corresponding MAC address below.
MAC Address	This is the MAC address of the device with the corresponding IP address above.
VID	This field displays the VLAN to which the device belongs.
Port	This field displays the port to which the device connects. <b>CPU</b> means this IP address is the Switch's management IP address.
Age(s)	This field displays how long (in seconds) an entry can still remain in the ARP table before it ages out and needs to be relearned. This shows $0$ for a static entry.
Туре	This shows whether the IP address is dynamic (learned by the Switch) or static (manually configured in the <b>Basic Setting</b> > <b>IP Setup</b> or <b>IP Applic ation</b> > <b>ARP Setup</b> > <b>Static ARP</b> screen).

# C HAPTER 41 Path MTU Table

## 41.1 Path MTU Overview

This chapter introduces the IPv6 Path MTU table.

The largest size (in bytes) of a packet that can be transferred over a data link is called the maximum transmission unit (MTU). The Switch uses Path MTU Discovery to discover Path MTU (PMTU), that is, the minimum link MTU of all the links in a path to the destination. If the Switch receives an ICMPv6 Packet Too Big error message after sending a packet, it fragments the next packet according to the suggested MTU in the error message.

## 41.2 Viewing the Path MTU Table

Use this screen to view IPv6 path MTU information on the Switch. Click **Management** > **Path MTU Table** in the navigation panel to display the screen as shown.

Figure 230	Management > Path MTU Table
l all	i MTU Table

Folh MTU Table Anth Witt organy terre - 18			
Index	Destination Address	MIU	Expres

Table 154 Management > Path MTU Table

LABEL	DESC RIPTIO N
Path MTU aging time	This field displays how long an entry remains in the Path MTU table before it ages out and needs to be relearned.
Index	This field displays the index number of each entry in the table.
Destination Address	This field displays the destination IPv6 address of each path or entry.
MTU	This field displays the maximum transmission unit of the links in the path.
Expire	This field displays how long (in minutes) an entry can still remain in the Path MTU table before it ages out and needs to be relearned.

# C HAPTER 42 Configure Clone

## 42.1 Overview

This chapter shows you how you can copy the settings of one port onto other ports.

## 42.2 Configure Clone

Cloning allows you to copy the basic and advanced settings from a source port to a destination port or ports. Click **Management** > **Configure Clone** to open the following screen.

Configure Clone	
Source	Destination
8 Port	
ort Features	
	Active Nome
Basic Selling	Seed / Duslex
	E Speed / Digitek
	VLANIg VLANig Member
	Nondwarkh Control
	Lort Security
	Broadcoal Stern Central
	— Minoring
	Gueung Method
	CRMP1 benng
	Spanning Tree Protocol
Advanced Application	Port Beaced VLAN
	Loop Guard
	Di Ki <sup>o</sup> Shooping
	ARP Learning
	CHU Insteation
	Power over Libernet
	SNMP Trop
	Creen Elhomol
	Detoerv
	Auto PD Recovery
	Apply Concel

Figure 231 Management > Configure Clone

Table 155	Management >	Configure Clone
-----------	--------------	-----------------

IABEL	DESC RIPIIO N
Source/ Destination Port	Enter the source port under the <b>Source</b> label. This port's attributes are copied. Enter the destination port or ports under the <b>Destination</b> label. These are the ports which are going to have the same attributes as the source port. You can enter individual ports separated by a comma or a range of ports by using a dash. Example: <b>2, 4, 6</b> indicates that ports 2, 4 and 6 are the destination ports.
	<b>2-6</b> indicates that ports 2 through 6 are the destination ports.
Basic Setting	Select * to apply all settings to the port. Use this first to select the common settings and then remove the settings you do not want copied. Select which port settings (you configured in the <b>Basic Setting</b> menus) should be copied to the
	destination ports.
Advanced Application	Select which port settings (you configured in the Advanced Application menus) should be copied to the destination ports.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 43 IPv6 Neighbor Table

## 43.1 IPv6 Neighbor Table Overview

This chapter introduces the IPv6 neighbor table.

An IPv6 host is required to have a neighbor table. If there is an address to be resolved or verified, the Switch sends out a neighbor solicitation message. When the Switch receives a neighbor advertisement in response, it stores the neighbor's link-layer address in the neighbor table. You can also manually create a static IPv6 neighbor entry using the **Basic Setting > IPv6 > IPv6 Configuration > IPv6 Neighbor Setup** screen.

When the Switch needs to send a packet, it first consults other table to determine the next hop. Once the next hop IPv6 address is known, the Switch looks into the neighbor table to get the link-layer address and sends the packet when the neighbor is reachable. If the Switch cannot find an entry in the neighbor table or the state for the neighbor is not reachable, it starts the address resolution process. This helps reduce the number of IPv6 solicitation and advertisement messages.

## 43.2 Viewing the IPv6 Neighbor Table

Use this screen to view IPv6 neighbor information on the Switch. Click **Management > IPv6 Neighbor Table** in the navigation panel to display the screen as shown.

Figure 232 Management > IPv6 Neighbor Table

Pes N	elghiocr Table			
Set by:	Accelent 1	96%C	history -	
Index.	Address	MAC	Skilus Type	Interface

T		
Table 156	Management > IPv6 Neighbor Table	

IABEL	DESC RIPIIO N
Sort by	Select this to display and arrange the data according to IPv6 address ( <b>Address</b> ), MAC address ( <b>MAC</b> ) or IPv6 interface ( <b>Interface</b> ). The information is then displayed in the summary table below.
Index	This field displays the index number of each entry in the table.
Address	This field displays the IPv6 address of the Switch or a neighboring device.
MAC	This field displays the MAC address of the IPv6 interface on which the IPv6 address is configured or the MAC address of the neighboring device.

IABEL	DESC RIPTIO N					
Status	This field displays whether the neighbor IPv6 interface is reachable. In IPv6, "reachable" means an IPv6 packet can be correctly forwarded to a neighbor node (host or router) and the neighbor can successfully receive and handle the packet. The available options in this field are:					
	• reachable (R): The interface of the neighboring device is reachable. (The Switch has received a response to the initial request.)					
	<ul> <li>stale (S): The last reachable time has expired and the Switch is waiting for a response to another initial request. The field displays this also when the Switch receives an unrequested response from the neighbor's interface.</li> </ul>					
	<ul> <li>delay (D): The neighboring interface is no longer known to be reachable, and traffic has been sent to the neighbor recently. The Switch delays sending request packets for a short to give upper-layer protocols a chance to determine reachability.</li> </ul>					
	• probe (P): The Switch is sending request packets and waiting for the neighbor's response.					
	<ul> <li>invalid (IV): The neighbor address is with an invalid IPv6 address.</li> </ul>					
	<ul> <li>unknown (?): The status of the neighboring interface cannot be determined for some reason.</li> <li>incomplete (I): Address resolution is in progress and the link-layer address of the neighbor has not yet been determined. The interface of the neighboring device did not give a complete response.</li> </ul>					
Туре	This field displays the type of an address mapping to a neighbor interface. The available options in this field are:					
	• other (O): none of the following type.					
	local (L): A Switch interface is using the address.					
	<ul> <li>dynamic (D): The IP address to MAC address can be successfully resolved using IPv6 Neighbor Discovery protocol. Is it similar as IPv4 ARP (Address Resolution protocol).</li> <li>static (S): The interface address is statically configured.</li> </ul>					
Interface	This field displays the ID number of the IPv6 interface on which the IPv6 address is created or through which the neighboring device can be reached.					

## C HAPTER 44 Port Status

## 44.1 Overview

This chapter introduces the port status screens.

### 44.2 Port Status

This screen displays a port statistical summary with links to each port showing statistical details. To view the port statistics, click **Status** in all Web Configurator screens and then the **Port Status** link in the **Quick Links** section of the **Status** screen to display the **Port Status** screen as shown next. You can also click **Management** > **Port Status** to see the following screen.

Po	d Status									DOM	Milantin
				PD .	LACP				Do REAS	Ra KB/s	
1	port1	103/F	FORWARDING	Qn	Disabled	252980	12252	D	0.504	0.0	8:29:45
2		Down	510P	07	Disabled	0	D	D	0.0	0.0	0:00:00
.2		103/7	FORWARDING	08	Disabled	33702	270160	0	13.315	1.575	8:20:51
4		103/7	FORWARDING	On	Disabled	26307-5	14034	0	0.505	0.0	8:20:45
2		Down	STOP	08	Discipled	0	D	D	0.0	0.0	0:00:00
4		Down	8008		Disobled	0	0	0	0.0	0.0	00000
Are											
Port	_		Clear Counter								

Figure 233 Port Status

The following table describes the labels in this screen.

Table	157	Port Status
IUDIC	107	1 011 310103

IABEL	DESC RIPTIO N
Port	This identifies the Ethernet port. Click a port number to display the <b>Port De tails</b> screen (refer to Figure 234 on page 317).
Name	This is the name you assigned to this port in the <b>Basic Setting</b> > <b>Port Setup</b> screen.
Link	This field displays the speed (either <b>10M</b> for 10 Mbps, <b>100M</b> for 100 Mbps, or <b>1G</b> for 1 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). It also shows the cable type ( <b>Copper</b> or <b>Fiber</b> ) for the combo ports. This field displays <b>Down</b> if the port is not connected to any device.
State	If STP (Spanning Tree Protocol) is enabled, this field displays the STP state of the port. See Section 13.1 on page 144 for more information.
	If STP is disabled, this field displays <b>FO RWARDING</b> if the link is up, otherwise, it displays <b>STO P</b> .
	When LACP (Link Aggregation Control Protocol) and STP are in blocking state, it displays $Blocking$ .
PD	This field displays whether or not a powered device (PD) is allowed to receive power from the Switch on this port.

GS1350 Series User's Guide

IABEL	DESC RIPIIO N
LACP	This fields displays whether LACP (Link Aggregation Control Protocol) has been enabled on the port.
TxPkts	This field shows the number of transmitted frames on this port.
RxPkts	This field shows the number of received frames on this port.
Errors	This field shows the number of received errors on this port.
Tx KB/s	This field shows the number of kilobytes per second transmitted on this port.
Rx KB/s	This field shows the number of kilobytes per second received on this port.
Up Time	This field shows the total amount of time in hours, minutes and seconds the port has been up.
Clear Counter	Select <b>Port</b> , enter a port number and then click <b>ClearCounter</b> to erase the recorded statistical information for that port, or select <b>Any</b> to clear statistics for all ports.

### 44.2.1 Port De tails

Click a number in the **Port** column in the **Port Status** screen to display individual port statistics. Use this screen to check status and detailed performance data about an individual port on the Switch.

Fort De	tain		Port Natus
Part Info	Port NO.	1	
	Marine	pant .	
	ink (	1.547	
	Arte.	DORWARDING:	
	A CT	Rivoble d	
	Table	S (2)(23	
	Ld Mb	260/5	
	LIN17	2	
	la kE/a	0.587	
	is clined to 6	0.0	
	Statistics.	0.844	
	Section descriptions	0.0	
	Di den.	54 M 7	
Di Racket	Unicost	267%	
	Multiness I	5405041	
	Second Install	5 A 17 5 7	
	* a 24		
RX Ponket	Unicost	1662.3	
	Multimeters I	2000.0	
	Second const	17(1-5)	
	Double.	2	
FX Collision	Single	D	
	Molt quite		
	Sciencive	5	
	ane.	5	
Error Pocketi	EX CRC	D	
	ength	5	
	5. ni	2	
0 Inhibition	64	381136	
	63 W 107	5002	
	190 no 953	7.1576	
	256 to 511	20n01	
	512 to 1020	25166	
	102415-1518	11	
	Clent	2	

Figure 234 Port Status > Port Details

The following table describes the labels in this screen.

#### Table 158 Port Status: Port Details

IABEL	DESC RIPIIO N
Port Info	
Port NO.	This field displays the port number you are viewing.
Name	This field displays the name of the port.
Link	This field displays the speed (either 10M for 10 Mbps, 100M for 100 Mbps, or 1G for 1 Gbps) and the duplex (F for full duplex or H for half duplex). It also shows the cable type (Copper or Fiber) for the combo ports. This field displays Down if the port is not connected to any device.
State	If STP (Spanning Tree Protocol) is enabled, this field displays the STP state of the port. See Section 13.1 on page 144 for more information.
	If STP is disabled, this field displays FORWARDING if the link is up, otherwise, it displays STOP.
	When LACP (Link Aggregation Control Protocol) and STP are in blocking state, it displays <b>Blocking</b> .

GS1350 Series User's Guide

LABEL	DESC RIPIIO N								
LACP	This field shows if LACP is enabled on this port or not.								
TxPkts	This field shows the number of transmitted frames on this port.								
RxPkts	This field shows the number of received frames on this port.								
Errors	This field shows the number of received errors on this port.								
Tx kB/s	This field shows the number of kilobytes per second transmitted on this port.								
Tx Utilization%	This field shows the percentage of actual transmitted frames on this port as a percentage of the <b>Iink</b> speed.								
Rx kB/s	This field shows the number of kilobytes per second received on this port.								
Rx Utilization%	This field shows the percentage of actual received frames on this port as a percentage of the <b>Link</b> speed.								
Up Time	This field shows the total amount of time the connection has been up.								
Tx Packet									
The following fie	elds display detailed information about packets transmitted.								
Unicast	This field shows the number of good unicast packets transmitted.								
Multicast	This field shows the number of good multicast packets transmitted.								
Broadcast	This field shows the number of good broadcast packets transmitted.								
Pause	This field shows the number of 802.3x Pause packets transmitted.								
Rx Packet									
	elds display detailed information about packets received.								
Unicast	This field shows the number of good unicast packets received.								
Multicast	This field shows the number of good multicast packets received.								
Broadcast	This field shows the number of good broadcast packets received.								
Pause	This field shows the number of 802.3x Pause packets received.								
TX Collision									
	elds display information on collisions while transmitting.								
0									
Single	This is a count of successfully transmitted packets for which transmission is inhibited by exactly one collision.								
Multiple	This is a count of successfully transmitted packets for which transmission was inhibited by more than one collision.								
Excessive	This is a count of packets for which transmission failed due to excessive collisions. Excessive collision is defined as the number of maximum collisions before the retransmission count is reset.								
Late	This is the number of times a late collision is detected, that is, after 512 bits of the packets have already been transmitted.								
Error Packet	The following fields display detailed information about packets received that were in error.								
RX CRC	This field shows the number of packets received with CRC (Cyclic Redundant Check) errors.								
Length	This field shows the number of packets received with a length that was out of range.								
Runt	This field shows the number of packets received that were too short (shorter than 64 octets), including the ones with CRC errors.								
Distribution									
64	This field shows the number of packets (including bad packets) received that were 64 octets in length.								
65 to 127	This field shows the number of packets (including bad packets) received that were between 65 and 127 octets in length.								

Table 158 Port Status: Port Details (continued)

LABEL	DESC RIPTIO N
128 to 255	This field shows the number of packets (including bad packets) received that were between 128 and 255 octets in length.
256 to 511	This field shows the number of packets (including bad packets) received that were between 256 and 511 octets in length.
512 to 1023	This field shows the number of packets (including bad packets) received that were between 512 and 1023 octets in length.
1024 to 1518	This field shows the number of packets (including bad packets) received that were between 1024 and 1518 octets in length.
Giant	This field shows the number of packets (including bad packets) received that were between 1519 octets and the maximum frame size.
	The maximum frame size varies depending on your switch model.

Table 158 Port Status: Port Details (continued)

#### 44.2.2 DDMI

The optical SFP transceiver's support for the Digital Diagnostics Monitoring Interface (DDMI) function lets you monitor the transceiver's parameters to perform component monitoring, fault isolation and failure prediction tasks. This allows proactive, preventative network maintenance to help ensure service continuity.

Use this screen to view the DDMI status of the Switch's SFP transceivers. Click **Management** > **Port Status** > **DDMI** to see the following screen. Alternatively, click **Status** from any Web Configurator screen and then the **Port Status** link in the **Quick Links** section of the **Status** screen to display the **Port Status** screen and then click the **DDMI** link tab.

Figure 235	Management > Port Status > DDMI
------------	---------------------------------

GDWJ						Peri Statue
Pari	Vender	Part Number	Secial Number	Revision	Date Code	Transceiver
+						

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Port	This identifies the SFP port.
Vendor	This displays the vendor name of the optical transceiver.
Part Number	This displays the part number of the optical transceiver.
Serial Number	This displays the serial number of the optical transceiver.
Revision	This displays the revision number of the optical transceiver.
Date Code	This displays the date when the optical transceiver was manufactured.
Transceiver	This displays whether the connection to the optical network is up or down.

Table 159 Management > Port Status > DDMI

#### 44.2.3 DDMI De ta ils

Use this screen to view the real-time SFP (Small Form Factor Pluggable) transceiver information and operating parameters on the SFP port. The parameters include, for example, transmitting and receiving power, and module temperature.

Click a number in the Port column in the DDMI screen to view current transceivers' status.

DOM: the back					1904
Renselver Information					
Part No: A					
Connector Type					
Vendor					
Port Rumber					
Seriel Number					
Keylekan -					
Data Cede					
handes/iver					
DOM Infernation					
	Current	High Alarm Threshold	High Warn Fhreichold	Low Worn Fireshold	Low Alerm Threshold
DOM Information	Current				
DOM Information Type	Current				
DCMI Information Dyp.e December (2.) Solito (c.2) TX Max(124)	Current				
DCMI Information Pype Information (2.) Water pet/2)		Threshold	Threshold	Threshold	Threathold

Figure 236 Management > Port Status > DDMI > DDMI Details

The following table describes the labels in this screen.

Table 160	Management > Port Status > DDMI > DDMI Details

LABEL	DESC RIPTIO N						
Transceiver Inform	ation						
Port No	This identifies the SFP port.						
Connector Type	This displays the connector type of the optical transceiver.						
Vendor	This displays the vendor name of the optical transceiver.						
Part Number	This displays the part number of the optical transceiver.						
Serial Number	This displays the serial number of the optical transceiver.						
Revision	This displays the revision number of the optical transceiver.						
Date Code	This displays the date when the optical transceiver was manufactured.						
Transceiver	This displays details about the type of transceiver installed in the SFP slot.						
Calibration	This field is available only when an SFP transceiver is inserted into the SFP slot.						
	<b>Intemal</b> displays if the measurement values are calibrated by the transceiver. <b>Extemal</b> displays if the measurement values are raw data which the Switch calibrates.						
DDMI Information							
Туре	This displays the DDMI parameter.						
Temperature (C)	This displays the temperature inside the SFP transceiver in degrees Celsius.						
Voltage (V)	This displays the level of voltage being supplied to the SFP transceiver.						
TX Bias (mA)	This displays the milliamps (mA) being supplied to the SFP transceiver's Laser Diode Transmitter.						
TX Power (dbm)	This displays the amount of power the SFP transceiver is transmitting.						
RX Power (dbm)	This displays the amount of power the SFP transceiver is receiving from the fiber optic cable.						

GS1350 Series User's Guide

IABEL	DESC RIPTIO N
Current	This displays the current status for each monitored DDMI parameter.
High Alarm Threshold	This displays the high value alarm threshold for each monitored DDMI parameter. An alarm signal is reported to the Switch if the monitored DDMI parameter reaches this value.
High Warn Threshold	This displays the high value warning threshold for each monitored DDMI parameter. A warning signal is reported to the Switch if the monitored DDMI parameter reaches this value.
Low Warn Threshold	This displays the low value warning threshold for each monitored DDMI parameter. A warning signal is reported to the Switch if the monitored DDMI parameter reaches this value.
Low Alarm Threshold	This displays the low value alarm threshold for each monitored DDMI parameter. An alarm signal is reported to the Switch if the monitored DDMI parameter reaches this value.

Table 160 Management > Port Status > DDMI > DDMI Details (continued)

### 44.2.4 Port Utilization

This screen displays the percentage of actual transmitted or received frames on a port as a percentage of the **Link** speed. To view port utilization, click **Management > Port Status > Port Utilization** to see the following screen. Alternatively, click **Status** from any Web Configurator screen and then the **Port Status** link in the **Quick Links** section of the **Status** screen to display the **Port Status** screen and then click the **Utilization** link tab.

Figure 237 Management > Port Status > Utilization

80	d 10 de colonne				Ford Shak
Feel 1	Link.	Do MBAN	to Universitien'S	EX KEAN	Re Universition's
1	NHT -	1.114	8 D	0.060	0.0
2	Deven	0.0	6.0	0.0	
2	1041	0.060	5 D	1.245	ω
2	517E	448	100	11.000	100
	Lines :	61-0	10.05	0.00	1111
0	Deven	0.0	2.0	0.0	(M)

IABEL	DESC RIPIIO N
Port	This identifies the Ethernet port.
Link	This field displays the speed (either <b>10M</b> for 10 Mbps, <b>100M</b> for 100 Mbps, or <b>1G</b> for 1 Gbps) and the duplex ( <b>F</b> for full duplex). It also shows the cable type ( <b>Copper</b> or <b>Fiber</b> ) for the combo ports. This field displays <b>Down</b> if the port is not connected to any device.
Tx kB/s	This field shows the transmission speed of data sent on this port in kilobytes per second.
Tx Utilization%	This field shows the percentage of actual transmitted frames on this port as a percentage of the Link speed.
Rx KB/s	This field shows the transmission speed of data received on this port in kilobytes per second.
Rx Utilization%	This field shows the percentage of actual received frames on this port as a percentage of the <b>Link</b> speed.

Table 161 Management > Port Status > Utilization

# CHAPTER 45 Surveillance Mode

## 45.1 Overview

Aside from the Web Configurator in Standard mode that has a complete set of configuration for network installation, you can switch to Surveillance mode.

Surveillance mode is a set of menus specifically designed for users who are mostly using the Switch for configuring and managing PoE devices like IP cameras.

Use a browser that supports HTML5, such Microsoft Edge, Internet Explorer 11, Mozilla Firefox, or Google Chrome. The recommended screen resolution is 1366 by 768 pixels.

The following sections introduces the configuration and functions of the Web Configurator In Surveillance mode.

Click **Surveillance** at the top right corner of the Web Configurator to switch between the Web Configurator's **Standard** or **Surveillance** mode.

Figure 238 Web Configurator - Surveillance Mode



This section describes the screens for System Status and Neighbor Details.


### 45.1.1 What You Can Do

- Use the Summary screen (Section 45.2 on page 322) to see the Switch's general device information, system status, and IP addresses. You can also display other status screens for more information.
- Use the **Neighbor Detail** screen (Section 45.2.1 on page 324) to view and manage Switch's neighbor devices.

### 45.2 Summary

The **Summary** screen displays when you log into the Switch or click **Summary** at the top right corner of the Web Configurator. The **Summary** screen displays general device information, system status, connected ports, used power for PoE devices, and its IP addresses.

322



										.A.	digo Manife	nih 10 line
ummary											ite	nonicidinat )
Ca	ninist Ports								Used	Pawer(W)		
	-		IF CAL							1		
	2		C/her							<b>0</b> 30		
et s ferree	•	jim Social	Pot Desw	konsteisen Setteffi		Dranstat Jurga	Tieretter Tielet	liatere Rearrie	1	Ukomend Seetin		Stan
1	÷	Davin)	107	9.62 9.0	30	Dictrie	-	-			1.12	10
1		Down:	101	9.02) 0.0	30	Dette				<b>.</b>		
1	-	(390)	0.0	0.07 0.0	45	Center	3	-		4	100	- jii
		.00vm	0.0	1.0) 0.0		Decte				1		
	÷	100000	9.0	0-03 0-0		Obstitie		(343,84)		4	112	- 17
1	-	0ovn	500	0.0/		Doctrie				ų.		

Table	162	Summary
IUDIE	IUZ	JUITINGLY

LABEL	DESC RIPTIO N				
Auto Refresh	Enter the number of seconds when the <b>Sum m a ry</b> screen details will be updated. Click the Pause or Play icon to stop or resume the screen update, or to update the automatic refresh interval.				
Connect Ports	This chart displays the number of ports with connection ( <b>IP CAM + NVR + O the rs</b> ) over the total number of ports on this Switch.				
Used Power(W)	This chart displays the used PoE Watts over the total number of Watts provided on this Switch.				
Port	This field displays the port of this Switch.				
Port Name	This field displays the port description of this Switch.				
PD Health	This field displays the status of auto PD recovery on this port.				
	<ul> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not supply power to the connected PD.</li> <li>Note: The status will NOT be updated instantaneously after enabling or disabling the Active switch in the Port &gt; Auto PD Recovery screen. It will wait until the configured Resume Polling Interval (sec) has lapsed.</li> </ul>				
Link Speed	This shows the speed (either <b>10M</b> for 10Mbps, <b>100M</b> for 100Mbps, or <b>1G</b> for 1 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). This field displays <b>Down</b> if the port is not connected to any device.				
PoE Draw	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.				
Bandwidth Tx/Rx (%)	This field displays the percentage of bandwidth usage on this port as a percentage of the <b>Link Speed</b> .				
CRC	This field displays the number of packets received with CRC (Cyclic Redundant Check) errors.				

LABEL	DESC RIPTIO N
Extended Range	This field shows whether PoE range is extended up to 250 meters for the port on this Switch.
Device Type	This field displays the model name of this Switch.
System Name	This field displays the name used to identify the Switch on any network.
IP	This field displays the Switch's current IPv4 address.
Discovered Devices	This field displays the <b>Ne ig hb or De ta il</b> of the discovered device by clicking the link.
Action	Click the <b>Reboot</b> button to restart the neighbor device. A warning message "Are you sure you want to reboot the powered device?" appears prompting you to confirm the action. After confirming the action a count down button (from 5 to 0) starts.
	Click the <b>Default</b> button to reset the neighbor device to its factory default settings. A warning message "Are you sure you want to reset the AP to factory default?" appears prompting you to confirm the action.

#### Table 162 Summary (continued)

#### 45.2.1 Neighbor Detail Screen

The **Neighbor Detail** screen allows you to view and manage the Switch's neighboring devices more conveniently. It uses Layer Link Discovery Protocol (LLDP) to discover all neighbor devices connected to the Switch including non-Zyxel devices. You can perform tasks on the neighboring devices like login, reboot (turn the power off and then back on again), and reset to factory default settings in the **Neighbor Detail** screen. For more information on LLDP, see (Section 27.1 on page 208).

This screen shows the neighboring device first recognized on an Ethernet port of the Switch. Device information is displayed in gray when the neighboring device is offline.

Up to 10 neighboring device records per Ethernet port can be retained in this screen even when the devices are offline. When the maximum number of neighboring device records per Ethernet port is reached, new device records automatically overwrite existing offline device records, starting with the oldest existing offline device record first.

Click Summary > Neighbor Detail to see the following screen.

and from	<u>, a</u>							W Physical
								100
+ њп								
Miz								
F red ()								1 1 an
+ Nota								
- No F								A 180
For the second	NUMBER		. where both	1784	fol tree.	$\sim$	31000	L.C. Const.
Friday (12)	252	8	Uderd konge		ne direkt	TEAL LOSCY		
sains <del>it</del>								
Selection (SVS) 4	348 (c)	(M) -		222720 X	(%);	2,32,5	1-396	
Locator Hogistus	UNR D		Single a	a aperator (1990). N	wet allowership		Ceske Lost +	
- Ind A								

Figure 240 Summary > Neighbor Detail

IABEL	DESC RIPTIO N
Search Ports	Enter the port number and click the magnify icon to view and manage the neighboring device connected to the port.
Flush All	Click the <b>Flush All</b> button to remove information about neighbors learned on all the ports of the Switch.
Port	This shows the port of the Switch, on which the neighboring device is discovered.
Flush	Click the <b>Flush</b> button to remove information about neighbors learned on the selected ports.
Port Name	This shows the port description of the Switch.
PD Health	This shows the status of auto PD recovery on this port.
	<ul> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not supply power to the connected PD.</li> <li>Note: The status will NOT be updated instantaneously after enabling or disabling the Active switch in the Port &gt; Auto PD Recovery screen. It will wait until the configured Resume Polling Interval (sec) has lapsed.</li> </ul>
Link Speed	This shows the speed (either <b>10M</b> for 10Mbps, <b>100M</b> for 100Mbps, or <b>1G</b> for 1 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). This field displays <b>Down</b> if the port is not connected to any device.
PoE Draw (W)	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.
Action	Click the <b>Reboot</b> button to turn OFF the power of the neighbor device and turn it back ON again.
	Note: The Switch must support power sourcing (PSE) or the network device is a powered device (PD).
Bandwidth Tx/Rx (%)	This field displays the percentage of bandwidth usage on this port as a percentage of the <b>Iink Speed</b> .
CRC	This shows the number of packets received with CRC (Cyclic Redundant Check) errors.
Extend Range	This shows whether PoE range is extended up to 250 meters for the port on this Switch.
PD Failed Count	Note: Make sure Auto PD Recovery is enabled on your Switch (see Section 48.2 on page 333).This shows the number of times the Switch attempts to restart the PD on the port.
	The PD Failed Count will reset after clicking the Flush button.
System Name	This shows the system name of the neighbor device.
Port	This shows the number of the neighbor device's port which is connected to the Switch.
Model	This shows the model name of the neighbor device. This field will show "" for devices that do not support the ZON utility.
IP	This shows the IPv4 or IPv6 address of the neighbor device. The IPv4 or IPv6 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.

Table 163 Summary > Neighbor Detail

LABEL	DESC RIPTIO N
Action	Click the <b>Default</b> button to reset the neighboring device to its factory default settings. A warning message " <b>Are you sure you want to reset the AP to factory default</b> ?" appears prompting you to confirm the action.
	• The Switch must support power sourcing (PSE) or the network device is a powered device (PD).
	<ul> <li>If multiple neighbor devices use the same port, the <b>De fa ult</b> button is not available.</li> <li>You can only reset Zyxel powered devices that support the ZON utility.</li> </ul>
Location	This shows the geographic location of the neighbor device. This field will show "" for devices that do not support the ZON utility.
Desc.	This shows the description of the neighbor device's port which is connected to the Switch.
Firmware	This shows the firmware version of the neighbor device. This field will show "" for devices that do not support the ZON utility.
MAC	This shows the MAC address of the neighbor device.
Device Type	This field displays the IP-based security products, for example IP camera or NVR (network video recorder), that is connected to this Switch.
Flush	Click the <b>Flush</b> button to remove information about neighbors learned on the selected ports.

 Table 163
 Summary > Neighbor Detail (continued)

# C HAPTER 46 Quick Setup

Use the Quick Setup screen to display the IP Address Information of the Switch and links to the IP Setup, Auto PD Recovery, PoE Setup, Port Setup, and ONVIF screens.

## 46.1 Quick Setup Screen

Click Quick Setup in the navigation panel to display this screen.

Figure 241 Quick Setup

IP Address Information		2504	Quick Links	
172.21.46.5 172.21.46.5 Samuel Island 858.259.355.8	Belout Butewaye 17235-85354		Rado Contanta Barconera Con Ecolorada Range A Part Indea	Constantia

IABEL	DESC RIPTIO N		
IP Address Informat	IP Address Information		
IPv4 Address	This displays the IP address of the Switch for it to be managed over the network.		
Subnet Mask	This displays the subnet mask that specifies the network number portion of an IP address.		
Default Gateway	This displays the IP address of the default outgoing gateway in dotted decimal notation.		
IP Setup	This link takes you to a screen where you can configure the IP address and subnet mask (necessary for Switch management) and set up to 64 IP routing domains.		
Quick Links			
Auto Camera Recovery	This link takes you to a screen where you can enable and configure Auto PD Recovery on the Switch.		
PoE Setup	This link takes you to a screen where you can set priorities, PoE power-up settings and schedule so that the Switch is able to reserve and allocate power to certain PDs.		
Extended Range & Port Setup	This link takes you to a screen where you can configure settings for individual Switch ports.		
ONVIF	This link takes you to a screen where you can configure a specific VLAN to run ONVIF.		

# C HAPTER 47 Syste m

## 47.1 What You Can Do

- Use the System Information screen (Section 47.2 on page 328) to check the firmware version number and monitor the Switch temperature.
- Use the General Setup screen (Section 47.3 on page 329) to configure general settings such as the system name and time.
- Use the Cloud Management screen (Section 47.4 on page 331) to display links to Nebula Control Center Discovery and Nebula Switch Registration screens.

## 47.2 System Information

In the navigation panel, click System > System Information to display the screen as shown. Use this screen to view general system information. You can check the firmware version number and monitor the Switch temperature.

Figure 242 System > System	Information
----------------------------	-------------

ure 242 System	eysterri merrianen				
System Info					
System Info					
lysten: Name Product Model 2pNOS F/W Version Dhemet Address CPU Utilization Current (%) Memory Utilization	061350 G5150-6HP WJ28(ABPL0)55   04/14/3525 bccb454757bf1 13.26				
Name	Total (byte)		Used (byte)		Utilization (%)
common	55351248		4174656		11
lardware Monitor					
				Temp	erofune Unit 🔕 G 🛛 🔿 F
Temperature (C)	Skatue	Current	MAX	MIN	Threshold
CPUMAC	Newwood	45.0	48.0	42.0	82.0

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
System Name	This field displays the descriptive name of the Switch for identification purposes.
Product Model	This field displays the product model of the Switch. Use this information when searching for firmware upgrade or looking for other support information in the website.
ZyNOS F/W Version	This field displays the version number of the Switch 's current firmware including the date created.
Ethernet Address	This field refers to the Ethernet MAC (Media Access Control) address of the Switch.
CPU Utilization Current (%)	CPU utilization quantifies how busy the system is. <b>Current</b> (%) displays the current percentage of CPU utilization.
Memory Utilization	Memory utilization shows how much DRAM memory is available and in use. It also displays the current percentage of memory utilization.
Name	This field displays the name of memory pool.
Total (byte)	This field displays the total number of bytes in this memory pool.
Used (byte)	This field displays the number of bytes being used in this memory pool.
Utilization (%)	This field displays the percentage (%) of memory being used in this memory pool.
Hardware Monite	or
Temperature Unit	The Switch has temperature sensors that are capable of detecting and reporting if the temperature rises above the threshold. You may choose the temperature unit (Centigrade or Fahrenheit) in this field.
Temperature (C)	CPU/MAC refers to the location of the temperature sensor on the Switch printed circuit board.
Status	This field displays $Nomal$ for temperatures below the threshold and $Enor$ for those above.
Current	This shows the current temperature at this sensor.
MAX	This field displays the maximum temperature measured at this sensor.
MIN	This field displays the minimum temperature measured at this sensor.
Threshold	This field displays the upper temperature limit at this sensor.

Table 165	System > System Info

# 47.3 General Setup

Use this screen to configure general settings such as the system name and time. Click System > GeneralSetup in the navigation panel to display the screen as shown.

General Setup	
General Setup	
Assiem Nome	stanistanis
Location	
Control Partonia Nome	
Use Time Server when Bootup	NP/RIC-1008
Time Server IP Address	Localimping
Gereni Time	07 : 14 : 00 UTC:x00:00
New fine (Mannes)	07 : 14 : 00
courrent conte	2016 01 01
New Date (www.mm.dd)	200 <b>8 00 00</b>
Time Ione	UTC Y
Doyight Solving Time	(ear)
Start Date	Fisi 💜 Sunday 💛 of January 🗠 of 0:00 🗠
EndDote	Fisi 🖂 Sunday 🖂 of Jencery 🗠 of 0:00 🗠
	$\Delta_{ m h}$ it will take 20 seconds it time server a unreachable.
	Apply concol

#### Figure 243 System > General Setup

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
System Name	Choose a descriptive name for identification purposes. This name consists of up to 64 printable characters; spaces are allowed.
Location	Enter the geographic location of your Switch. You can use up to 32 printable ASCII characters; spaces are allowed.
Contact Person's Name	Enter the name of the person in charge of this Switch. You can use up to 32 printable ASCII characters; spaces are allowed.
Use Time Server when Bootup	Enter the time service protocol that your time server uses. Not all time servers support all protocols, so you may have to use trial and error to find a protocol that works. The main differences between them are the time format.
	When you select the <b>Daytime</b> ( <b>RPC 867</b> ) format, the Switch displays the day, month, year and time with no time zone adjustment. When you use this format it is recommended that you use a Daytime timeserver within your geographical time zone.
	Time (RFC-868) format displays a 4-byte integer giving the total number of seconds since 1970/ 1/1 at 0:0:0.
	NTP (RFC-1305) is similar to Time (RFC-868).
	<b>None</b> is the default value. Enter the time manually. Each time you turn on the Switch, the time and date will be reset to 1970-1-1 0:0:0.
Time Server IP Address	Enter the IP address or domain name of your timeserver. The Switch searches for the timeserver for up to 60 seconds.
Current Time	This field displays the time you open this menu (or refresh the menu).
New Time (hh:min:ss)	Enter the new time in hour, minute and second format. The new time then appears in the <b>Current Time</b> field after you click <b>Apply</b> .
Current Date	This field displays the date you open this menu.
New Date (yyyy- mm-dd)	Enter the new date in year, month and day format. The new date then appears in the <b>Cument Date</b> field after you click <b>Apply</b> .

#### Table 166 System > General Setup

G\$1350 Series User's Guide

IABEL	DESC RIPTIO N
Time Zone	Select the time difference between UTC (Universal Time Coordinated, formerly known as GMT, Greenwich Mean Time) and your time zone from the drop-down list box.
Daylight Saving Time	Daylight saving is a period from late spring to early fall when many countries set their clocks ahead of normal local time by one hour to give more daytime light in the evening.
	Set the switch to $\mathbf{ON}$ if you use Daylight Saving Time.
Start Date	Configure the day and time when Daylight Saving Time starts if you selected <b>Daylight Saving</b> <b>Time</b> . The time is displayed in the 24 hour format. Here are a couple of examples:
	Daylight Saving Time starts in most parts of the United States on the second Sunday of March. Each time zone in the United States starts using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>Second</b> , <b>Sunday</b> , <b>March</b> and <b>2:00</b> .
	Daylight Saving Time starts in the European Union on the last Sunday of March. All of the time zones in the European Union start using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last</b> , <b>Sunday</b> , <b>March</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).
End Date	Configure the day and time when Daylight Saving Time ends if you selected <b>Daylight Saving</b> <b>Time</b> . The time field uses the 24 hour format. Here are a couple of examples:
	Daylight Saving Time ends in the United States on the first Sunday of November. Each time zone in the United States stops using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>First, Sunday</b> , <b>November</b> and <b>2:00</b> .
	Daylight Saving Time ends in the European Union on the last Sunday of October. All of the time zones in the European Union stop using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Iast, Sunday, October</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 166 System > General Setup (continued)

## 47.4 Cloud Management

The Switch supports NebulaFlex which can set the Switch to operate in either standalone or Nebula cloud management mode. When the Switch is in standalone mode, it can be configured and managed by the Web Configurator. When the Switch is in Nebula cloud management mode, it can be managed and provisioned by the Zyxel Nebula Control Center (NCC).

The Zyxel Nebula Control Center (NCC) is a cloud-based network management system that allows you to remotely manage and monitor Zyxel Nebula APs, Ethernet switches and security gateways.

Note: NebulaFlex for hybrid mode and NCC registration are NOT supported at the time of writing and reserved for future use.

The Switch is managed and provisioned automatically by the NCC (Nebula Control Center) when:

- The Switch is connected to the Internet.
- The Nebula Control Center Discovery feature is enabled.
- The Switch has been registered in the NCC.

The **Cloud Management** screen displays links to **Nebula Switch Registration** which has a QR code containing the Switch's serial number and MAC address for handy registration of the Switch at NCC.

Click System > Cloud Management in the navigation panel to display this screen.

Figure 244 System > Cloud Management

Cloud Managem	ant -
Cloud Manageme	m
Nebulo Sontrol Cerry	er )+26( Decavery
Cloud Castnersilias Chech	> ternstrature Chicolo > ternstrature Bobolo Controllos
	terbuic Control Center & just lew steps (word We <sup>4</sup> Network World <sup>®</sup> 1 (pp. from App store to Coople plus store from the CR cools to register the Search and you can start to edge the parter of Cloud Management.

Select **On** to turn on NCC discovery on the Switch. If the Switch has Internet access and has been registered in the NCC, it will go into cloud management mode.

In cloud management mode, then NCC will first check if the firmware on the Switch needs to be upgraded. If it does, the Switch will upgrade the firmware immediately. If the firmware does not need to be upgraded, but there is newer firmware available for the Switch, then it will be upgraded according to the firmware upgrade schedule for the Switch on the NCC. Below is the process for upgrading firmware:

- 1 Download firmware via the NCC.
- 2 Upgrade the firmware and reboot.

Note: While the Switch is rebooting, do NOT turn off the power.

Disable  $\mathbf{On}$  to turn off NCC discovery on the Switch. The Switch will NOT discover the NCC and remain in standalone mode.

This screen has a QR code containing the Switch's serial number and MAC address for handy NCC registration of the Switch using the Nebula Mobile app. First, download the app from the Google Play store for Android devices or the App Store for iOS devices and create an organization and site.

# C HAPTER 48 Port

## 48.1 What You Can Do

- Use the Auto PD Recovery screen (Section 48.2 on page 333) to turn on automatic PD recovery on the Switch and its Ethernet ports.
- Use the **PoE Status** screen (Section 48.3 on page 335) to view the current amount of power that PDs are receiving from the Switch.
- Use the **PoESetup** screen (Section 48.4 on page 338) to set the PoE power management mode, priority levels, power-up mode and the maximum amount of power for the connected PDs.
- Use the Port Setup screen (Section 48.5 on page 340) to configure Switch port settings.

## 48.2 Auto PD Recovery

This screen lets you turn on automatic PD recovery on the Switch and its Ethernet ports. You can configure whether the Switch uses LLDP or ping to check current status of a connected PD.

The ping is sent through the Switch's default management IP address to the designated port. To ping the PD, the port must share the same VLAN as the Switch's management VLAN.




Figure 245 Auto PD Recovery Application

To open this screen, click Port > Auto PD Recovery.

	rD Kecov I Recov	22 C							
-101	dar me	Wasak	1.944	Poling Hilored Verd	Talina Court	As fuir	Maxim, Policy Mixture (Rect. )	insection insection	Record Roma Innova (Jacque
165	111	O meri O fro	ar			school singt		1.1.	
$\widetilde{\mathbf{F}}_{i}^{(i)}$		101.0 B1		20.	-	Sebool-Alort	r ~   500		10
2	$\{i\}$	O aper	1	25		-stud Aur			(d
A	E.	0 (DP 200		20		[Sebash-Marr	t   <del>4</del> 99	1	14
39	:51	O LLDP Trig	1	20	5	[networkstore		t	12
50 C	333	0 mm	1202-84	<b>.</b>	1	• shoel sheet		1	[e68] ]

Figure 246 Port > Auto PD Recovery

Table 167 Port > Auto PD Recovery

IABEL	DESC RIPTIO N
Active	Select this option to enable Auto PD Recovery on the Switch.
Port	This field displays the index number of a port on the Switch.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Set the switch to <b>ON</b> to enable Auto PD Recovery on the ports.
Mode	Select <b>IIDP</b> to have the Switch passively monitor current status of the connected PD by reading LLDP packets from the PD on the port. The Switch also sends out LLDP packets to the PD to update the <b>Switch Neighbor</b> table on the PD (see Section 45.2.1 on page 324 for details).
	Select $\mathbf{Ping}$ to have the Switch ping the IP address of the connected PD to test whether the PD is reachable or not.
Neighbor	If <b>Mode</b> is set to <b>IIDP</b> , the system name of the connected PD displays automatically.
	If <b>Mode</b> is set to <b>Ping</b> and the PD supports LLDP, the connected PD's IPv4 or IPv6 address to which the Switch sends ping requests will display automatically. If not, enter the IP address manually.
Polling Interval (sec)	Specify the number of seconds the Switch waits for a response before sending another ping request.
	For example, the Switch will try to detect the PD status by performing ping requests every 20 seconds.

IABEL	DESC RIPTIO N
Polling Count	Specify how many times the Switch is to resend a ping request before considering the PD unreachable.
	For example, If there is no ping reply from the PD after the <b>Polling Interval</b> has elapsed, <b>Polling Count</b> starts from 1. After <b>Polling Count</b> reaches 3, the <b>PD He alth</b> status LED will turn to red in the <b>Status &gt; Neighbor</b> screen (see Section 45.2.1 on page 324 for details). The Switch will then perform your choice in the <b>Action</b> field.
Action	Set the action to take when the connected PD has stopped responding.
	Select <b>Reboot-Alam</b> to have the Switch turn OFF the power of the connected PD (the connecting port is detected as link-down) and turn it back ON again to restart the PD after sending an SNMP trap and generating a log message.
	When restarting, the PD entry disappears from the Switch's LLDP table and the <b>PD He a lth</b> status LED will turn to yellow in the <b>Status</b> > <b>Neighbor</b> screen (see Section 45.2.1 on page 324 for details).
	Select $A la m$ to have the Switch send an SNMP trap and generate a log message.
Resume Polling Interval (sec)	Specify the number of seconds the Switch waits before monitoring the PD status again after it restarts the PD on the port.
PD Reboot Count	Specify how many times the Switch attempts to restart the PD on the port.
	The PD Reboot Count will reset
	<ul> <li>as soon as a ping is successful,</li> <li>or when any modification to the Auto PD Recovery screen is applied,</li> <li>or after restarting the Switch.</li> </ul>
Resume Power Interval (sec)	Specify the number of seconds the Switch waits before supplying power to the connected PD again after it restarts the PD on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.


Table 167 Port > Auto PD Recovery (continued)

## 48.3 PoEStatus

A powered device (PD) is a device such as an access point or a switch, that supports PoE (Power over Ethernet) so that it can receive power from another device through an Ethernet port.

You can also set priorities so that the Switch is able to reserve and allocate power to certain PDs.

Note: The PoE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.



To view the current amount of power that PDs are receiving from the Switch, click Port > PoESetup > PoEStatus.

#### Figure 248 Port > PoE Setup > PoE Status

PoE Statue	NoE :	ietup				
PoE Status						
PoF Mode		Consumption				
tolo (Power (	W)	6000				
Foli Urage (7		0				
sonouming <del>v</del>	neer (m)	103				
Alcooled Po	WME (W)	NA.				
Servicining Pr	www.(W)	A0A0				
Poel	8 al e	Olem	Mixily	Rower Up	Concerning Power (W)	Mus Power (W)
Pol	State [enable]	class o	Pioly Low	Rower Op Jacobie	Concerning Power (M) 100	Mos Power (W) 191
				· · ·		
1	[enable]	•	1 cm	and the second	11.0	101
1 2	Enable Enable	0 0	i ow Low	900.357	110 110	101 040

 Table 168
 Port > PoE Setup > PoE Status

IABEL	DESC RIPTIO N
PoE Mode	This field displays the power management mode used by the Switch, whether it is in <b>C la ssific a tion</b> or <b>C onsum p tion</b> mode.
Total Power (W)	This field displays the total power the Switch can provide to the connected PoE-enabled devices on the PoE ports.

IABEL	DESC RIPTIO N
	This field displays the amount of power currently being supplied to connected PoE devices (PDs)
PoE Usage (%)	as a percentage of the total PoE power the Switch can supply.
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in <b>Port</b> > <b>PoE Se tup</b> > <b>PoE Se tup</b> .
Consuming Power (W)	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices.
Allocated Power (W)	This field displays the total amount of power the Switch (in classification mode) has reserved for PoE after negotiating with the connected PoE devices. It shows <b>NA</b> when the Switch is in consumption mode.
	Consuming Power(W) can be less than or equal but not more than the Allocated Power(W).
Remaining Power (W)	This field displays the amount of power the Switch can still provide for PoE.
	Note: The Switch must have at least 16 W of remaining power in order to supply power to a PoE device, even if the PoE device needs less than 16 W.
Port	This is the port index number.
State	This field shows which ports can receive power from the Switch. You can set this in Section 48.4 on page 338.
	<ul> <li>Disable – The PD connected to this port cannot get power supply.</li> <li>Enable – The PD connected to this port can receive power.</li> </ul>
Class	This shows the power classification of the PD. Each PD has a specified maximum power that fall under one of the classes.
	The Class is a number from 0 to 6, where each value represents the range of power that the Switch provides to the PD. The power ranges in PoE standards are as follows.
	• Class 0 - default: 0.44 W to 15.4 W.
	• Class 1 - default: 0.44 W to 4 W.
	• Class 2 – default: 0.44 W to 7 W.
	• Class 3 – default: 0.44 W to 15.4 W.
	<ul> <li>Class 4 – default: 0.44 W to 30 W.</li> <li>Class 5 – default: 0.44 W to 45 W.</li> </ul>
	• Class 6 – default: 0.44 W to 60 W.
	Note: You can extend or set a limit on the maximum power the connected PD can use on a port in <b>Port &gt; PoESetup &gt; PoESetup</b> .
Priority	When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority first.
	Critic al has the highest priority.
	<ul> <li>High has the Switch assign power to the port after all critical priority ports are served.</li> </ul>
	• Low has the Switch assign power to the port after all critical and high priority ports are served.
Power-Up	This field displays the PoE standard the Switch uses to provide power on this port.
Consuming Power (W)	This field displays the current amount of power consumed by the PD from the Switch on this port.
Max Power (W)	This field displays the maximum amount of power the PD could use from the Switch on this port.

<b>T</b> I I <b>I I I I I I I I I</b>			
Table 168 H	Port > PoE Setup > PoE Status (	continued)	

# 48.4 PoESetup

Use this screen to set the PoE power management mode, priority levels, power-up mode and the maximum amount of power for the connected PDs.

Click Port > PoESetup > PoESetup, the following screen opens.

of Shahua	fob3	etup				
E Setup						
: Mede niin Joos tubi		kancore 🤇	Consemption			
561	Acres	Pricedy	Permanag	NascPower (1119)	Wide Kenyd	LIPP Fore Wo
(Spill)	CACENO.	P) (4)	Permity	Water Forward (2019)	Color-Brin	LIDP Funder Vio Set 5
33		istent -	en sat i i i i i i i i i i i i i i i i i i i		-	1111
		10W -	802.301			12
8.2						
2		Den ×	802.261			
	8	Dow	802.561 ×		2	2
2		provide the second				1.11

The following table describes the labels in this screen.

Table 169 Port > PoE Setup > PoE Setup

IABEL	DESC RIPTIO N
PoE Mode	Select the power management mode you want the Switch to use.
	<ul> <li>Classification - Select this if you want the Switch to reserve the maximum power for each PD according to the PD's power class and priority level. If the total power supply runs out, PDs with lower priority do not get power to function. In this mode, the maximum power is reserved based on what you configure in Max Power or the standard power limit for each class.</li> <li>Consumption - Select this if you want the Switch to supply the actual power that the PD needs. The Switch also allocates power based on a port's Max Power and the PD's power</li> </ul>
	class and priority level. The Switch puts a limit on the maximum amount of power the PD can request and use. In this mode, the default maximum power that can be delivered to the PD is 33 W (IEEE 802.3at Class 4) or 22 W (IEEE 802.3af Classes 0 to 3).
Continuous PoE	Select <b>ON</b> to guarantee continuous power supply to the connected PDs while the Switch is restarting after a warm reboot. The Switch will NOT perform a power cycle on the connected PDs.
	If you do a cold reboot, the Switch also restarts the connected PDs.
Port	This is the port index number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Select this to provide power to a PD connected to the port.
	If left unchecked, the PD connected to the port cannot receive power from the Switch.

Table 169	Port > PoE Setup > PoE Setup	(continued)

LABEL	DESC RIPHO N
Priority	When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority.
	Select <b>C ritic a I</b> to give the highest PD priority on the port.
	Select <b>High</b> to set the Switch to assign the remaining power to the port after all critical priority ports are served.
	Select $\mathbf{Low}$ to set the Switch to assign the remaining power to the port after all critical and high priority ports are served.
Power-Up	Set how the Switch provides power to a connected PD at power-up.
	802.3af – the Switch follows the IEEE 802.3af Power over Ethernet standard to supply power to the connected PDs during power-up.
	$\mathbf{Legacy}$ – the Switch can provide power to the connected PDs that require high inrush currents at power-up. Inrush current is the maximum, instantaneous input current drawn by the PD when first turned on.
	<b>Pre-802.3a t</b> – the Switch initially offers power on the port according to the IEEE 802.3af standard, and then switches to support the IEEE 802.3at standard within 75 milliseconds after a PD is connected to the port. Select this option if the Switch is performing 2-event Layer-1 classification (PoE+ hardware classification) or the connected PD is NOT performing Layer 2 power classification using Link Layer Discovery Protocol (LLDP).
	<b>802.3at</b> – the Switch supports the IEEE 802.3at High Power over Ethernet standard and can supply power of up to 30 W per Ethernet port. IEEE 802.3at is also known as PoE+ or PoE Plus. An IEEE 802.3at compatible device is referred to as Type 2. Power Class 4 (High Power) can only be used by Type 2 devices. If the connected PD requires a Class 4 current when it is turned on, it will be powered up in this mode.
	For $e-802.3at$ – the Switch offers power of up to 33 W on the port without performing PoE hardware classification. Select this option if the connected PD does not comply with any PoE standard and requests power higher than a standard power limit.
	<b>Pre-802.3b</b> t – the Switch offers power on the port according to the IEEE 802.3bt standard. Select this option if the connected PD was developed before the IEEE 802.3bt standard is implemented but requires power between 33 W and 60 W.
	802.3bt – the Switch supports the IEEE 802.3bt standard and can supply power of up to 60 W per Ethernet port to the connected PDs at power-up.
Max Power (mW)	Specify the maximum amount of power the PD could use from the Switch on this port. If you leave this field blank, the Switch refers to the standard or default maximum power for each class.
	Note: The setting you enter here will NOT take effect when the power-up mode is set to <b>802.3bt</b> .
Wide Range	Select this to let the Switch have a wider detection range for the PD.
Detection	The Switch detects whether a connected device is a powered device or not before supplying power to the port. For the PD detection, the Switch applies a fixed voltage to the device and then receives returned current. If the returned current is within the IEEE 802.3AF/AT standard range, the device will be considered as a valid PD by the Switch.
	However, in real cases, environmental interferences might easily cause the returned current to be out of the standard range.

Telela 1/0	Dout > Do Coturo > Do Coturo	(a a lation , a al)	
10DIE 169	Port > PoE Setup > PoE Setup	(coniinuea)	

IABEL	DESC RIPIIO N
LLDP Power Via MDI	Select this to have the Switch negotiate PoE power with the PD connected to the port by transmitting LLDP Power Via MDI TLV frames. This helps the Switch allocate less power to the PD on this port. The connected PD must be able to request PoE power through LLDP.
	The Power Via MDI TLV allows PoE devices to advertise and discover the MDI power support capabilities of the sending port on the remote device.
	<ul> <li>Port Class</li> <li>MDI Supported</li> <li>MDI Enabled</li> <li>Pair Controllable</li> <li>PSE Power Pairs</li> <li>Power Class</li> </ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 48.5 Port Setup

Use this screen to configure Switch port settings. Click Port > Port Setup in the navigation panel to display the configuration screen.

A0404042	vp						
Wi -	AK: 174	Austin	tpeac? D	upler:	Extended Renge 1	Flow Coninci	SCOLU Chork
1.1		Ŭ,	Aith	<u></u>		12	n -
11		1	70.0	- V			0.00
a)S	(31)		Auro		<u></u>	11	$[0, [\omega]]$
	Con Core	1	2400			Π.	0.7
4	<b>CH</b> 7	1	An. 9.	1		141	o ~
5	CELC _		Aim	14	-		0 -
20			7010	10 C	<b>a</b>	销售店	0.

#### Figure 250 Port > Port Setup

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Port	This is the port index number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable a port. The factory default for all ports is enabled. A port must be enabled for data transmission to occur.
Name	Enter a descriptive name that identifies this port. You can enter up to 64 alpha-numerical characters.
	Note: Due to space limitation, the port name may be truncated in some Web Configurator screens.
Speed/Duplex	Select the speed and the duplex mode of the Ethernet connection on this port. Choices are <b>Auto</b> , <b>10-an</b> (10M/auto-negotiation), <b>10M</b> / <b>Half Duplex</b> , <b>10M</b> / <b>Full Duplex</b> , <b>10M</b> / <b>Full Duplex</b> , <b>100</b> / auto-negotiation), <b>100M</b> / <b>Half Duplex</b> , <b>100M</b> / <b>Full Duplex</b> and <b>1G</b> / <b>Full Duplex</b> (Gigabit connections only).
	Selecting <b>Auto</b> (auto-negotiation) allows one port to negotiate with a peer port automatically to obtain the connection speed and duplex mode that both ends support. When auto-negotiation is turned on, a port on the Switch negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer port does not support auto-negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, a port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer port are the same in order to connect.
Extended	Select this check box to extend the PoE range up to 250 meters.
Range	After you enable this feature, the port will transfer data at a rate up to10 Mbps in full duplex mode. If a PD is connected to the port, the Switch follows the IEEE 802.3at PoE+ standard to supply power to the connected PD during power-up.
	Note: Maximum PoE power that can be supplied to a PD at 250 m is 15 W.
	Note: If you enable extended range on a port after the connected PD starts up completely, you must disable PoE and enable it again or disconnect and reconnect the cable to the port for extended mode to take effect.
	Note: The port speed and duplex mode you previously configured will be applied automatically when the extend range feature is disabled.
Flow Control	A concentration of traffic on a port decreases port bandwidth and overflows buffer memory causing packet discards and frame losses. <b>Flow Control</b> is used to regulate transmission of signals to match the bandwidth of the receiving port.
	The Switch uses IEEE802.3x flow control in full duplex mode and backpressure flow control in half duplex mode.
	IEEE802.3x flow control is used in full duplex mode to send a pause signal to the sending port, causing it to temporarily stop sending signals when the receiving port memory buffers fill.
	Back Pressure flow control is typically used in half duplex mode to send a "collision" signal to the sending port (mimicking a state of packet collision) causing the sending port to temporarily stop sending signals and resend later. Select <b>Flow Control</b> to enable it.
802.1p Priority	This priority value is added to incoming frames without a (802.1p) priority queue tag. See <b>Priority</b> <b>Queue Assignment</b> in Table 168 on page 336 for more information.

Table 170 Port > Port Setup

IABEL	DESC RIPTIO N			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

Table 170 Port > Port Setup (continued)

# C HAPTER 49 Switching

## 49.1 Broadcast Storm Control

Broadcast storm control limits the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports. When the maximum number of allowable broadcast, multicast and/or DLF packets is reached per second, the subsequent packets are discarded. Enable this feature to reduce broadcast, multicast and/or DLF packets in your network. You can specify limits for each packet type on each port.

Click Switching > Broadcast Storm Control in the navigation panel to display the screen as shown next.

Broade	ast Stor	m Control 📐		
Broadco	st Storn	n Control		
Active		on 🌒		
Port	Brow	arianat (pirija)	viultionst (pkr/k)	Di E (aktor)
1		0		
2	I.	0	L L D	1 I o
3		0		
		0	□   P	
6		0		
κ.		0	П. <u>в</u>	
1				upply Concel

Figure 251 Switching > Broadcast Storm Control

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
Active	Set this switch to <b>ON</b> to enable traffic storm control on the Switch. Otherwise, select <b>OFF</b> to disable this feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

GS1350 Series User's Guide

IABEL	DESC RIPIIO N
Broadcast (pkt/s)	Select this option and specify how many broadcast packets the port receives per second.
Multicast (pkt/s)	Select this option and specify how many multicast packets the port receives per second.
DLF (pkt/s)	Select this option and specify how many destination lookup failure (DLF) packets the port receives per second.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

 Table 171
 Switching > Broadcast Storm Control (continued)

# 49.2 Link Aggregation

This section shows you how to logically aggregate physical links to form one logical, higher-bandwidth link.

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

The beginning port of each trunk group must be physically connected to form a trunk group.

### 49.2.1 What You Can Do

- Use the **Link Aggregation Status** screen (Section 49.3 on page 344) to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.
- Use the **Link Aggregation Setting** screen (Section 49.4 on page 345) to configure to enable static link aggregation.
- Use the **Link Aggregation Control Protocol** screen (Section 49.5 on page 347) to enable Link Aggregation Control Protocol (LACP).

# 49.3 Link Aggregation Status

Use the **Link Aggregation Status** screen to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.

Click Switching > Link Aggregation > Link Aggregation Status in the navigation panel.

Figure 252 Switching > Link Aggregation > Link Aggregation Status

Trade Gergerig	ntino Subs. 📐	Trak Appropriate Selling	tak Septemb	ne Grebel Policial	
nk Aggrege	hen States				
Group D	unabled i orb	synamoniona norte	Aggregatorius	urteda	statu
		-	•	ak-dé-mak	-
12				ax-dá-max	-
<b>6</b> -	-	-		ax-dd-max	-

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Group ID	This field displays the group ID to identify a trunk group, that is, one logical link containing multiple ports.
Enabled Ports	These are the ports you have configured in the <b>Link Aggregation</b> screen to be in the trunk group.
	The port numbers displays only when this trunk group is activated and there is a port belonging to this group.
Synchronized Ports	These are the ports that are currently transmitting data as one logical link in this trunk group.
Aggregator ID	Link Aggregator ID consists of the following: system priority, MAC address, key, port priority and port number.
	The ID displays only when there is a port belonging to this trunk group and LACP is also enabled for this group.
Criteria	This shows the outgoing traffic distribution algorithm used in this trunk group. Packets from the same source and/or to the same destination are sent over the same link within the trunk.
	$\mathbf{src}$ - $\mathbf{mac}$ means the Switch distributes traffic based on the packet's source MAC address.
	dst-mac means the Switch distributes traffic based on the packet's destination MAC address.
	src - dst - mac means the Switch distributes traffic based on a combination of the packet's source and destination MAC addresses.
	${f src}$ - ${f ip}$ means the Switch distributes traffic based on the packet's source IP address.
	${f dst}$ ip means the Switch distributes traffic based on the packet's destination IP address.
	$\mathbf{src}$ - $\mathbf{dst}$ - $\mathbf{ip}$ means the Switch distributes traffic based on a combination of the packet's source and destination IP addresses.
Status	This field displays how these ports were added to the trunk group. It displays:
	<ul> <li>Static - if the ports are configured as static members of a trunk group.</li> <li>IACP-if the ports are configured to join a trunk group via LACP.</li> </ul>

Table 172 Switching > Link Aggregation > Link Aggregation Status

# 49.4 Link Aggregation Setting

Use the **Link Aggregation Setting** screen to enable static link. Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

Click Switching > Link Aggregation > Link Aggregation Setting to display the screen shown next.

lek Aggingation Slatus		Unk Aggregation Setting	Link Aggregation Cantel Poles
t Aggregatio	an Setting		
1 anna 1 anna 1	Althen	stim	40
TT.	a.C	mastalen	ner
10	( <b>313</b> )	stadien	665
100	(2000)	provide the	10(1) P
3) Terl		Group:	
1		Nor <u>s</u>	
2		hore v	
		b000 -	
×		SIT 1	
× .		Nume >	

Figure 253 Switching > Link Aggregation > Link Aggregation Setting

LABEL	DESC RIPTIO N
Link Aggregation Setting	This is the only screen you need to configure to enable static link aggregation.
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.
Active	Set this switch to on to activate a trunk group.
Criteria	Select the outgoing traffic distribution type. Packets from the same source and/or to the same destination are sent over the same link within the trunk. By default, the Switch uses the sme dst-mac distribution type. If the Switch is behind a router, the packet's destination or source MAC address will be changed. In this case, set the Switch to distribute traffic based on its IP address to make sure port trunking can work properly.
	Select $\mathbf{src}$ - $\mathbf{mac}$ to distribute traffic based on the packet's source MAC address.
	Select $dst - mac$ to distribute traffic based on the packet's destination MAC address.
	Select <b>src-dst-mac</b> to distribute traffic based on a combination of the packet's source and destination MAC addresses.
	Select $\mathbf{src}$ - $\mathbf{ip}$ to distribute traffic based on the packet's source IP address.
	Select $\mathbf{dst}$ - $\mathbf{ip}$ to distribute traffic based on the packet's destination IP address.
	Select <b>src</b> - <b>dst</b> - <b>ip</b> to distribute traffic based on a combination of the packet's source and destination IP addresses.
Port	This field displays the port number.
Group	Select the trunk group to which a port belongs.
	Note: When you enable the port security feature on the Switch and configure port security settings for a port, you cannot include the port in an active trunk group.

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 173
 Switching > Link Aggregation > Link Aggregation Setting (continued)

# 49.5 Link Aggregation Control Protocol

When you enable LACP link aggregation on a port, the port can automatically negotiate with the ports at the remote end of a link to establish trunk groups. LACP also allows port redundancy, that is, if an operational port fails, then one of the "standby" ports become operational without user intervention.

Click Switching > Link Aggregation > Link Aggregation Control Protocol to display the screen shown next. See Dynamic Link Aggregation on page 156 for more information on dynamic link aggregation.

Figure 254 Switching > Link Aggregation > Link Aggregation Control Protocol

lisk Aggregation Status	Link Aggregation Setting	Link Aggregation Control Protocol
Unk Aggregation Control Pro	Nocol	
Active College System Prosity Accus		
Group D	Loop Aaron	
1	-	
×	123	
<b>101</b>	L4C* howco	
1	Sp. > somewilk	
1	20 · oversets	
8	<u>-20 -</u> 360.000.0	
a. a	<u>20 × secondo</u> xo: = secondo.	
÷	10 - Secondy	
а н <sup>и</sup>	appaly	Carnel

The following table describes the labels in this screen.


Table 174	Switching > Link Aggr	egation > Link Aggreg	ation Control Protocol
-----------	-----------------------	-----------------------	------------------------


LABEL	DESC RIPIIO N				
Link Aggregation Control Protocol	Note: Do NOT configure this screen unless you want to enable dynamic link aggregation.				
Active	Set this switch to <b>ON</b> to enable Link Aggregation Control Protocol (LACP).				
System Priority	LACP system priority is a number between 1 and 65,535. The switch with the lowest system priority (and lowest port number if system priority is the same) becomes the LACP "server". The LACP "server" controls the operation of LACP setup. Enter a number to set the priority of an active port using Link Aggregation Control Protocol (LACP). The smaller the number, the higher the priority level.				
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.				
LACP Active	Select this option to enable LACP for a trunk.				
Port	This field displays the port number.				
*	Settings in this row apply to all ports.				
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.				
	Note: Changes in this row are copied to all the ports as soon as you make them.				
LACP Timeout	Timeout is the time interval between the individual port exchanges of LACP packets in order to check that the peer port in the trunk group is still up. If a port does not respond after three tries, then it is deemed to be "down" and is removed from the trunk. Set a short timeout (one second) for busy trunked links to ensure that disabled ports are removed from the trunk group as soon as possible.				
	Select either 1 second or 30 seconds.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to begin configuring this screen afresh.				

# 49.6 Loop Guard

This section shows you how to configure the Switch to guard against loops on the edge of your network.

Loop guard allows you to configure the Switch to shut down a port if it detects that packets sent out on that port loop back to the Switch. While you can use Spanning Tree Protocol (STP) to prevent loops in the core of your network. STP cannot prevent loops that occur on the edge of your network.






#### 49.6.1 What You Need to Know

Loop guard is designed to handle loop problems on the edge of your network. This can occur when a port is connected to a Switch that is in a loop state. Loop state occurs as a result of human error. It happens when two ports on a switch are connected with the same cable. When a switch in loop state sends out broadcast messages the messages loop back to the switch and are re-broadcast again and again causing a broadcast storm.

If a switch (not in loop state) connects to a switch in loop state, then it will be affected by the switch in loop state in the following way:

- The switch (not in loop state) will receive broadcast messages sent out from the switch in loop state.
- The switch (not in loop state) will receive its own broadcast messages that it sends out as they loop back. It will then re-broadcast those messages again.

The following figure shows port  $\mathbf{N}$  on switch  $\mathbf{A}$  connected to switch  $\mathbf{B}$ . Switch  $\mathbf{B}$  has two ports,  $\mathbf{x}$  and  $\mathbf{y}$ , mistakenly connected to each other. It forms a loop. When broadcast or multicast packets leave port  $\mathbf{N}$  and reach switch  $\mathbf{B}$ , they are sent back to port  $\mathbf{N}$  on  $\mathbf{A}$  as they are rebroadcast from  $\mathbf{B}$ .




The loop guard feature checks to see if a loop guard enabled port is connected to a Switch in loop state. This is accomplished by periodically sending a probe packet and seeing if the packet returns on the same port. If this is the case, the Switch will shut down the port connected to the switch in loop state.

Loop guard can be enabled on both Ethernet ports. The following figure shows a loop guard enabled port **N** on switch **A** sending a probe packet **P** to switch **B**. Since switch **B** is in loop state, the probe packet **P** returns to port **N** on **A**. The Switch then shuts down port **N** to ensure that the rest of the network is not affected by the switch in loop state.




Figure 257 Loop Guard - Probe Packet



The Switch also shuts down port  $\mathbf{N}$  if the probe packet returns to switch  $\mathbf{A}$  on any other port. In other words loop guard also protects against standard network loops.

The following figure illustrates three switches forming a loop. A sample path of the loop guard probe packet is also shown. In this example, the probe packet is sent from port  $\mathbf{N}$  and returns on another port. As long as loop guard is enabled on port  $\mathbf{N}$ . The Switch will shut down port  $\mathbf{N}$  if it detects that the probe packet has returned to the Switch.





Note: After resolving the loop problem on your network you can re-activate the disabled port via the Web Configurator or via commands (See the CLI Reference Guide).

Click Switching > Loop Guard in the navigation panel to display the screen as shown.

Note: The loop guard feature cannot be enabled on the ports that have Spanning Tree Protocol (RSTP) enabled.

ling Shared	
Loop Goard	
NA .	A dise
	Г
1	
2 C	П
	Г
÷.	Г
	Apple Council

Figure 259 Switching > Loop Guard

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Active	Set the switch to <b>ON</b> to enable loop guard on the Switch.
	The Switch generates syslog, internal log messages as well as SNMP traps when it shuts down a port via the loop guard feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the loop guard feature on this port. The Switch sends probe packets from this port to check if the switch it is connected to is in loop state. If the switch that this port is connected is in loop state the Switch will shut down this port.
	Clear this check box to disable the loop guard feature.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Tabla	175	Switching > Loop Guard
lable	1/5	Switching > Loop Guard

## 49.7 VIAN

This section shows you how to configure 802.1Q tagged and port-based VLANs.

### 49.7.1 What You Can Do

- Use the VIAN Status screen (Section 49.8 on page 354) to view and search all VLAN groups.
- Use the VIAN Detail screen (Section 49.8.1 on page 355) to view detailed port settings and status of the VLAN group.
- Use the **Static VIAN** screen (Section 49.9 on page 356) to configure and view 802.1Q VLAN parameters for the Switch.
- Use the **VIAN Port Setting** screen (Section 49.10 on page 358) to configure the static VLAN (IEEE 802.1Q) settings on a port.

### 49.7.2 What You Need to Know

Read this section to know more about VLAN and how to configure the screens.




Figure 260 Shared Server Using VLAN Example

#### IEEE 802.1Q Tagged VIANs

A tagged VLAN uses an explicit tag (VLAN ID) in the MAC header to identify the VLAN membership of a frame across bridges – they are not confined to the switch on which they were created. The VLANs can be created statically by hand dynamically through GVRP. The VLAN ID associates a frame with a specific VLAN and provides the information that switches need to process the frame across the network. A tagged frame is 4 bytes longer than an untagged frame and contains 2 bytes of TPID (Tag Protocol Identifier, residing within the type/length field of the Ethernet frame) and 2 bytes of TCI (Tag Control Information, starts after the source address field of the Ethernet frame).

The CFI (Canonical Format Indicator) is a single-bit flag, always set to zero for Ethernet switches. If a frame received at an Ethernet port has a CFI set to 1, then that frame should not be forwarded as it is to an untagged port. The remaining twelve bits define the VLAN ID, giving a possible maximum number of 4,096 VLANs. Note that user priority and VLAN ID are independent of each other. A frame with VID (VLAN Identifier) of null (0) is called a priority frame, meaning that only the priority level is significant and the default VID of the ingress port is given as the VID of the frame. Of the 4096 possible VIDs, a VID of 0 is used to identify priority frames and value 4095 (FFF) is reserved, so the maximum possible VLAN configurations are 4,094.

TPID	User Priority	CFI	VLAN ID
2 Bytes	3 Bits	1 Bit	12 bits

#### Forwarding Tagged and Untagged Frames

Each port on the Switch is capable of passing tagged or untagged frames. To forward a frame from an 802.1Q VLAN-aware switch to an 802.1Q VLAN-unaware switch, the Switch first decides where to forward the frame and then strips off the VLAN tag. To forward a frame from an 802.1Q VLAN-unaware switch to an 802.1Q VLAN-aware switch, the Switch first decides where to forward the frame, and then inserts a VLAN tag reflecting the ingress port's default VID. The default PVID is VLAN 1 for all ports, but this can be changed.

A broadcast frame (or a multicast frame for a multicast group that is known by the system) is duplicated only on ports that are members of the VID (except the ingress port itself), thus confining the broadcast to a specific domain.

#### 49.7.2.1 Automatic VIAN Registration

GARP and GVRP are the protocols used to automatically register VLAN membership across switches.

#### GARP

GARP (Generic Attribute Registration Protocol) allows network switches to register and de-register attribute values with other GARP participants within a bridged LAN. GARP is a protocol that provides a generic mechanism for protocols that serve a more specific application, for example, GVRP.

#### GARP Timers

Switches join VLANs by making a declaration. A declaration is made by issuing a Join message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All message terminates all registrations. GARP timers set declaration timeout values.

#### GVRP

GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Enable this function to permit VLAN groups beyond the local Switch.

Please refer to the following table for common IEEE 802.1Q VLAN terminology.

VIAN PARAMEIER	TERM	DESC RIPTIO N	
VLAN Type	Permanent VLAN	This is a static VLAN created manually.	
	Dynamic VLAN	This is a VLAN configured by a GVRP registration or de-registration process.	
VLAN Administrative	Registration Fixed	Fixed registration ports are permanent VLAN members.	
Control	Registration Forbidden	Ports with registration forbidden are forbidden to join the specified VLAN.	
	Normal Registration	Ports dynamically join a VLAN using GVRP.	
VLAN Tag Control	Tagged	Ports belonging to the specified VLAN tag all outgoing frames transmitted.	
	Untagged	Ports belonging to the specified VLAN do not tag all outgoing frames transmitted.	
VLAN Port	Port VID	This is the VLAN ID assigned to untagged frames that this port received.	
	Acceptable Frame Type	You may choose to accept both tagged and untagged incoming frames, just tagged incoming frames or just untagged incoming frames on a port.	
	Ingress filtering	If set, the Switch discards incoming frames for VLANs that do not have this port as a member.	


Table 176 IEEE 802.1Q VLAN Terminology

#### 49.7.2.2 Port VIAN Trunking

Enable **VIAN Trunking** on a port to allow frames belonging to unknown VLAN groups to pass through that port. This is useful if you want to set up VLAN groups on end devices without having to configure the same VLAN groups on intermediary devices.

Refer to the following figure. Suppose you want to create VLAN groups 1 and 2 (V1 and V2) on devices A and B. Without **VIAN Tiunking**, you must configure VLAN groups 1 and 2 on all intermediary switches C, D and E; otherwise they will drop frames with unknown VLAN group tags. However, with **VIAN Tiunking** enabled on ports in each intermediary switch you only need to create VLAN groups in the end devices

(A and B). C, D and E automatically allow frames with VLAN group tags 1 and 2 (VLAN groups that are unknown to those switches) to pass through their VLAN trunking ports.



## 49.8 VIAN Status

Use this screen to view and search all static VLAN groups. Click **Switc hing** > **VLAN** from the navigation panel to display the **VLAN Status** screen as shown next.

Figure 262 S	witching	g > VLAN: VLA	AN Status			
VLAN Status	51	ofic VLAN	VLAN Port Setting			
VLAN Status						
VLAN Secreb by 1	vo		Secroh			
The Number of VL	AN: 1					
					K < Pa	ge 1 of 1 > X
Index	VID	Name	Toggod Port	Untragged Port	Bopsed Time	Status
1	1			1-6	9:44:27	Shufe:
					R CPa	gelt [aft>×

IABEL	DESC RIPIIO N
VLAN Search by VID	Enter an existing VLAN ID numbers (separated by a comma) and click $\mathbf{Seach}$ to display only the specified VLANs in the list below.
	Leave this field blank and click $\mathbf{Search}$ to display all VLANs configured on the Switch.
The Number of VLAN	This is the number of VLANs configured on the Switch.
The Number of	This is the number of VLANs that match the searching criteria and display in the list below.
Search Results	This field displays only when you use the $\operatorname{Seaw} h$ button to look for certain VLANs.
Index	This is the VLAN index number. Click on an index number to view more VLAN details.
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.
Name	This fields shows the descriptive name of the VLAN.
Tagged Port	This field shows the tagged ports that are participating in the VLAN.

Table 177 Switching > VLAN: VLAN Status

LABEL	DESC RIPTIO N
Untagged Port	This field shows the untagged ports that are participating in the VLAN.
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	This field shows how this VLAN was added to the Switch.
	Static: added as a permanent entry.
Page	Click the forward or back icon to show the previous or next screen if all status information cannot be seen in one screen. Or enter the page number.

Table 177 Switching > VLAN: VLAN Status (continued)

### 49.8.1 VLAN Detail

Use this screen to view detailed port settings and status of the static VLAN group. Click on an index number in the **VIAN Status** screen to display VLAN details.

Figure 263 Switching > VLAN > VLAN Status > VLAN Detail

VLAN Status	Static VLAN	VLAN Port Setting	
VLAN Stotus 🗧 VI	AN Dotal		
VD	1		
Lopsed time	10:25:20		
Status	Stohe		
Port Number			
2		A	6
1		3	5
U		U	U
		0	U.
			UtUnlogged Diogge

 Table 178
 Switching > VLAN > VLAN Status > VLAN Detail

LABEL	DESC RIPIIO N		
VLAN Status	Click this to go to the VIAN Status screen.		
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.		
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.		
Status	This field shows how this VLAN was added to the Switch.		
	Static: added as a permanent entry.		
Port Number	This column displays the ports that are participating in a VLAN. A tagged port is marked as <b>T</b> , an untagged port is marked as <b>U</b> and ports not participating in a VLAN are marked as "-".		

## 49.9 Static VIAN


Use a static VLAN to decide whether an incoming frame on a port should be

- sent to a VLAN group as normal depending on its VLAN tag.
- sent to a group whether it has a VLAN tag or not.
- blocked from a VLAN group regardless of its VLAN tag.

You can also tag all outgoing frames (that were previously untagged) from a port with the specified VID.

Use this screen to view static VLAN status for the Switch. Click Switching > VIAN > Static VIAN to display the screen as shown next.

Figure 264 Switching > VLAN > Static VLAN



The following table describes the related labels in this screen.

LABEL	DESC RIPIIO N		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
VID	This field displays the ID number of the VLAN group. Click the number to edit the VLAN settings.		
Active	This field indicates whether the VLAN settings are enabled (ON) or disabled (OFF).		
Name	This field displays the descriptive name for this VLAN group.		
Add	Click this button to create a new static VLAN.		
Edit	Click this button to configure the static VLAN.		
Delete	Click this button to remove the static VLAN.		

#### Table 179 Switching > VLAN > Static VLAN

Click Add or Edit button to open the following screen. Use this screen to configure a static VLAN for the Switch.

Figure 265 Switching > VLAN > Static VLAN > Add/Edit Static VLAN

		O Add	S Prices	D Dwight
679E 1				
1				
	i stativi		magina	8
	Hormal -		🖬 Ta Tagang	202
Citizinal	Orient	Chorolodon	in soring	
Citizanet	O Fined	Citoronden	In regional	
C Somel	O ficed	Cortection	🗆 Di Teasing 🗌	
🔅 Neimid	ORead	C Forbicite 6	🗌 Di Totasha 🗌	
🗌 Normal	Oriend	Chorologies	The capping	
Chicadori	Oriect	Choroleden	in logging -	
Choront	Orield	I.S.	20,200	
	C flornet O flornet O somet O somet	Normal - Normal Oriecti Hornet Oriecti Somet Oriect Somet Oriect Somet Oriect Somet Oriect	Normal Orbed Porticales Normal Orbed Porticales Normal Orbed Porticales Normal Orbed Porticales Normal Orbed Porticales Normal Orbed Porticales Normal Orbed Porticales	Image: Second

IABEL	DESC RIPTIO N			
ACTIVE	Select this switch to activate the VLAN settings.			
Name	Enter a descriptive name for the VLAN group for identification purposes. This name consists of up to 64 printable characters. Spaces are allowed.			
VLAN Group ID	Enter the VLAN ID for this static entry; the valid range is between 1 and 4094.			
Port	The port number identifies the port you are configuring.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Note: Changes in this row are copied to all the ports as soon as you make them.			
Control	Select <b>Nomal</b> for the port to dynamically join this VLAN group. This is the default selection.			
	Select $\mathbf{Fixed}$ for the port to be a permanent member of this VLAN group.			
	Select Forbidden if you want to prohibit the port from joining this VLAN group.			
Tagging	Select <b>TX Tagging</b> if you want outgoing traffic to contain this VLAN tag.			
	Otherwise, to ensure that VLAN-unaware devices (such as computers and hubs) can receive frames properly, clear the <b>TX Tagging</b> check box to set the Switch to remove VLAN tags before sending.			
Add/Edit	Click <b>Add</b> or <b>Edit</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Clear	Click Clear to reset the fields to the factory defaults.			
Cancel	Click <b>Cancel</b> to change the fields back to their last saved values.			

Table 180 Switching > VLAN > Static VLAN > Add/Edit Static VLAN

# 49.10 VIAN Port Setting

Use this screen to configure the static VLAN (IEEE 802.1Q) settings on a port. Click the **VIAN Port Setting** tab in the **VIAN** screen.

Figure 266	Switching > VLAN > VLAN Port Setting
------------	--------------------------------------

VLAN S	latva Static V	AAN YAAN FOR	Setting 📐		
VIAN Po	n Setting				
Levit.	ngara uneck	190	Autorgehalden bezinnt. IVOR	vuer multing	<b>iolation</b>
I.		H	A ~	I	I.
I.			<b>A</b>	1	1
2			<b>A</b> ~	I	I.
2			<b>A</b>	1	1
			<b>A</b> ~	I	I.
÷			<b>A</b>	1	1
٠			<b>A</b> ~	I	I.
			Apply Canad		

IABEL	DESC RIPIIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Ingress Check	If this check box is selected, the Switch discards incoming frames on a port for VLANs that do not include this port in its member set.
	Clear this check box to disable ingress filtering.
PVID	A PVID (Port VLAN ID) is a tag that adds to incoming untagged frames received on a port so that the frames are forwarded to the VLAN group that the tag defines.
	Enter a number between 1 and 4094 as the port VLAN ID.
Acceptable	Specify the type of frames allowed on a port. Choices are All, Tag Only and Untag Only.
Frame Type	Select All from the drop-down list box to accept all untagged or tagged frames on this port. This is the default setting.
	Select $\operatorname{Tag} \mathbf{Only}$ to accept only tagged frames on this port. All untagged frames will be dropped.
	Select <b>Untag Only</b> to accept only untagged frames on this port. All tagged frames will be dropped.
VLAN Trunking	Enable <b>VIAN Tiunking</b> on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the Switch.

Table 181 Switching > VLAN > VLAN Port Setting

LABEL	DESC RIPIIO N
Isolation	Select this to allows this port to communicate only with the CPU management port and the ports on which the isolation feature is NOT enabled.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 181
 Switching > VLAN > VLAN Port Setting (continued)

# C HAPTER 50 Networking

This section shows you how to configure the default gateway device, the default domain name server and add IP domains.

### 50.1 IP Interfaces

The Switch needs an IP address for it to be managed over the network. When the Switch (in standalone mode) fails to obtain an IP address from a DHCP server, the static IP address 192.168.1.1 will be automatically added and used as the Switch's management IP address.

On the Switch, an IP address is not bound to any physical ports. Since each IP address on the Switch must be in a separate subnet, the configured IP address is also known as IP interface (or routing domain). In addition, this allows routing between subnets based on the IP address without additional routers.

You can configure multiple routing domains on the same VLAN as long as the IP address ranges for the domains do not overlap. To change the IP address of the Switch in a routing domain, simply add a new routing domain entry with a different IP address in the same subnet.

You can configure up to 64 IP domains which are used to access and manage the Switch from the ports belonging to the pre-defined VLANs.

Note: You must configure a VLAN first. Each VLAN can have multiple management IP addresses, and you can log into the Switch via different management IP addresses simultaneously.

### 50.1.1 What You Can Do

- Use the IP Setup screen (Section 50.2 on page 360) to configure the default gateway device, the default domain name server and add IP domains.
- Use the **ONVIF** screen (Section 50.3 on page 362) to enable the ONVIF protocol on the Switch.

## 50.2 IP Setup

Use the **IP** Se tup screen to configure the default gateway device, the default domain name server and add IP domains. See Section 8.6 on page 94 for more information on IP setup.

Figure 267 Networking > IP Setup

elaul Monogeme	See Sec.						
elanı, wayademe	enr in Addres						
olohon olohi Datalari Artices							
P Avideou	100.0 200	6					
* Subner More	100.000.000	ý					
Seloul Galeway	172.31 / 3.25	(					
a i							
			and the second second				
			Search C	or the second			
			Analy C	enti i			
anoin Nome Serv			94919 C	ound -			
main Nome Serv			ente 🛛	annet - I	Q Add	er top	e Cerete
		urau - Norma	init C	enutri (	Q Ads	and the second	e Ceista
		widen 140 mg	enia C	eesst 11	Q Add	er tip	e carda
		ikinan Nama	anis C		Q Ada	e ta	e Cerete
		stanu ti Müssel	ante C	entit in 🕅	Q Ads	<b>E</b> 612	e Celete
	tán D	asaan Norta	anti C		<b>0</b> Ada	<b>7</b> 629	e carata
	tán D	wine of Net State	ania S		Q Ada	<u>e</u> tre	e cerete
amain Nome Serv	tán D	ukinu ti tAčittaj	anta		Q Ada	e co	Consta Consta

Table 182 Networking > IP Setup

IABEL	DESC RIPTIO N
Default Managen	nent IP Address
Use these fields to	create or edit IP routing domains on the Switch.
DHCP Client	Select this option if you have a DHCP server that can assign the Switch an IP address, subnet mask, a default gateway IP address and a domain name server IP address automatically.
Static IP Address	Select this option if you do not have a DHCP server or if you wish to assign static IP address information to the Switch. You need to fill in the following fields when you select this option.
IP Address	Enter the IP address of your Switch in dotted decimal notation, for example, 172.21.40.x. This is the IP address of the Switch in an IP routing domain.
IP Subnet Mask	Enter the IP subnet mask of an IP routing domain in dotted decimal notation, for example, 255.255.252.0.
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 172.21.43.254.
VID	Enter the VLAN identification number to which an IP routing domain belongs.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to your previous configuration.
Domain Name Se	rver
Use these fields to	add, edit, or delete the IP address of the DNS server.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.

IABEL	DESC RIPTIO N
Index	This field displays the index number of an entry.
Domain Name Server	This field displays the IP address of the DNS server.
Add	Click this button to create a new IP address for the DNS server.
Edit	Click this button to configure the IP address of the DNS server.
Delete	Click this button to remove the IP address of the DNS server.
Management IP A	ddress
Use these fields to	set the settings for the management port.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Index	This field displays the index number of an entry.
IP Address	This field displays IP address of the Switch in the IP domain.
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.
VID	This field displays the VLAN identification number of the IP domain on the Switch.
Default Gateway	This field displays the IP address of the default outgoing gateway in dotted decimal notation.
Add	Click this button to create new settings for the management port.
Edit	Click this button to configure the settings for the management port.
Delete	Click this button to remove the settings for the management port.

Table 182 Networking > IP Setup (continued)

### 50.3 ONVIF

When ONVIF is enabled and configured, the Switch can obtain the ONVIF security device's information such as system name and IP address. This lets you to know which IP-based security products, for example IP camera or NVR (network video recorder), is connected to the Switch.

Use the **ONVIF** screen to enable the ONVIF protocol on the Switch.

4	, uic 200		ig on in						
	ONVE								
	ONME								
	Archien.	08							
					Apply	Cancel			
	VLAN								
							C And	🖉 Nit	🛔 Delete
		Index	VID	Fort					
	2	I	1	1					

Figure 268 Networking > ONVIF

LABEL	DESC RIPTIO N
ONVIF	
Active	Select Active to allow this Switch to send ONVIF packets to discover or scan for ONVIF- compatible IP-based security devices connected to its ports. Make sure to enter the port numbers in <b>Port</b> to allow discovery of ONVIF-compatible devices.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.
VLAN	· · ·
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Index	This is the index number of the ONVIF entry in the table.
VID	This field displays the VLAN to which the ports belong.
Port	This field displays the ports to which the Switch applies the settings.
Add	Click this button to create new ONVIF settings for the VLAN port.
Edit	Click this button to configure the ONVIF settings for the VLAN port.
Delete	Click this button to remove the ONVIF settings for the VLAN port.

Table 183 Networking > ONVIF

## C HAPTER 51 Security

## 51.1 Access Control

A console port and FTP are allowed one session each, Telnet and SSH share nine sessions, up to five Web sessions (five different user names and passwords) and/or limitless SNMP access control sessions are allowed.

Table 184 Access Control Overview

Console Port	SSH	Telnet	FTP	Web	SNMP
One session	Share up to 9 s	sessions	One session	Up to 5 accounts	No limit

A console port access control session and Telnet access control session cannot coexist when multi-login is disabled. See the CLI Reference Guide for more information on disabling multi-login.

This section describes how to control access to the Switch.

#### 51.1.1 What You Can Do

- Use the Logins screen (Section 51.2 on page 364) to assign which users can access the Switch via Web Configurator at any one time.
- Use the **Remote Management** screen (Section 51.3 on page 366) to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
- Use the SNMP screen (Section 51.4 on page 368) to configure your SNMP settings.
- Use the Service Access Control screen (Section 51.8 on page 374) to decide what services you may use to access the Switch.

### 51.2 Set Up Login Accounts

Up to 5 people (one administrator and four non-administrators) may access the Switch via Web Configurator at any one time.

• An administrator is someone who can both view and configure Switch changes. The username for the Administrator is always **admin**. The default administrator password is **1234**.

Note: It is highly recommended that you change the default administrator password (1234).

• A non-administrator (username is something other than **admin**) is someone who can view and/or configure Switch settings. The configuration right varies depending on the user's privilege level.

Click Security > Access Control > Logins to view the screen as shown.

Wielesse.					
inidealar.					
Commond.	<b>F</b>	'ei			
furning a		- AP			
nto confirm		(南)			
Logins	d), Pierza jed gonavosti		neever wit shorpe it. The	nymm will odryn and Franciscer (	venete
Logins	A Perse er provint		none-recou chongeit. The Balypo le contem	nymen will ordryn, ald Frankows : Dreisge	ocycle
Logins		nan wur ihm primerium			tocaolie
Logins 1		nan waar nee potteerin w Farming R	Balypo le contron		torgoffe
logins 		oco va z new posterovske	Balipa le contem		tooy die

Figure 269 Security > Access Control > Logins

LABEL	DESC RIPTIO N
Administrator	
Administrator	
This is the default ad user name.	ministrator account with the "admin" user name. You cannot change the default administrator
Old Password	Type the existing system password (1234 is the default password when shipped).
New Password	Enter your new system password.
Retype to confirm	Retype your new system password for confirmation.
Edit Logins	
give users higher priv	passwords for up to four users. These users can have read-only or read/write access. You can vileges via the Web Configurator or the CLI. For more information on assigning privileges via the <sup>5</sup> Switch CLI Reference Guide.
Login	This field displays the index number of an entry.
User Name	Set a user name (up to 32 ASCII characters long).
Password	Enter your new system password.
Retype to confirm	Retype your new system password for confirmation.

LABEL	DESC RIPTIO N
Privilege	Type the privilege level for this user. At the time of writing, users may have a privilege level of 0, 3, 13, or 14 representing different configuration rights as shown below.
	• 0 – Display basic system information.
	3 – Display configuration or status.
	<ul> <li>13 – Configure features except for login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, administrator and enable passwords, and configuration information display.</li> </ul>
	<ul> <li>14 – Configure login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, and administrator and enable passwords, and display configuration information.</li> </ul>
	Users can run command lines if the session's privilege level is greater than or equal to the command's privilege level. The session privilege initially comes from the privilege of the login account. For example, if the user has a privilege of 5, he or she can run commands that requires privilege level of 5 or less but not more.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 185	Security > Access	Control > Logins	(continued)
	Jucomy - Aucuss	COINTOI > LOGINS	

## 51.3 Remote Management

Use this screen to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

Click Security > Access Control > Remote Management to view the screen as shown next.

386	Activity	Story Address	Diel Aufdeste	Tetral	- ATTACK	0.000	IC.MIT	28.M*	<b>\$</b> 30	, me
1	Gall	inn cin 🔄	Asia							12
$\hat{F}^{(i)}$	000	0.0 1.0	0.500		1		11		11	
5	(187	0.0 0.0	0.0,0,0	1.12		122	12	120	CE:	12
÷.		harsa	103300	L.F	Π	-			10	
8	200	[04:00 ]	0.000	L.	14		11		1	-
4		Innen	กระกา	E.						
2	()20)	100:00	0.300		Ĩ.		- hi			
6	1	0.0.0.0	0.0.0.0			-				
<u>(7</u> )	() BP	liar en 👘	10300	ÉГ	<u>II</u>		17		10	
10	100	0.000	0.0.00	- L	11		1.1		11_	
15		[nnon]	naria	1						
120	333	0.0 : 0	0.200	j, l	11		- M	111	110	
( <b>t</b> ))	( <b>19</b> )	0.0 0.0	0.000	12			12	120	E	12
183		haran	10300	L T	Π					
12	20	0.000	00.00	L.	14		Ú.		1	-
14	(Tate)	Innen	143.04	1.		-	11	-	-	-


Figure 270 Sec	urity > Access	Control >	Remote Ma	nagement
----------------	----------------	-----------	-----------	----------

Table 186	Security >	Access Control >	Remote Management
-----------	------------	------------------	-------------------

LABEL	DESC RIPIIO N
Entry	This is the client set index number. A "client set" is a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
Active	Set this switch to <b>ON</b> to activate this secured client set. Clear the check box if you wish to temporarily disable the set without deleting it.
Start Address	Configure the IP address range of trusted computers from which you can manage this Switch.
End Address	The Switch checks if the client IP address of a computer requesting a service or protocol matches the range set here. The Switch immediately disconnects the session if it does not match.
Telnet/FTP/ HTTP/ICMP/ SNMP/SSH/ HTTPS	Select services that may be used for managing the Switch from the specified trusted computers.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 51.4 Configure SNMP

Use this screen to configure your SNMP settings. Simple Network Management Protocol (SNMP) is an application layer protocol used to manage and monitor TCP/IP-based devices. SNMP is used to exchange management information between the network management system (NMS) and a network element (NE). A manager station can manage and monitor the Switch through the network via SNMP version 1 (SNMPv1), SNMP version 2c or SNMP version 3. The next figure illustrates an SNMP management operation. SNMP is only available if TCP/IP is configured.



An SNMP managed network consists of two main components: agents and a manager.

An agent is a management software module that resides in a managed Switch (the Switch). An agent translates the local management information from the managed Switch into a form compatible with SNMP. The manager is the console through which network administrators perform network management functions. It executes applications that control and monitor managed devices.

The managed devices contain object variables or managed objects that define each piece of information to be collected about a Switch. Examples of variables include number of packets received, node port status and so on. A Management Information Base (MIB) is a collection of managed objects. SNMP allows a manager and agents to communicate for the purpose of accessing these objects.

SNMP itself is a simple request or response protocol based on the manager or agent model. The manager issues a request and the agent returns responses using the following protocol operations:

LABEL	DESC RIPIIO N
Get	Allows the manager to retrieve an object variable from the agent.
GetNext	Allows the manager to retrieve the next object variable from a table or list within an agent. In SNMPv1, when a manager wants to retrieve all elements of a table from an agent, it initiates a Get operation, followed by a series of GetNext operations.
Set	Allows the manager to set values for object variables within an agent.
Trap	Used by the agent to inform the manager of some events.

Table 187 SNMP Commands

#### SNMP v3 and Security

SNMP v3 enhances security for SNMP management. SNMP managers can be required to authenticate with agents before conducting SNMP management sessions.

Security can be further enhanced by encrypting the SNMP messages sent from the managers.

Encryption protects the contents of the SNMP messages. When the contents of the SNMP messages are encrypted, only the intended recipients can read them.

Click Security > Access Control > SNMP > SNMP to view the screen as shown.

Figure 272 Security > Access Control > SNMP > SNMP

SNMP	Trap Group	Trap Group Port	User Information	
General Settin	19			
Version Oct Community Sel Community Trap Community	public politic	đ		
Trap Destination	on			
Index	Venion	IP.	Port	Demone
1	w?c: **	onon	162	
2	V2c [2]	0.0.0.0	162	
3	v2c >	onan	162	
4	V2c ~	0.0.0.0	162	
			Apply Cancel	

Table 188	Security > Access Control > SNMP > SNMP
-----------	---

IABEL	DESC RIPTIO N	
General Setting	Use this section to specify the SNMP version and community (password) values.	
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .	
	SNMP version 2c is backwards compatible with SNMP version 1.	
Get Community	Enter the GetCommunity string, which is the password for the incoming Get- and GetNext-requests from the management station.	
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.	
Set Community	Enter the <b>Set Community</b> , which is the password for incoming Set- requests from the management station.	
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.	
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.	
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.	
Trap Destination	Use this section to configure where to send SNMP traps from the Switch.	
Index	This field displays the index number of an entry.	
Version	Specify the version of the SNMP trap messages.	
IP	Enter the IP addresses of up to 4 managers to send your SNMP traps to.	
Port	Enter the port number upon which the manager listens for SNMP traps.	

IABEL	DESC RIPTIO N
Username	Enter the username to be sent to the SNMP manager along with the SNMP v3 trap.
	This username must match an existing account on the Switch (configured in the $Management > Access Control > SNMP > User screen$ ).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 188 Security > Access Control > SNMP > SNMP (continued)

## 51.5 Configure SNMP Trap Group

The Switch sends traps to an SNMP manager when an event occurs. From the  $\mathbf{SNMP}$  screen, click  $\mathbf{Thap}$ Group to view the screen as shown. Use the Thap Group screen to specify the types of SNMP traps that should be sent to each SNMP manager.

Figure 273 Se	ecurity > Acces	s Control > SNMP > T	rap Group	
28.97	Trap Group	Rep Group Peri	Ver internation	
Trop Group				
te qui tradici de anti				
E System			_ hites	
I politikan    n -  _ antikaan    putienega	Li Asimina ∏ kasiyan Li yan			Hinkdown Hidp warddin ∏rdan Gaelad
E 444			T n	
L - A wede at	en Lastar	e se e constante a		in a second second
E Johan				
1.0	in the second se			
			Apply Danied	

Table 189	Security > Access	Control > SNMP	> Trap Group
-----------	-------------------	----------------	--------------

LABEL	DESC RIPHO N
Trap Destination IP	Select one of your configured trap destination IP addresses. These are the IP addresses of the SNMP managers. You must first configure a trap destination IP address in the <b>SNMP Setting</b> screen.
	Use the rest of the screen to select which traps the Switch sends to that SNMP manager.
Туре	Select the categories of SNMP traps that the Switch is to send to the SNMP manager.

IABEL	DESC RIPTIO N
Options	Select the individual SNMP traps that the Switch is to send to the SNMP station. The traps are grouped by category. Selecting a category automatically selects all of the category's traps. Clear the check boxes for individual traps that you do not want the Switch to send to the SNMP station. Clearing a category's check box automatically clears all of the
Apply	category's trap check boxes (the Switch only sends traps from selected categories). Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 189 Security > Access Control > SNMP > Trap Group (continued)

## 51.6 Enable or Disable Sending of SNMP Traps on a Port

Click Security > Access Control > SNMP > Thep Group Port to view the screen as shown. Use this screen to set whether a trap received on the ports would be sent to the SNMP manager.

SNMP	Trap Group	Trap Group Port	User Information	
Irap Group	Port			
Oplive: [keep	ngurand M			
Port			Active	
-			() or	
1			( • ( )	
2			(m 🕘	
8			<b>(1(</b> )	
4			(at ()	
<i>N</i>			<b>(III)</b>	
4			(ok ())	
			Apply Concel	

Figure 274 Security > Access Control > SNMP > Trap Group Port

Table 190 Security > Access Control > SNMP > Trap Group Port

LABEL	DESC RIPTIO N
Option	Select the trap type you want to configure here.
Port	This field displays a port number.

IABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Set this switch to $\mathbf{ON}$ to enable the trap type of SNMP traps on this port.
	Set this switch to $\mathbf{OFF}$ to disable the sending of SNMP traps on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

#### Table 190 Security > Access Control > SNMP > Trap Group Port (continued)

## 51.7 Configure SNMP User

From the **SNMP** screen, click **User Inform a tion** to view the screen as shown. Use the **User Inform a tion** screen to view SNMP users for authentication with managers using SNMP v3. An SNMP user is an SNMP manager.

SHEE	Top Group	Top Group for	User Financellan				
ia hian	alert.						
					10 Ade	(C. 1.4)	. Delata
	5414	A. 81 (197	Served and	and a second	1 ann		Čere –

Figure 275 Security > Access Control > SNMP > User Information

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Index	This is a read-only number identifying a login account on the Switch. Click on an index number to view more details and edit an existing account.
Username	This field displays the username of a login account on the Switch.
Security Level	This field displays whether you want to implement authentication and/or encryption for SNMP communication with this user.
Authentication	This field displays the authentication algorithm used for SNMP communication with this user.
Privacy	This field displays the encryption method used for SNMP communication with this user.
Group	This field displays the SNMP group to which this user belongs.
Add	Click this button to create new SNMP users for authentication with managers.
Edit	Click this button to configure SNMP users for authentication with managers.
Delete	Click this button to remove the selected entry from the summary table.

Table 191 Security > Access Control > SNMP > User Information

Click **Add** or **Edit** button to open the following screen. Use this screen to create or edit SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups.

			O Add T 111	- II Deiste
which the				
stitutly out	ocarda ~			
Active log	W-17517	Persword		1
Tracey	EES -	Pataword		1
Gerag	is chroim 🗠			- A
			Add Clean	Careel

Figure 276 Security > Access Control > SNMP > User Information > Add or Edit User Information

Table 192 Security > Access Control > SNMP > User Information > Add or Edit User Information

LABEL	DESC RIPTIO N	
User Information	Note: Use the username and password of the login accounts you specify in this screen to create accounts on the SNMP v3 manager.	
Username	Specify the username of a login account on the Switch.	
Security Level	Select whether you want to implement authentication and/or encryption for SNMP communication from this user. Choose:	
	<ul> <li>noauth – to use the username as the password string to send to the SNMP manager. This is equivalent to the Get, Set and Trap Community in SNMP v2c. This is the lowest security level.</li> <li>auth – to implement an authentication algorithm for SNMP messages sent by this user.</li> </ul>	
	• <b>priv</b> – to implement authentication and encryption for SNMP messages sent by this user. This is the highest security level.	
	Note: The settings on the SNMP manager must be set at the same security level or higher than the security level settings on the Switch.	
Authentication	Select an authentication algorithm. <b>MD5</b> (Message Digest 5) and <b>SHA</b> (Secure Hash Algorithm) are hash algorithms used to authenticate SNMP data. SHA authentication is generally considered stronger than MD5, but is slower.	
Password	Enter the password of up to 32 ASCII characters for SNMP user authentication.	
Privacy	Specify the encryption method for SNMP communication from this user. You can choose one of the following:	
	<ul> <li>DES – Data Encryption Standard is a widely used (but breakable) method of data encryption. It applies a 56-bit key to each 64-bit block of data.</li> </ul>	
	AES – Advanced Encryption Standard is another method for data encryption that also     uses a secret key. AES applies a 128-bit key to 128-bit blocks of data.	
Password	Enter the password of up to 32 ASCII characters for encrypting SNMP packets.	
Group	SNMP v3 adopts the concept of View-based Access Control Model (VACM) group. SNMP managers in one group are assigned common access rights to MIBs. Specify in which SNMP group this user is.	
	a dmin – Members of this group can perform all types of system configuration, including the management of administrator accounts.	
	<b>re a dwrite</b> – Members of this group have read and write rights, meaning that the user can create and edit the MIBs on the Switch, except the user account and AAA configuration.	
	$\mathbf{readonly}$ – Members of this group have read rights only, meaning the user can collect information from the Switch.	

IABEL	DESC RIPIIO N
Add	Click this to create a new entry or to update an existing one.
	This saves your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to reset the fields to the factory defaults.
Cancel	Click Cancel to reset the fields to your previous configuration.

 Table 192
 Security > Access Control > SNMP > User Information > Add or Edit User Information

## 51.8 Service Access Control Screen

Service Access Control allows you to decide what services you may use to access the Switch. You may also change the default service port and configure "trusted computers" for each service in the **Remote Management** screen (discussed earlier). Click **Security** > **Access Control** > **Service Access Control** to view the screen as shown.

Figure 277 Security > Access Control > Service Access Control

levicer	Active	Lervice Purt		imesói	Lingth	t Presbut
Convie			5	Minister		
Tunut		22	3	Nicoco	150	Secon.
5518	(III)	7.				
115		21	3	lanear.		
HUT		80	1	Minater		
(mes		445				
CNF		3300				
SNOP						

Table 173 Secondy - Access Connor - Service Access Connor				
LABEL	DESC RIPIIO N			
Services	Services you may use to access the Switch are listed here.			
Active	Select this option for the corresponding services that you want to allow to access the Switch.			
Service Port	For Telnet, SSH, FTP, HTTP or HTTPS services, you may change the default service port by typing the new port number in the <b>Service Port</b> field. If you change the default port number then you will have to let people (who wish to use the service) know the new port number for that service.			
Timeout	Enter how many minutes (from 1 to 255) a management session can be left idle before the session times out. After it times out you have to log in with your password again. Very long idle timeouts may have security risks.			

Table 193 Security > Access Control > Service Access Control

IABEL	DESC RIPTIO N
Login Timeout	The Telnet or SSH server do not allow multiple user logins at the same time. Enter how many seconds (from 30 to 300 seconds) a login session times out. After it times out you have to start the login session again. Very long login session timeouts may have security risks. For example, if User A attempts to connect to the Switch (via SSH), but during the login stage, do not enter the user name and/or password, User B cannot connect to the Switch (via SSH) before the Login Timeout for User A expires (default 150 seconds).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 193 Security > Access Control > Service Access Control (continued)

## C HAPTER 52 Maintenance

This section explains how to configure the screens that let you maintain the firmware and configuration files.

## 52.1 What You Can Do


- Use the **Backup Configuration** screen (Section 52.2 on page 376) to save your configuration for later use.
- Use the Firm ware Upgrade screen (Section 52.3 on page 377) to upload the latest firmware.
- Use the **Reboot System** screen (Section 52.4 on page 378) to restart the Switch without physically turning the power off and load a specific configuration file.
- Use the **Restore Configuration** screen (Section 52.5 on page 379) to upload a stored device configuration file.
- Use the **Save Configuration** screen (Section 52.6 on page 379) to save the current configuration settings to a specific configuration file on the Switch.
- Use the Tech-Support screen (Section 52.7 on page 380) to create reports for customer support if there are problems with the Switch.

## 52.2 Backup Configuration

Backing up your Switch configurations allows you to create various "snap shots" of your device from which you may restore at a later date.

Click **Maintenance** > **Maintenance** > **Backup Configuration** to display the screen as shown next. Use this screen to back up your current Switch configuration and log files to a server or as local files to your computer.

Figure 278 Maintenance > Maintenance > Backup Configuration



Follow the steps below to back up the current Switch configuration to your computer in this screen.

- 1 Choose the type of configuration files for backup (running, current, and custom default).
- 2 Click Backup.
- 3 If a dialog box pops up asking whether you want to open or save the file, click **Save File** to download it to the default downloads folder on your computer. Click **OK** to save the configuration file to your computer.

## 52.3 Firmware Upgrade

Use the following screen to upgrade your Switch to the latest firmware.

Make sure you have downloaded (and unzipped) the correct model firmware and version to your computer before uploading to the device.

## Be sure to upload the correct model firm ware as uploading the wrong model firm ware may damage your device.

Click Maintenance > Maintenance > Firm ware Upgrade to view the screen as shown next.

Figure 279 Maintenance > Maintenance > Firmware Upgrade

Firmes	ie Upgrode
Elmovoue	Upgrade
Phase.	Vertex Fail 1
Vector	V1.70(AB110)B1   00/04/2020
To Logical Escitato	e the Internal relach firmware, proved the localian of the binary ( 2 %) file and a loc Upgrade button Binary ( 24048-13 Alice) Upgrade

Click **Choose File** or **Browse** to locate the firmware file you wish to upload to the Switch. Firmware upgrades are only applied after a reboot. Click **Upgrade** to load the new firmware.

After the firmware upgrade process is complete, see the **System Info** screen to verify your current firmware version number.

LABEL	DESC RIPIIO N		
Name	This is the name of the Switch that you are configuring.		
Version	This is the version number (and model code) and MM/DD/YYYY creation date of the firmware currently in use on the Switch. The firmware information is also displayed at System Information in Basic Settings.		
File Path	Enter the path and file name of the firmware file you wish to upload to the Switch in the <b>File Upload</b> text box or click <b>Choose File</b> or <b>Browse</b> to locate it.		
Upgrade	Click <b>Upgrade</b> to load the new firmware. Firmware upgrades are only applied after a reboot. To reboot, go to <b>Maintenance</b> > <b>Maintenance</b> > <b>Reboot System</b> and click <b>Current Configuration</b> , <b>Factory Default</b> , or <b>Custom Default</b> ( <b>Current Configuration</b> , <b>Factory Default</b> , and <b>Custom Default</b> are the configuration files you want the Switch to use when it restarts).		

Table 194 Maintenance > Maintenance > Firmware Upgrade

### 52.4 Reboot System

**Reboot System** allows you to restart the Switch without physically turning the power off. It also allows you to load the **Current Configuration**, a **Custom Default** or the **Factory Default** configuration when you reboot. Follow the steps below to reboot the Switch.

Click Maintenance > Maintenance > Reboot System to view the screen as shown next.


Figure 280 Maintenance > Maintenance > Reboot System

<u>.</u>
Cancel Cooliganillos
Rectory Defeat
vurion seksit

1 In the **Reboot System** screen, click a configuration button next to **Reboot System with** to reboot and load that configuration file. The following screen displays.

If you select **Current Configuration**, make sure to save the Switch settings as the current configuration in the **Maintenance** > **Maintenance** > **Save Configuration** screen.

Figure 281 Reboot System: Use the Current Configuration Confirmation




If you select Factory Default, the following warning will appear.

Figure 282 Reboot System: Use the Factory Default Confirmation



If you select Custom Default, the following warning will appear.

Figure 283 Reboot System: Use the Custom Default Confirmation



2 Click **OK** again and then wait for the Switch to restart. This takes up to 2 minutes. This does not affect the Switch's configuration.

Click **Current Configuration** and follow steps 1 to 2 to reboot and load the current configuration on the Switch.

Click Factory Default and follow steps 1 to 2 to reboot and load Zyxel factory default configuration settings on the Switch.

Click Custom Default and follow steps 1 to 2 to reboot and load a customized default file on the Switch.

### 52.5 Restore Configuration

You can restore a previously saved device configuration from your computer.

Click **Maintenance** > **Maintenance** > **Restore Configuration** to display the screen as shown next. Use this screen to restore a previously saved configuration from your computer.

Figure 284 Maintenance > Maintenance > Restore Configuration

Bestare Configuration
lectore Configuration
A content to the environment of the terms of the terms of the terms of the environment of the terms of the terms
eter Malla artes eter, and the refer tied.
Bahas

Follow the steps below to restore a previously saved configuration from your computer in this screen.

- 1 Click Choose File or Browse to locate the configuration file you wish to restore to the Switch.
- 2 Click **Restore**. The restore progress is shown.

Figure 285 Restoring Configuration (Progress Bar)

Fedore Configuration	
Redore Configuration	
	Configuration restoring

## 52.6 Save Configuration

Click Maintenance > Maintenance > Save Configuration to view the screen as shown next.

Figure 286 Maintenance > Maintenance > Save Configuration

Solve Configuration		
Sove Configuration		
vore vonliguration as	General Conteption	2050-012000
	Cales Salad	

Click **Current Configuration** to save the current configuration settings permanently to the Switch. This configuration is set up according to your network environment.

Click **Custom Default** to save the current configuration settings permanently to a customized default file on the Switch.

Note: If a customized default file was not saved, clicking **Custom Default** in the **Maintenance** > **Reboot System** screen loads the factory default configuration on the Switch.


Alternatively, click **Save** on the top right-hand corner in any screen to save the configuration changes to the current configuration.

### 52.7 Tech-Support

The Tech-Support feature is a log enhancement tool that logs useful information such as CPU utilization history, memory and Mbuf (Memory Buffer) log and crash reports for issue analysis by customer support should you have difficulty with your Switch. The Tech Support menu eases your effort in obtaining reports and it is also available in CLI command by typing "Show tech-support" command.

Click Maintenance > Maintenance > Tech-Support to see the following screen.

Figure 287 Maintenance > Maintenance > Tech-Support



You may need WordPad or similar software to see the log report correctly. The table below describes the fields in the above screen.

LABEL	DESC RIPIIO N
Tech-Support	Click <b>Download</b> to see all the log report and system status. This log report is stored in flash memory. If the <b>All</b> log report is too large, you can download the log reports separately below.
ROM	Click <b>Download</b> to see the Read Only Memory (ROM) log report. This report is stored in flash memory.

# PART III Throuble shooting and Appendices

## C HAPTER 53 Trouble shooting

This chapter offers some suggestions to solve problems you might encounter. The potential problems are divided into the following categories.

- Power, Hardware Connections, and LEDs
- Switch Access and Login
- Switch Configuration

### 53.1 Power, Hardware Connections, and LEDs

#### The Switch does not turn on. None of the LEDs turn on.

- 1 Make sure the Switch is turned on.
- 2 Make sure you are using the power adapter or cord included with the Switch.
- 3 Make sure the power adapter or cord is connected to the Switch and plugged in to an appropriate power source. Make sure the power source is turned on.
- **4** Turn the Switch off and on.
- 5 Disconnect and re-connect the power adapter or cord to the Switch.
- 6 If the problem continues, contact the vendor.

One of the LEDs does not behave as expected.

- 1 Make sure you understand the normal behavior of the LED. See Section 3.3 on page 39.
- 2 Check the hardware connections. See Section 3.1 on page 32.
- 3 Inspect your cables for damage. Contact the vendor to replace any damaged cables.
- 4 Turn the Switch off and on.
- 5 Disconnect and re-connect the power adapter or cord to the Switch.
- 6 If the problem continues, contact the vendor.

#### 382

## 53.2 Switch Access and Login

#### I forgot the IP address for the Switch.

- 1 The default in-band IP address in standalone mode is http://DHCP-assigned IP (when connecting to a DHCP server) or 192.168.1.1.
- 2 Use the ZON utility to find the IP address.
- 3 If this does not work, you have to reset the device to its factory defaults. See Section 4.8 on page 67.

I forgot the user name and/or password.

- 1 The default user name is **admin** and the default password is **1234**.
- 2 If this does not work, you have to reset the device to its factory defaults. See Section 4.8 on page 67.

I cannot see or access the Login screen in the Web Configurator.

- 1 Make sure you are using the correct IP address.
  - The default in-band IP address in standalone mode is <a href="http://DHCP-assigned IP">http://DHCP-assigned IP</a> (when connecting to a DHCP server) or 192.168.1.1.
     If you changed the IP address, use the new IP address.
  - If you changed the IP address and have forgotten it, see the troubleshooting suggestions for I forgot the IP address for the Switch.
- 2 Check the hardware connections, and make sure the LEDs are behaving as expected. See Section 3.3 on page 39.
- 3 Make sure your Internet browser does not block pop-up windows and has JavaScripts and Java enabled.
- 4 Make sure your computer is in the same subnet as the Switch. (If you know that there are routers between your computer and the Switch, skip this step.)
- 5 Reset the device to its factory defaults, and try to access the Switch with the default IP address. See Section 4.8 on page 67.
- 6 If the problem continues, contact the vendor, or try the advanced suggestion.

#### Advanced Suggestion

• Try to access the Switch using another service, such as Telnet. If you can access the Switch, check the remote management settings to find out why the Switch does not respond to HTTP.

#### I can see the **Login** screen, but I cannot log in to the Switch.

- 1 Make sure you have entered the user name and password correctly. The default user name is **admin**, and the default password is **1234**. These fields are case-sensitive, so make sure [Caps Lock] is not on.
- 2 You may have exceeded the maximum number of concurrent Telnet sessions. Close other Telnet sessions or try connecting again later.

Check that you have enabled logins for HTTP or Telnet. If you have configured a secured client IP address, your computer's IP address must match it. Refer to the chapter on access control for details.

- **3** Disconnect and re-connect the cord to the Switch.
- 4 If this does not work, you have to reset the device to its factory defaults. See Section 4.8 on page 67.

Pop-up Windows, JavaScripts and Java Permissions

In order to use the Web Configurator you need to allow:

- Web browser pop-up windows from your device.
- JavaScripts (enabled by default).
- Java permissions (enabled by default).

There is unauthorized access to my Switch via telnet, HTTP and SSH.

To avoid unauthorized access, configure the secured client setting in the **Management > Access Control > Remote Management** screen for telnet, HTTP and SSH (see Section 34.6 on page 277). Computers not belonging to the secured client set cannot get permission to access the Switch.

## 53.3 Switch Configuration

I lost my configuration settings after I restart the Switch.

Make sure you save your configuration into the Switch's nonvolatile memory each time you make changes. Click **Save** at the top right corner of the Web Configurator to save the



configuration permanently. See also Section 33.2.2 on page 259 for more information about how to save your configuration.

I accidentally unplugged the Switch. I am not sure which configuration file will be loaded.

If you plug the power cable back to the Switch, it will reboot and load the configuration file that was used the last time. For example, if **Config 1** was used on the Switch before you accidentally unplugged the Switch, **Config 1** will be loaded when rebooting.

## A PPENDIX A Customer Support

In the event of problems that cannot be solved by using this manual, you should contact your vendor. If you cannot contact your vendor, then contact a Zyxel office for the region in which you bought the device.

See *https://www.zyxelcom/homepage.shtml* and also *https://www.zyxelcom/about\_zyxel/zyxel\_worldwide.shtml* for the latest information.

Please have the following information ready when you contact an office.

#### Required Information

- Product model and serial number.
- Warranty Information.
- Date that you received your device.
- Brief description of the problem and the steps you took to solve it.

#### Corporate Headquarters (Worldwide)

#### Ta iwa n

- Zyxel Communications Corporation
- http://www.zyxel.com

#### Asia

#### China

- Zyxel Communications (Shanghai) Corp.
   Zyxel Communications (Beijing) Corp.
  - Zyxel Communications (Tianjin) Corp.
- https://www.zyxel.com/cn/zh/

#### India

- Zyxel Technology India Pvt Ltd
- https://www.zyxel.com/in/en/

#### Ka za khsta n

- Zyxel Kazakhstan
- https://www.zyxel.kz

#### Ko re a

- Zyxel Korea Corp.
- http://www.zyxel.kr

#### Ma la ysia

- Zyxel Malaysia Sdn Bhd.
- http://www.zyxel.com.my

#### Pa kista n

- Zyxel Pakistan (Pvt.) Ltd.
- http://www.zyxel.com.pk

#### **Philippines**

- Zyxel Philippines
- http://www.zyxel.com.ph

#### Singapore

- Zyxel Singapore Pte Ltd.
- http://www.zyxel.com.sg

#### Ta iwa n

- Zyxel Communications Corporation
- https://www.zyxel.com/tw/zh/

#### Tha ila nd

- Zyxel Thailand Co., Ltd.
- https://www.zyxel.com/th/th/

#### Vie tna m

- Zyxel Communications Corporation-Vietnam Office
- https://www.zyxel.com/vn/vi

#### Europe

#### Be la rus

- Zyxel BY
- https://www.zyxel.by

#### Be lg ium

- Zyxel Communications B.V.
- https://www.zyxel.com/be/nl/

https://www.zyxel.com/be/fr/

#### Bulg a ria

- Zyxel България
- https://www.zyxel.com/bg/bg/

#### Czech Republic

- Zyxel Communications Czech s.r.o
- https://www.zyxel.com/cz/cs/

#### De nm a rk

- Zyxel Communications A/S
- https://www.zyxel.com/dk/da/

#### Esto nia

- Zyxel Estonia
- https://www.zyxel.com/ee/et/

#### Finla nd

- Zyxel Communications
- https://www.zyxel.com/fi/fi/

#### Fra nc e

- Zyxel France
- https://www.zyxel.fr

#### Gemany

- Zyxel Deutschland GmbH
- https://www.zyxel.com/de/de/

#### Hung a ry

- Zyxel Hungary & SEE
- https://www.zyxel.com/hu/hu/

#### Ita ly

- Zyxel Communications Italy
- https://www.zyxel.com/it/it/

#### La tvia

- Zyxel Latvia
- https://www.zyxel.com/lv/lv/

#### Lithua nia

- Zyxel Lithuania
- https://www.zyxel.com/lt/lt/

#### Ne the rlands

- Zyxel Benelux
- https://www.zyxel.com/nl/nl/

#### Norway

- Zyxel Communications
- https://www.zyxel.com/no/no/

#### Poland

- Zyxel Communications Poland
- https://www.zyxel.com/pl/pl/

#### Rom a nia

- Zyxel Romania
- https://www.zyxel.com/ro/ro

#### Russia

- Zyxel Russia
- https://www.zyxel.com/ru/ru/

#### Slo va kia

- Zyxel Communications Czech s.r.o. organizacna zlozka
- https://www.zyxel.com/sk/sk/

#### Spain

- Zyxel Communications ES Ltd.
- https://www.zyxel.com/es/es/

#### Sweden

- Zyxel Communications
- https://www.zyxel.com/se/sv/

#### Switze rla nd

- Studerus AG
- https://www.zyxel.ch/de
- https://www.zyxel.ch/fr

#### Turke y

- Zyxel Turkey A.S.
- https://www.zyxel.com/tr/tr/

#### UK

- Zyxel Communications UK Ltd.
- https://www.zyxel.com/uk/en/

#### Ukra ine

- Zyxel Ukraine
- http://www.ua.zyxel.com

#### South America

#### Argentina

- Zyxel Communications Corporation
- https://www.zyxel.com/co/es/

#### Bra zil

- Zyxel Communications Brasil Ltda.
- https://www.zyxel.com/br/pt/

#### Colombia

- Zyxel Communications Corporation
- https://www.zyxel.com/co/es/

#### Ecuador

- Zyxel Communications Corporation
- https://www.zyxel.com/co/es/

#### South America

- Zyxel Communications Corporation
- https://www.zyxel.com/co/es/

#### Middle East

#### Isra e l

- Zyxel Communications Corporation
- http://il.zyxel.com/

#### Middle East

- Zyxel Communications Corporation
- https://www.zyxel.com/me/en/

#### North America

#### USA

- Zyxel Communications, Inc. North America Headquarters
- https://www.zyxel.com/us/en/

#### O c e a nia

#### Austra lia

- Zyxel Communications Corporation
- https://www.zyxel.com/au/en/

#### A fric a

#### So uth Afric a

- Nology (Pty) Ltd.
- https://www.zyxel.com/za/en/

## **APPENDIX B** Common Services

The following table lists some commonly-used services and their associated protocols and port numbers. For a comprehensive list of port numbers, ICMP type/code numbers and services, visit the IANA (Internet Assigned Number Authority) web site.

- **Name**: This is a short, descriptive name for the service. You can use this one or create a different one, if you like.
- **Protocol:** This is the type of IP protocol used by the service. If this is **TCP**/**UDP**, then the service uses the same port number with TCP and UDP. If this is **Use r-Defined**, the **Port(s)** is the IP protocol number, not the port number.
- Port(s): This value depends on the Protocol. Please refer to RFC 1700 for further information about port numbers.
  - If the Protocol is TCP, UDP, or TCP/UDP, this is the IP port number.
  - If the Protocol is USER, this is the IP protocol number.
- Description: This is a brief explanation of the applications that use this service or the situations in which this service is used.

NAME	PROTOCOL	PO RI(S)	DESC RIPTIO N
AH (IPSEC_TUNNEL)	User-Defined	51	The IPSEC AH (Authentication Header) tunneling protocol uses this service.
AIM/New-ICQ	TCP	5190	AOL's Internet Messenger service. It is also used as a listening port by ICQ.
AUTH	TCP	113	Authentication protocol used by some servers.
BGP	TCP	179	Border Gateway Protocol.
BOOTP_CLIENT	UDP	68	DHCP Client.
BOOTP_SERVER	UDP	67	DHCP Server.
CU-SEEME	TCP	7648	A popular videoconferencing solution from
	UDP	24032	White Pines Software.
DNS	TCP/UDP	53	Domain Name Server, a service that matches web names (for example <u>www.zyxel.com</u> ) to IP numbers.
ESP (IPSEC_TUNNEL)	User-Defined	50	The IPSEC ESP (Encapsulation Security Protocol) tunneling protocol uses this service.
FINGER	ТСР	79	Finger is a UNIX or Internet related command that can be used to find out if a user is logged on.
FTP	TCP	20	File Transfer Program, a program to enable fast
	ТСР	21	transfer of files, including large files that may not be possible by e-mail.
H.323	TCP	1720	NetMeeting uses this protocol.
HTTP	TCP	80	Hyper Text Transfer Protocol - a client/server protocol for the world wide web.

#### Table 196 Commonly Used Services

NAME	PROTOCOL	PO RI(S)	DESC RIPTIO N
HTTPS	TCP	443	HTTPS is a secured http session often used in e- commerce.
ICMP	User-Defined	1	Internet Control Message Protocol is often used for diagnostic or routing purposes.
ICQ	UDP	4000	This is a popular Internet chat program.
IGMP (MULTICAST)	User-Defined	2	Internet Group Multicast Protocol is used when sending packets to a specific group of hosts.
IKE	UDP	500	The Internet Key Exchange algorithm is used for key distribution and management.
IRC	TCP/UDP	6667	This is another popular Internet chat program.
MSN Messenger	TCP	1863	Microsoft Networks' messenger service uses this protocol.
NEW-ICQ	TCP	5190	An Internet chat program.
NEWS	TCP	144	A protocol for news groups.
NFS	UDP	2049	Network File System - NFS is a client/server distributed file service that provides transparent file sharing for network environments.
NNTP	TCP	119	Network News Transport Protocol is the delivery mechanism for the USENET newsgroup service.
PING	User-Defined	1	Packet INternet Groper is a protocol that sends out ICMP echo requests to test whether or not a remote host is reachable.
POP3	TCP	110	Post Office Protocol version 3 lets a client computer get e-mail from a POP3 server through a temporary connection (TCP/IP or other).
РРТР	TCP	1723	Point-to-Point Tunneling Protocol enables secure transfer of data over public networks. This is the control channel.
PPTP_TUNNEL (GRE)	User-Defined	47	PPTP (Point-to-Point Tunneling Protocol) enables secure transfer of data over public networks. This is the data channel.
RCMD	TCP	512	Remote Command Service.
REAL_AUDIO	TCP	7070	A streaming audio service that enables real time sound over the web.
REXEC	TCP	514	Remote Execution Daemon.
RLOGIN	TCP	513	Remote Login.
RTELNET	TCP	107	Remote Telnet.
RTSP	TCP/UDP	554	The Real Time Streaming (media control) Protocol (RTSP) is a remote control for multimedia on the Internet.
SFTP	TCP	115	Simple File Transfer Protocol.
SMTP	ТСР	25	Simple Mail Transfer Protocol is the message- exchange standard for the Internet. SMTP enables you to move messages from one e-mail server to another.
SNMP	TCP/UDP	161	Simple Network Management Program.
SNMP-TRAPS	TCP/UDP	162	Traps for use with the SNMP (RFC:1215).

Table 196	Commonly Used Services (continued)
-----------	------------------------------------

NAME	PROTOCOL	PO RI(S)	DESC RIPTIO N
SQL-NET	TCP	1521	Structured Query Language is an interface to access data on many different types of database systems, including mainframes, midrange systems, UNIX systems and network servers.
SSH	TCP/UDP	22	Secure Shell Remote Login Program.
STRM WORKS	UDP	1558	Stream Works Protocol.
SYSLOG	UDP	514	Syslog allows you to send system logs to a UNIX server.
TACACS	UDP	49	Login Host Protocol used for (Terminal Access Controller Access Control System).
TELNET	TCP	23	Telnet is the login and terminal emulation protocol common on the Internet and in UNIX environments. It operates over TCP/IP networks. Its primary function is to allow users to log into remote host systems.
TFTP	UDP	69	Trivial File Transfer Protocol is an Internet file transfer protocol similar to FTP, but uses the UDP (User Datagram Protocol) rather than TCP (Transmission Control Protocol).
VDOLIVE	TCP	7000	Another videoconferencing solution.

Table 196 Commonly Used Services (continued)

## A PPENDIX C IPv6

#### Ove rvie w

IPv6 (Internet Protocol version 6), is designed to enhance IP address size and features. The increase in IPv6 address size to 128 bits (from the 32-bit IPv4 address) allows up to  $3.4 \times 10^{38}$  IP addresses.

#### IPv6 Addressing

The 128-bit IPv6 address is written as eight 16-bit hexadecimal blocks separated by colons (:). This is an example IPv6 address 2001:0db8:1a2b:0015:0000:1a2f:0000.

IPv6 addresses can be abbreviated in 2 ways:

- Leading zeros in a block can be omitted. So 2001:0db8:1a2b:0015:0000:0000:1a2f:0000 can be written as 2001:db8:1a2b:15:0:0:1a2f:0.
- Any number of consecutive blocks of zeros can be replaced by a double colon. A double colon can only appear once in an IPv6 address. So 2001:0db8:0000:0000:1a2f:0000:0000:0015 can be written as 2001:0db8::1a2f:0000:0000:0015, 2001:0db8:0000:0000:1a2f::0015, 2001:db8::1a2f:0:0:15 or 2001:db8:0:0:1a2f::15.

#### Prefix and Prefix Length

Similar to an IPv4 subnet mask, IPv6 uses an address prefix to represent the network address. An IPv6 prefix length specifies how many most significant bits (start from the left) in the address compose the network address. The prefix length is written as "/x" where x is a number. For example,

2001:db8:1a2b:15::1a2f:0/32

means that the first 32 bits (2001:db8) is the subnet prefix.

#### Link-local Address

A link-local address uniquely identifies a device on the local network (the LAN). It is similar to a "private IP address" in IPv4. You can have the same link-local address on multiple interfaces on a device. A link-local unicast address has a predefined prefix of fe80::/10. The link-local unicast address format is as follows.

Table 197 Link-local Unicast Address Format

1111 1110 10	0	Interface ID
10 bits	54 bits	64 bits

#### **Global Address**

A global address uniquely identifies a device on the Internet. It is similar to a "public IP address" in IPv4. A global unicast address starts with a 2 or 3.

#### Unspecified Address

An unspecified address (0:0:0:0:0:0:0:0:0 or ::) is used as the source address when a device does not have its own address. It is similar to "0.0.0.0" in IPv4.

#### Loopback Address

A loopback address (0:0:0:0:0:0:0:0:1 or ::1) allows a host to send packets to itself. It is similar to "127.0.0.1" in IPv4.

#### Multic a st Addre ss

In IPv6, multicast addresses provide the same functionality as IPv4 broadcast addresses. Broadcasting is not supported in IPv6. A multicast address allows a host to send packets to all hosts in a multicast group.

Multicast scope allows you to determine the size of the multicast group. A multicast address has a predefined prefix of ff00::/8. The following table describes some of the predefined multicast addresses.

Table 198 Predefined Multicast Address

MULTICASTADDRESS	DESC RIPTIO N
FF01:0:0:0:0:0:0:1	All hosts on a local node.
FF01:0:0:0:0:0:0:2	All routers on a local node.
FF02:0:0:0:0:0:1	All hosts on a local connected link.
FF02:0:0:0:0:0:0:2	All routers on a local connected link.
FF05:0:0:0:0:0:0:2	All routers on a local site.
FF05:0:0:0:0:1:3	All DHCP severs on a local site.

The following table describes the multicast addresses which are reserved and cannot be assigned to a multicast group.

Table 199 Reserved Multicast Address	Table 199
--------------------------------------	-----------

MULTIC A ST A DDRESS         FF00:0:0:0:0:0:0         FF01:0:0:0:0:0:0         FF01:0:0:0:0:0:0         FF02:0:0:0:0:0:0         FF03:0:0:0:0:0:0         FF03:0:0:0:0:0:0         FF04:0:0:0:0:0:0         FF05:0:0:0:0:0:0         FF05:0:0:0:0:0:0         FF06:0:0:0:0:0         FF07:0:0:0:0:0         FF08:0:0:0:0:0         FF08:0:0:0:0:0         FF09:0:0:0:0:0         FF00:0:0:0:0         FF00:0:0:0:0         FF00:0:0:0         FF00:0:0:0         FF0D:0:0         FF0D:0:0         FF0D:0         FF	
FF01:0:0:0:0:0:0:0         FF02:0:0:0:0:0:0:0         FF03:0:0:0:0:0:0:0         FF04:0:0:0:0:0:0:0         FF05:0:0:0:0:0:0:0         FF05:0:0:0:0:0:0:0         FF06:0:0:0:0:0:0:0         FF07:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0	MULTICASTADDRESS
FF02:0:0:0:0:0:0:0         FF03:0:0:0:0:0:0:0         FF04:0:0:0:0:0:0:0         FF05:0:0:0:0:0:0:0         FF06:0:0:0:0:0:0:0         FF07:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF00B:0:0:0:0:0:0         FF0C:0:0:0:0:0:0         FF0D:0:0:0:0:0:0         FF0D:0:0:0:0:0:0	FF00:0:0:0:0:0:0:0
FF03:0:0:0:0:0:0:0         FF04:0:0:0:0:0:0:0         FF05:0:0:0:0:0:0:0         FF06:0:0:0:0:0:0         FF07:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF09:0:0:0:0:0         FF00:0:0:0:0:0         FF00:0:0:0:0:0         FF00:0:0:0:0:0	FF01:0:0:0:0:0:0:0
FF04:0:0:0:0:0:0:0         FF05:0:0:0:0:0:0:0         FF06:0:0:0:0:0:0:0         FF07:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0	FF02:0:0:0:0:0:0:0
FF05:0:0:0:0:0:0:0         FF06:0:0:0:0:0:0         FF07:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF08:0:0:0:0:0:0         FF09:0:0:0:0:0:0         FF00:0:0:0:0:0         FF0D:0:0:0:0:0         FF0D:0:0:0:0:0         FF0E:0:0:0:0:0	FF03:0:0:0:0:0:0:0
FF06:0:0:0:0:0:0:0         FF07:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0         FF00:0:0:0:0:0:0	FF04:0:0:0:0:0:0:0
FF07:0:0:0:0:0:0:0         FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0:0         FF0A:0:0:0:0:0:0:0         FF0B:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0	FF05:0:0:0:0:0:0:0
FF08:0:0:0:0:0:0:0         FF09:0:0:0:0:0:0:0         FF0A:0:0:0:0:0:0:0         FF0B:0:0:0:0:0:0:0         FF0C:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0	FF06:0:0:0:0:0:0:0
FF09:0:0:0:0:0:0:0         FF0A:0:0:0:0:0:0:0         FF0B:0:0:0:0:0:0:0         FF0C:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0	FF07:0:0:0:0:0:0:0
FF0A:0:0:0:0:0:0:0         FF0B:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0	FF08:0:0:0:0:0:0:0
FF0B:0:0:0:0:0:0:0         FF0C:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0	FF09:0:0:0:0:0:0:0
FF0C:0:0:0:0:0:0:0         FF0D:0:0:0:0:0:0:0:0         FF0E:0:0:0:0:0:0:0:0	FF0A:0:0:0:0:0:0:0
FF0D: 0: 0: 0: 0: 0: 0: 0 FF0E: 0: 0: 0: 0: 0: 0: 0	FF0B:0:0:0:0:0:0:0
FF0E:0:0:0:0:0:0:0	FF0C:0:0:0:0:0:0:0
	FF0D:0:0:0:0:0:0:0
FF0F:0:0:0:0:0:0:0	FF0E:0:0:0:0:0:0:0
	FF0F:0:0:0:0:0:0:0

### Subnet Masking

### Interface ID

In IPv6, an interface ID is a 64-bit identifier. It identifies a physical interface (for example, an Ethernet port) or a virtual interface (for example, the management IP address for a VLAN). One interface should have a unique interface ID.

### EUI-64

The EUI-64 (Extended Unique Identifier) defined by the IEEE (Institute of Electrical and Electronics Engineers) is an interface ID format designed to adapt with IPv6. It is derived from the 48-bit (6-byte) Ethernet MAC address as shown next. EUI-64 inserts the hex digits fffe between the third and fourth bytes of the MAC address and complements the seventh bit of the first byte of the MAC address. See the following example.

Table 200

MAC		00		3 :	49	:	12	:	34	:	56		
Table 201													
EUI- 64	02	: 13	: 4	19 :	FF	:	FE	:	12	:	34	:	56

#### State less Auto-configuration

With stateless auto-configuration in IPv6, addresses can be uniquely and automatically generated. Unlike DHCPv6 (Dynamic Host Configuration Protocol version six) which is used in IPv6 stateful autoconfiguration, the owner and status of addresses don't need to be maintained by a DHCP server. Every IPv6 device is able to generate its own and unique IP address automatically when IPv6 is initiated on its interface. It combines the prefix and the interface ID (generated from its own Ethernet MAC address, see Interface ID and EUI-64) to form a complete IPv6 address.

When IPv6 is enabled on a device, its interface automatically generates a link-local address (beginning with fe80).

When the interface is connected to a network with a router and the Switch is set to automatically obtain an IPv6 network prefix from the router for the interface, it generates <sup>2</sup>another address which combines its interface ID and global and subnet information advertised from the router. This is a routable global IP address.

### DHC Pv6


The Dynamic Host Configuration Protocol for IPv6 (DHCPv6, RFC 3315) is a server-client protocol that allows a DHCP server to assign and pass IPv6 network addresses, prefixes and other configuration information to DHCP clients. DHCPv6 servers and clients exchange DHCP messages using UDP.

<sup>2.</sup> In IPv6, all network interfaces can be associated with several addresses.

Each DHCP client and server has a unique DHCP Unique IDentifier (DUID), which is used for identification when they are exchanging DHCPv6 messages. The DUID is generated from the MAC address, time, vendor assigned ID and/or the vendor's private enterprise number registered with the IANA. It should not change over time even after you reboot the device.

### Identity Association

An Identity Association (IA) is a collection of addresses assigned to a DHCP client, through which the server and client can manage a set of related IP addresses. Each IA must be associated with exactly one interface. The DHCP client uses the IA assigned to an interface to obtain configuration from a DHCP server for that interface. Each IA consists of a unique IAID and associated IP information. The IA type is the type of address in the IA. Each IA holds one type of address. IA\_NA means an identity association for non-temporary addresses and IA\_TA is an identity association for temporary addresses. An IA\_NA option contains the T1 and T2 fields, but an IA\_TA option does not. The DHCPv6 server uses T1 and T2 to control the time at which the client contacts with the server to extend the lifetimes on any addresses in the IA\_NA were obtained) a Renew message. If the time T2 is reached and the server does not respond, the client sends a Rebind message to any available server (**S2**). For an IA\_TA, the client may send a Renew or Rebind message at the client's discretion.



### DHCP Re la y Agent

A DHCP relay agent is on the same network as the DHCP clients and helps forward messages between the DHCP server and clients. When a client cannot use its link-local address and a well-known multicast address to locate a DHCP server on its network, it then needs a DHCP relay agent to send a message to a DHCP server that is not attached to the same network.

The DHCP relay agent can add the remote identification (remote-ID) option and the interface-ID option to the Relay-Forward DHCPv6 messages. The remote-ID option carries a user-defined string, such as the system name. The interface-ID option provides slot number, port information and the VLAN ID to the DHCPv6 server. The remote-ID option (if any) is stripped from the Relay-Reply messages before the relay agent sends the packets to the clients. The DHCP server copies the interface-ID option from the Relay-Forward message into the Relay-Reply message and sends it to the relay agent. The interface-ID should not change even after the relay agent restarts.

### Pre fix De le g a tio n

Prefix delegation enables an IPv6 router to use the IPv6 prefix (network address) received from the ISP (or a connected uplink router) for its LAN. The Switch uses the received IPv6 prefix (for example, 2001:db2::/ 48) to generate its LAN IP address. Through sending Router Advertisements (RAs) regularly by multicast, the Switch passes the IPv6 prefix information to its LAN hosts. The hosts then can use the prefix to generate their IPv6 addresses.

398

### IC MPv6

Internet Control Message Protocol for IPv6 (ICMPv6 or ICMP for IPv6) is defined in RFC 4443. ICMPv6 has a preceding Next Header value of 58, which is different from the value used to identify ICMP for IPv4. ICMPv6 is an integral part of IPv6. IPv6 nodes use ICMPv6 to report errors encountered in packet processing and perform other diagnostic functions, such as "ping".

### Neighbor Discovery Protocol (NDP)

The Neighbor Discovery Protocol (NDP) is a protocol used to discover other IPv6 devices and track neighbor's reachability in a network. An IPv6 device uses the following ICMPv6 messages types:

- Neighbor solicitation: A request from a host to determine a neighbor's link-layer address (MAC address) and detect if the neighbor is still reachable. A neighbor being "reachable" means it responds to a neighbor solicitation message (from the host) with a neighbor advertisement message.
- Neighbor advertisement: A response from a node to announce its link-layer address.
- Router solicitation: A request from a host to locate a router that can act as the default router and forward packets.
- Router advertisement: A response to a router solicitation or a periodical multicast advertisement from a router to advertise its presence and other parameters.

### IPv6 Cache

An IPv6 host is required to have a neighbor cache, destination cache, prefix list and default router list. The Switch maintains and updates its IPv6 caches constantly using the information from response messages. In IPv6, the Switch configures a link-local address automatically, and then sends a neighbor solicitation message to check if the address is unique. If there is an address to be resolved or verified, the Switch also sends out a neighbor solicitation message. When the Switch receives a neighbor advertisement in response, it stores the neighbor's link-layer address in the neighbor cache. When the Switch uses a router solicitation message to query for a router and receives a router advertisement message, it adds the router's information to the neighbor cache, prefix list and destination cache. The Switch creates an entry in the default router list cache if the router can be used as a default router.

When the Switch needs to send a packet, it first consults the destination cache to determine the next hop. If there is no matching entry in the destination cache, the Switch uses the prefix list to determine whether the destination address is on-link and can be reached directly without passing through a router. If the address is onlink, the address is considered as the next hop. Otherwise, the Switch determines the next-hop from the default router list or routing table. Once the next hop IP address is known, the Switch looks into the neighbor cache to get the link-layer address and sends the packet when the neighbor is reachable. If the Switch cannot find an entry in the neighbor cache or the state for the neighbor is not reachable, it starts the address resolution process. This helps reduce the number of IPv6 solicitation and advertisement messages.

### Example - Enabling IPv6 on Windows XP/2003/Vista

By default, Windows XP and Windows 2003 support IPv6. This example shows you how to use the ipv6 install command on Windows XP/2003 to enable IPv6. This also displays how to use the ipconfig command to see auto-generated IP addresses.

IPv6 is installed and enabled by default in Windows Vista. Use the *ipconfig* command to check your automatic configured IPv6 address as well. You should see at least one IPv6 address available for the interface on your computer.

### Example - Enabling DHCPv6 on Windows XP

Windows XP does not support DHCPv6. If your network uses DHCPv6 for IP address assignment, you have to additionally install a DHCPv6 client software on your Windows XP. (Note: If you use static IP addresses or Router Advertisement for IPv6 address assignment in your network, ignore this section.)

This example uses Dibbler as the DHCPv6 client. To enable DHCPv6 client on your computer:

- 1 Install Dibbler and select the DHCPv6 client option on your computer.
- 2 After the installation is complete, select Start > All Programs > Dib b ler DHC Pv6 > C lient Install as service.
- 3 Select Start > Control Panel > Administrative Tools > Services.
- 4 Double click Dibbler- a DHC Pv6 client.

팀 Columbia (Loop )	Services (Local)						
	Dibbler - a DHCPv6 client	-18°6 -	Description	10004	tonia igos	toponia	14
	Depice a chief to cherk	<b>Франции на селот на селот</b>	Aran decise .		• # 2007.00	Local unitam	12
	Start the screek	Statik Care Solither of Totacet	Tester e	Obertaic	Automode Automode	Loca Sugar	1
		Hitten a file faith faith Brance Dynasta ( anneith Brancher:	National and an Constant second seco		d diana k Menaz Automatik	from Source Metwork Source Metwork 1	
	Dibble - a periable DHCPv6.	References References References	Ak-rans. Bratki m	Contine -	Aufsande Aufsande	Loca 241917	
	This is OHCIV6 disnt, yonsu 0.7.2.	All the standard standards at the state	Andrea Andrea		Mars. Mars	traces and traces and	
	1	Rest	horeas.		20042	1008-01911	$^{\circ}$ b

5 Click Start and then OK.

	enter (Register (Law Grage (19)) 🥂 👔
thend digits	Frances De male sie
Service same	DI 0%32.49
Day System	2 states Diff. No days
Description	Calls applied (Dr. Set (Dr. 1909)) for approx(),2
Peinio executi United set into	tio no MCMAR Jacobiel State national end and and an an an an ANNAN
St. giby r	a de la de
Service of a 24 Vice experts backer Skippe else	Salayed Prove Prove Decare De
	tarte lectr


6 Now your computer can obtain an IPv6 address from a DHCPv6 server.

### Example - Enabling IPv6 on Windows 7

Windows 7 supports IPv6 by default. DHCPv6 is also enabled when you enable IPv6 on a Windows 7 computer.

To enable IPv6 in Windows 7:

- 1 Select Control Panel > Network and Sharing Center > Local Area Connection.
- 2 Select the Internet Protocol Version 6 (TCP/IPv6) check box to enable it.
- 3 Click **OK** to save the change.



- 4 Click Close to exit the Local Area Connection Status screen.
- 5 Select Start > All Programs > Accessories > Command Prompt.
- 6 Use the ipconfig command to check your dynamic IPv6 address. This example shows a global address (2001:b021:2d::1000) obtained from a DHCP server.

# A PPENDIX D Legal Information

#### Copyright

Copyright © 2020 by Zyxel Communications Corporation.

The contents of this publication may not be reproduced in any part or as a whole, transcribed, stored in a retrieval system, translated into any language, or transmitted in any form or by any means, electronic, mechanical, magnetic, optical, chemical, photocopying, manual, or otherwise, without the prior written permission of Zyxel Communications Corporation. Published by Zyxel Communications Corporation. All rights reserved.

ublished by Zyxel Communications Corporation. All rights rese

#### Disc la im e r

Zyxel does not assume any liability arising out of the application or use of any products, or software described herein. Neither does it convey any license under its patent rights nor the patent rights of others. Zyxel further reserves the right to make changes in any products described herein without notice. This publication is subject to change without notice.

#### Regulatory Notice and Statement

#### **United States of America**



The following information applies if you use the product within USA area.

#### Federal Communications Commission (FCC) EMC Statement

- This device complies with Part 15 of FCC rules. Operation is subject to the following two conditions:
  - (1) This device may not cause harmful interference.
  - (2) This device must accept any interference received, including interference that may cause undesired operations.
- Changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.
- This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

#### Canada

The following information applies if you use the product within Canada area.

#### Innovation, Science and Economic Development Canada ICES statement

CAN ICES-3 (A)/NMB-3(A)

#### **European Union**



The following information applies if you use the product within the European Union.

#### CEEMC statement

WARNING: This equipment is compliant with Class A of EN55032. In a residential environment this equipment may cause radio interference.

403

COUNTRY	ISO 3166 2 LETTER CODE	COUNTRY	ISO 3166 2 LETTER CODE		
Austria	AT	Liechtenstein	LI		
Belgium	BE	Lithuania	LT		
Bulgaria	BG	Luxembourg	LU		
Croatia	HR	Malta	MT		
Cyprus	СҮ	Netherlands	NL		
Czech Republic	CR	Norway	NO		
Denmark	DK	Poland	PL		
Estonia	EE	Portugal	PT		
Finland	FI	Romania	RO		
France	FR	Serbia	RS		
Germany	DE	Slovakia	SK		
Greece	GR	Slovenia	SI		
Hungary	HU	Spain	ES		
Iceland	IS	Sweden	SE		
Ireland	IE	Switzerland	СН		
Italy	IT	Turkey	TR		
Latvia	LV	United Kingdom	GB		

#### List of National Codes

#### Safety Wamings

- To avoid possible eye injury, do NOT look into an operating fiber-optic module's connector.
- Do not use this product near water, for example, in a wet basement or near a swimming pool.
- Do not expose your device to dampness, dust or corrosive liquids.
- Do not store things on the device.
- Do not obstruct the device ventilation slots as insufficient airflow may harm your device. For example, do not place the device in an
- enclosed space such as a box or on a very soft surface such as a bed or sofa.Do not install, use, or service this device during a thunderstorm. There is a remote risk of electric shock from lightning.
- Connect ONLY suitable accessories to the device.
- Do not open the device or unit. Opening or removing covers can expose you to dangerous high voltage points or other risks. Only qualified service personnel should service or disassemble this device. Please contact your vendor for further information.
- Make sure to connect the cables to the correct ports.
- Place connecting cables carefully so that no one will step on them or stumble over them.
- Always disconnect all cables from this device before servicing or disassembling.
- Do not remove the plug and connect it to a power outlet by itself; always attach the plug to the power adaptor first before connecting it to a power outlet.
- Do not allow anything to rest on the power adaptor or cord and do NOT place the product where anyone can walk on the power adaptor or cord.
- Please use the provided or designated connection cables/power cables/ adaptors. Connect it to the right supply voltage (for example, 110V AC in North America or 230V AC in Europe). If the power adaptor or cord is damaged, it might cause electrocution. Remove it from the device and the power source, repairing the power adapter or cord is prohibited. Contact your local vendor to order a new one.
- Do not use the device outside, and make sure all the connections are indoors. There is a remote risk of electric shock from lightning.
   Caution: Risk of explosion if battery is replaced by an incorrect type, dispose of used batteries according to the instruction. Dispose them at the applicable collection point for the recycling of electrical and electronic device. For detailed information about recycling of this product, please contact your local city office, your household waste disposal service or the store where you purchased the product.
- Use ONLY power wires of the appropriate wire gauge for your device. Connect it to a power supply of the correct voltage.
- Fuse Warning! Replace a fuse only with a fuse of the same type and rating.
- The POE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.
- The following warning statements apply, where the disconnect device is not incorporated in the device or where the plug on the power supply cord is intended to serve as the disconnect device,
  - For permanently connected devices, a readily accessible disconnect device shall be incorporated external to the device;
- For pluggable devices, the socket-outlet shall be installed near the device and shall be easily accessible.
- This device must be grounded by qualified service personnel. Never defeat the ground conductor or operate the device in the absence of a suitably installed ground conductor. Contact the appropriate electrical inspection authority or an electrician if you are uncertain that suitable grounding is available.
- When connecting or disconnecting power to hot-pluggable power supplies, if offered with your system, observe the following guidelines: - Install the power supply before connecting the power cable to the power supply.
  - Unplug the power cable before removing the power supply.
  - If the system has multiple sources of power, disconnect power from the system by unplugging all power cables from the power supply.
- CLASS 1 LASER PRODUCT (for products with mini-GBIC slots or laser products, such as fiber-optic transceiver and GPON products).
   PRODUCT COMPLIES WITH 21 CFR 1040.10 AND 1040.11. (for products with mini-GBIC slots or laser products, such as fiber-optic transceiver and GPON products)
- APPAREIL À LASER DE CLASS 1 (for products with mini-GBIC slots or laser products, such as fiber-optic transceiver and GPON products).

PRODUIT CONFORME SELON 21 CFR 1040.10 ET 1040.11. (for products with mini-GBIC slots or laser products, such as fiber-optic transceiver and GPON products)

#### Environment Statement

#### European Union - Disposal and Recycling Information

The symbol below means that according to local regulations your product and/or its battery shall be disposed of separately from domestic waste. If this product is end of life, take it to a recycling station designated by local authorities. At the time of disposal, the separate collection of your product and/or its battery will help save natural resources and ensure that the environment is sustainable development.

Die folgende Symbol bedeutet, dass Ihr Produkt und/oder seine Batterie gemäß den örtlichen Bestimmungen getrennt vom Hausmüll entsorgt werden muss. Wenden Sie sich an eine Recyclingstation, wenn dieses Produkt das Ende seiner Lebensdauer erreicht hat. Zum Zeitpunkt der Entsorgung wird die getrennte Sammlung von Produkt und/oder seiner Batterie dazu beitragen, natürliche Ressourcen zu sparen und die Umwelt und die menschliche Gesundheit zu schützen.

El símbolo de abajo indica que según las regulaciones locales, su producto y/o su batería deberán depositarse como basura separada de la domástica. Cuando este producto alcance el final de su vida útil, llévelo a un punto limpio. Cuando llegue el momento de desechar el producto, la recogida por separado éste y/o su batería ayudará a salvar los recursos naturales y a proteger la salud humana y medioambiental.

Le symbole ci-dessous signifie que selon les réglementations locales votre produit et/ou sa batterie doivent être éliminés séparément des ordures ménagères. Lorsque ce produit atteint sa fin de vie, amenez-le à un centre de recyclage. Au moment de la mise au rebut, la collecte séparée de votre produit et/ou de sa batterie aidera à économiser les ressources naturelles et protéger l'environnement et la santé humaine.

Il simbolo sotto significa che secondo i regolamenti locali il vostro prodotto e/o batteria deve essere smaltito separatamente dai rifiuti domestici. Quando questo prodotto raggiunge la fine della vita di servizio portarlo a una stazione di riciclaggio. Al momento dello smaltimento, la raccolta separata del vostro prodotto e/o della sua batteria aiuta a risparmiare risorse naturali e a proteggere l'ambiente e la salute umana.

Symbolen innebär att enligt lokal lagstiftning ska produkten och/eller dess batteri kastas separat från hushållsavfallet. När den här produkten når slutet av sin livslängd ska du ta den till en återvinningsstation. Vid tiden för kasseringen bidrar du till en bättre miljö och mänsklig hälsa genom att göra dig av med den på ett återvinningsställe.



#### 台灣

警告使用者:

• 這是甲類的資訊產品,在居住的環境中使用時,可能會造成射頻干擾,在這種情況下,使用者會被要求採取某些適當的對策。」

安全警告 - 為了您的安全, 請先閱讀以下警告及指示:

- 請勿將此產品接近水、火焰或放置在高溫的環境。
- 避免設備接觸
  - 任何液體 切勿讓設備接觸水、雨水、高濕度、污水腐蝕性的液體或其他水份。
  - 灰塵及污物 切勿接觸灰塵、污物、沙土、食物或其他不合適的材料。
- · 雷雨天氣時,不要安裝,使用或維修此設備。有遭受電擊的風險。
- 切勿重摔或撞擊設備,並勿使用不正確的電源變壓器。
- 若接上不正確的電源變壓器會有爆炸的風險。
- 請勿隨意更換產品內的電池。
- 如果更換不正確之電池型式,會有爆炸的風險,請依製造商說明書處理使用過之電池。
- 請將廢電池丟棄在適當的電器或電子設備回收處。
- 請勿將設備解體。
- 請勿阻礙設備的散熱孔,空氣對流不足將會造成設備損害。
- 請插在正確的電壓供給插座 (如:北美 / 台灣電壓 110V AC, 歐洲是 230V AC)。
- 假若電源變壓器或電源變壓器的纜線損壞,請從插座拔除,若您還繼續插電使用,會有觸電死亡的風險。
- 請勿試圖修理電源變壓器或電源變壓器的纜線,若有毀損,請直接聯絡您購買的店家,購買一個新的電源變壓器。
- 請勿將此設備安裝於室外,此設備僅適合放置於室內。

GS1350 Series User's Guide

- 請勿隨一般垃圾丟棄。
- 請參閱產品背貼上的設備額定功率。
- 請參考產品型錄或是彩盒上的作業溫度。
- 設備必須接地,接地導線不允許被破壞或沒有適當安裝接地導線,如果不確定接地方式是否符合要求可聯繫相應的電氣檢驗機構檢驗。
- 如果您提供的系統中有提供熱插拔電源,連接或斷開電源請遵循以下指導原則:
   先連接電源線至設備連,再連接電源。
  - 先斷開電源再拔除連接至設備的電源線。
  - 如果系統有多個電源,需拔除所有連接至電源的電源線再關閉設備電源。
- 產品沒有斷電裝置或者採用電源線的插頭視為斷電裝置的一部分,以下警語將適用:
  - 對永久連接之設備,在設備外部須安裝可觸及之斷電裝置;
  - 對插接式之設備,插座必須接近安裝之地點而且是易於觸及的。

#### About the Symbols

Various symbols are used in this product to ensure correct usage, to prevent danger to the user and others, and to prevent property damage. The meaning of these symbols are described below. It is important that you read these descriptions thoroughly and fully understand the contents.

#### Explanation of the Symbols

SYMBOL	EXPLANATION
	Alternating current (AC):
$\sim$	AC is an electric current in which the flow of electric charge periodically reverses direction.
	Direct current (DC):
	DC if the unidirectional flow or movement of electric charge carriers.
	Earth; ground:
	A wiring terminal intended for connection of a Protective Earthing Conductor.
	Class II equipment:
	The method of protection against electric shock in the case of class II equipment is either double insulation or reinforced insulation.

### Viewing Certifications

Go to http://www.zyxel.com to view this product's documentation and certifications.

#### Zyxel Limited Warranty

Zyxel warrants to the original end user (purchaser) that this product is free from any defects in material or workmanship for a specific period (the Warranty Period) from the date of purchase. The Warranty Period varies by region. Check with your vendor and/or the authorized Zyxel local distributor for details about the Warranty Period of this product. During the warranty period, and upon proof of purchase, should the product have indications of failure due to faulty workmanship and/or materials, Zyxel will, at its discretion, repair or replace the defective products or components without charge for either parts or labor, and to whatever extent it shall deem necessary to restore the product or components to proper operating condition. Any replacement will consist of a new or re-manufactured functionally equivalent product of equal or higher value, and will be solely at the discretion of Zyxel. This warranty shall not apply if the product has been modified, misused, tampered with, damaged by an act of God, or subjected to abnormal working conditions.

#### Note

Repair or replacement, as provided under this warranty, is the exclusive remedy of the purchaser. This warranty is in lieu of all other warranties, express or implied, including any implied warranty of merchantability or fitness for a particular use or purpose. Zyxel shall in no event be held liable for indirect or consequential damages of any kind to the purchaser.

To obtain the services of this warranty, contact your vendor. You may also refer to the warranty policy for the region in which you bought the device at http://www.zyxel.com/web/support\_warranty\_info.php.

#### Registration

Register your product online at www.zyxel.com to receive e-mail notices of firmware upgrades and related information.

#### Trademarks

ZyNOS (Zyxel Network Operating System) and ZON (Zyxel One Network) are registered trademarks of Zyxel Communications, Inc. Other trademarks mentioned in this publication are used for identification purposes only and may be properties of their respective owners.

# Index

### **Numerics**

802.1P priority 101, 341

### Α

AAA 176 accounting 176 authentication 176 authorization 176 external server 176 RADIUS 176 **TACACS+ 176** AAA (Authentication, Authorization and Accounting) 176 AAA screen 177 Access Control overview 364 access control limitations 268, 364 login account 274, 364 overview 268 remote management 277, 366 service port 276, 374 SNMP 279 Access Control screen 268 accounting setup 179 add or edit static VLAN 357 Address Resolution Protocol (ARP) 253, 308, 311, 312 administrator password 46, 275, 365 AES (Advanced Encryption Standard) 373 aging time 93 All connected Setting Wizard 135 applications backbone 22 bridging 23 fiber uplink 23 IEEE 802.1Q VLAN 24

PoE 21 switched workgroup 24 ARP how it works 253 learning mode 253 overview 253 setup 255 ARP (Address Resolution Protocol) 308 ARP Learning screen 255 ARP Setup screen 255 ARP Table screen 308 ARP-Reply 253 ARP-Request 254 authentication setup 179 authentication, authorization and accounting 176 authorization privilege levels 180 setup 179 auto PD recovery 230 enable 230, 333 quick link 327 restart 230 use LLDP or ping 230, 333 auto-crossover port 33 auto-fan 20 automatic PD recovery create 232 automatic VLAN registration 352 auto-MDIX port 33

### В

back up configuration file 262, 376 Backup Configuration screen 262, 376, 379 bandwidth control 150, 151 egress rate 151 ingress rate 151 setup 150

GS1350 Series User's Guide

407

Bandwidth Control screen 150 basic settings 88 basic setup tutorial 74 Basic TLV Setting screen 223 binding table building 185 BPDUs 145 Bridge Protocol Data Units (BPDUs) 145 broadcast storm control 152 Wizard 56 Broadcast Storm Control screen 343

# С

CE EMC statement 403 Certificates screen 264 certifications viewing 406 CFI (Canonical Format Indicator) 122, 352 changing the password 66 Class of Service 237 cloning a port, see port cloning Cloud Management screen 332 cluster management 299 and switch passwords 302 cluster manager 299, 301 cluster member 299, 302 cluster member firmware upgrade 303 network example 299 setup 301 specification 299 status 300 switch models 299 VID 301 Web Configurator 302 Cluster Management Configuration screen 301 cluster manager 299 configuration change running config 259, 378 save 380 saving 66 configuration file backup 262, 376 restore 261, 379 save 259, 380

Configure Clone screen **311** console port settings **38** contact information customer support **386** copying port settings, see port cloning copyright **403** CoS **237** CPU management port **133** CPU protection **199** current date **91**, **330** current time **91**, **330** custom default restore **36**, **67** customer support **386** 

### D

date current 91 daylight saving time 91, 331 DDMI Details screen 320 DDMI screen 319 DES (Data Encryption Standard) 373 DHCP configuration options 241 Dynamic Host Configuration Protocol 241 modes **241** Relay Agent Information format 243 setup 242 DHCP Option 82 Profile screen 244 DHCP relay configure 80 tutorial 77 DHCP relay agent 398 DHCP relay option 82 194 DHCP Relay screen 245, 247 DHCP screen 242 DHCP snooping 74, 193 configure 195 DHCP relay option 82 194 trusted ports 193 untrusted ports 193 DHCP Snooping Configure screen 189

DHCP snooping database 194 DHCP Snooping Port Configure screen 76, 190 DHCP Snooping screen 186 DHCP Snooping VLAN Configure screen 191 DHCP Status screen 242 DHCP Unique IDentifier (DUID) 398 DHCP-assigned IP 383 DHCPv4 global relay 245 global relay example 247 option 82 243 option 82 profiles 244 Relay Agent Information 243 DHCPv4 relay 242 DHCPv6 enable in Windows XP 400 DHCPv6 Client Setup screen 118 DHCPv6 relay 251 interface-ID 251 remote-ID 251 DHCPv6 Relay screen 251 diagnostics 292 Ethernet port test 293 ping 293 Differentiated Service (DiffServ) 237 DiffServ 237 activate 238 DS field 237 DSCP 237 network example 238 PHB 237 service level 237 DiffServ Code Points 237 Digital Diagnostics Monitoring Interface 319 disclaimer 403 disposal and recycling information EU 405 DS (Differentiated Services) 237 DSCP 237 what it does 237 dual firmware images 260, 377 dual personality interface 40 Dynamic Host Configuration Protocol for IPv6 (DHCPv6) 397 dynamic link aggregation 156

### Ε

egress port 135 egress rate 151 electrostatic discharge (ESD) 33 Environment Statement 405 Errdisable Detect screen 203 Errdisable Recovery screen 204 Errdisable screen 200 errdisable status 202 error disable 199 control packets 201 CPU protection 202 detect 203 recovery 204 status 200 error-disable recovery 199 Ethernet broadcast address 253, 308 Ethernet MAC 89, 329 Ethernet port auto-crossover 32 auto-negotiating 32 dual personality 33 Ethernet port test 293 Ethernet ports number of 20 Ethernet settings default 33 external authentication server 177

# F

FCC interference statement 403 fiber optic cable connecting 34 removal 35 file transfer using FTP command example 266 filename convention, configuration file names 266 filtering 142 rules 142 filtering database, MAC table 305 Filtering screen 142 firmware 329 upgrade 260, 303, 377 ZyNOS 89 firmware upgrade 377 Firmware Upgrade screen 260 flow control back pressure 101, 341 IEEE802.3x 101, 341 frames tagged 128, 358 untagged 128, 358 front panel 32 FTP 266 file transfer procedure 266 restrictions over WAN 267

# G

GARP (Generic Attribute Registration Protocol) 353 GARP timer 353 GbE combo ports number of 20 general setup 90 General Setup screen 90, 329 getting help 68 gigabit ports 32 GMT (Greenwich Mean Time) 91, 331 gratuitous ARP 254 green Ethernet 206 and uplink port 206 auto power down 206 EEE 206 short reach 206 grounding 36 GS1350 Series comparison table 20 models 20 GVRP 353 GVRP (GARP VLAN Registration Protocol) 353

# Η

hardware installation 26

hardware monitor 89, 329 hardware overview 32 HTTPS 286 certificates 286 implementation 286 public keys, private keys 286 HTTPS Certificates screen 265 HTTPS example 286

# I

IANA (Internet Assigned Number Authority) 392 Identity Association (IA) 398 IEEE 802.3af 21 IEEE 802.3at 21 IEEE 802.3az 206 IEEE 802.3bt 21 IGMP snooping 170 IGMP snooping and VLANs 171 ingress port 135 ingress rate 151 initial setup 69 Innovation, Science and Economic Development Canada ICES statement 403 installation air circulation 26 desktop 27 rack-mounting 29 transceiver 34 wall mounting 27 installation requirements wall mounting 27 installation scenarios 26 Interface Setup screen 107 Internet Protocol version 6, see IPv6 IP configuration 96 routing domain 94, 360 status 95 IP address 95, 96 IP Address Information 327 IP interface 94, 360 **IP** Setup quick link 327

IP setup 360 IP Setup screen 73, 94, 360 IP Status Detail screen 95 IP subnet mask 95, 96 IPv6 395 addressing 395 enable in Windows 7 401 EUI-64 397 global address 395 interface ID 397 link-local address 395 Neighbor Discovery Protocol 395 neighbor table 313 ping 395 prefix 395 prefix length 395 stateless auto-configuration 397 unspecified address 396 IPv6 cache 399 IPv6 Configuration screen 111 IPv6 Global Address Setup screen 114 IPv6 Global Setup screen 111 IPv6 interface 107 DHCPv6 client 117 enable 112 global address 114 alobal unicast address 110 link-local address 113 link-local IP 110 neighbor discovery 115 neighbor table 116 stateless auto-configuration 112 status 108 IPv6 Interface Setup screen 113 IPv6 Interface Status screen 109 IPv6 Link-Local Address Setup screen 113 IPv6 Neighbor Setup screen 117 IPv6 neighbor table 313 IPv6 Neighbor Table screen 313 IPv6 screen 108

### J

Java permission 43, 384 JavaScript 43, 384

### L

LACP 156 system priority 160, 348 timeout 161, 348 Layer Link Discovery Protocol (LLDP) 324 LED description 39 LEDs 39 limit MAC address learning 164 link aggregation 54, 156 dynamic 156 ID information 157 setup 158, 345 traffic distribution algorithm 158, 345 traffic distribution type 159, 346 trunk group 156 Link aggregation (trunking) 345 Link Aggregation Control Protocol (LACP) 156 Link Aggregation Control Protocol screen 347 Link Aggregation screen Wizard 54 Link Aggregation Setting screen 345 Link Aggregation Status screen 344 Link Layer Discovery Protocol 208 LLDP 208, 324 basic TLV 223 global settings 222 local port status 212 organization-specific TLV 224 status of remote device 216 TLV 208 LLDP (Link Layer Discovery Protocol) 208 LLDP screen 210 LLDP-MED 209 classes of endpoint devices 209 example 209 LLDP-MED Configuration screen 225 LLDP-MED Location screen 227 lockout 67 Switch 67 log message 295 login 43 password 66 privilege level 276 login account administrator 274, 364

non-administrator 274, 364 login accounts 274, 364 configuring via Web Configurator 274, 364 multiple 274, 364 login password 365 edit 275 Logins screen 274, 364 loop guard 196, 348 examples 197, 349 port shut down 197, 350 setup 198, 350 vs. STP 196, 348 Wizard 56 Loop Guard screen 350

## Μ

MAC (Media Access Control) 89, 329 MAC address 89, 308, 329 maximum number per port 164 MAC address learning 93, 164 specify limit 164 MAC Based VLAN screen 130 MAC freeze 164 MAC table 305 display criteria 307 how it works 305 sorting criteria 307 transfer type 307 viewing 306 MAC-based VLAN 130 maintenance 257 configuration backup 262, 376 current configuration 258 firmware 260, 377 main screen 258 restore configuration 261, 379 Maintenance screen 257 Management Information Base (MIB) 279, 368 management IP address 71 management port 135 managing the device cluster management 25 good habits 25

NCC 25 using FTP, see FTP 25 using SNMP 25 using Telnet, see command interface 25 using the command interface, see command interface 25 ZON Utility 25 maximum transmission unit 310 Maximum Transmission Unit (MTU) 109 Mbuf (Memory Buffer) 263, 380 MD5 (Message Digest 5) 373 MDIX (Media Dependent Interface Crossover) 33 Media Access Control 89, 329 Memory Buffer 263 MIB and SNMP 279, 368 supported MIBs 280 MIB (Management Information Base) 279, 368 mirroring ports 154 Mirroring screen 154 monitor port 154 mounting brackets 30 MSTP 144 MTU 310 MTU (Multi-Tenant Unit) 92 multicast IP addresses 170 setup 171 multicast MAC address 138 Multiple Spanning Tree Protocol, see MSTP 144 Multi-Tenant Unit 92

# Ν

navigation panel Standard mode 62 Surveillance mode 64 Nebula Switch Registration screen 120 Neighbor Detail screen 86, 324 Neighbor Discovery Protocol (NDP) 399 Neighbor screen 84 network applications 21 network element (NE) 368 network management system (NMS) 279, 368 NTP (RFC-1305) 91, 330

## 0

one-time schedule 165 ONVIF 362 enable 235 quick link 327 ONVIF protocol 235, 360, 362 ONVIF screen 362 option 82 243 Organizationally Unique Identifiers (OUI) 129 Org-specific TLV Setting screen 224

# Ρ

password 66 administrator 46, 275, 365 change via Wizard 53 password change via Password / SNMP link 45 Path MTU Discovery 310 Path MTU Table screen 310 Per-Hop Behavior 237 PHB 237 ping, test connection 293 PoE PD priority 105, 339 power management mode 105, 338 power-up mode 104, 333, 338 PoE (Power over Ethernet) 101 PoE features by model 21 PoE ports number of 20 PoE Setup quick link 327 PoE Setup screen 104 PoE standards 21 PoE Status screen 102 PoE Time Range Setup screen 104 port setup 99

speed/duplex 100 Port Based VLAN Setup screen 134 port cloning 311, 312 advanced settings 311, 312 basic settings 311, 312 port details 316 port isolation Setting Wizard 135 port mirroring 154 port redundancy 156 Port screen DHCP snooping 192 DHCPv4 Global Relay 246 DHCPv4 VLAN 249 SNMP traps 371 port security 163 address learning 164 limit MAC address learning 164 setup 163 port setup 340 quick link 327 Port Setup screen 99, 340 port status 315 port details 316 port utilization 321 port utilization 321 Port VID (PVID) 70 port VLAN ID, see PVID 128, 358 port VLAN trunking 122, 353 port-based VLAN 133 all connected 135 configure 133 port isolation 135 settings wizard 135 ports diagnostics 293, 294 mirroring 154 speed/duplex 341 standby 157 Power Budget PoE 21 power connections 38 power connector 38 power management mode PoE 21 powered device (PD) 101

prefix delegation 398 priority level queue assignment 93 priority queue assignment 93 product registration 406 PVID 122, 352

# Q

QoS 237 priority setting 60 QoS setting 59 Quality of Service 237 queue weight 168 queuing 167, 168 SPQ 167 WRR 167 queuing method 167, 169 Quick Setup screen 327

# R

rack-mount 20 rack-mounting 29 installation requirements 29 precautions 30 RADIUS 177 advantages 177 and tunnel protocol attribute 183 setup 177 Rapid Spanning Tree Protocol (RSTP) 144 Rapid Spanning Tree Protocol, see RSTP 144 Read Only Memory (ROM) 380 rear panel 36 reboot load configuration 259, 378 reboot system 259, 378 Reboot System screen 378 recurring schedule 165 registration product 406 Regulatory Notice and Statement 403

remote management 277, 366 service 278, 367 trusted computers 278, 367 Remote Management screen 366 RESET button 36, 67 resetting 35, 67, 258 to factory default settings 258 restore configuration file 379 RESTORE button 36, 67 restore configuration 261 restoring configuration 35, 67 RFC 3164 296 Round Robin Scheduling 167 Router Advertisement (RA) 398 routing domain 94, 360 **RSTP 144** configuration 147 rubber feet attach 27 running configuration 258 erase 258 reset 258

# S

safety warnings 404 save configuration 66, 259, 380 Save Configuration screen 379 Save link 67 schedule one-time 165 recurring 165 type **166** screw anchors using 28 Secure Shell, see SSH service access control 276, 374 service port 276, 374 Service Access Control screen 374 Setup Wizard parts 51 Setup Wizard screen 45 SFP interface

number of 20 SHA (Secure Hash Algorithm) 373 Simple Network Management Protocol (SNMP) 368 Simple Network Management Protocol, see SNMP Small Form-factor Pluggable (SFP) 33 SNMP 279 agent 279, 368 and MIB 279, 368 authentication 273, 274, 372, 373 communities 46, 270, 369 management model 279, 368 manager 279, 368 MIB 280 network components 279, 368 object variables 279, 368 protocol operations 279, 368 security 273, 372, 373 security level 274 settings 368 setup 269, 368 traps 270, 370 users 272, 372 version 3 and security 279, 368 versions supported 279, 368 **SNMP** agent enable via Wizard 53 SNMP screen 369 SNMP traps 280 supported **280**, **283 SNMP** version select 53 Spanning Tree Protocol (RSTP) 350 Spanning Tree Protocol, see STP 144 SPQ (Strict Priority Queuing) 167 SSH encryption methods 285 how it works 284 implementation 285 SSH (Secure Shell) 284 SSL (Secure Socket Layer) 286 standby ports 157 static MAC address 136 static MAC forwarding 136 Static MAC Forwarding screen 136 static multicast forwarding 138 Static Multicast Forwarding screen 139

static VLAN 126, 356 control 127, 357 tagging 127, 357 Static VLAN screen 70, 356 status 60, 82, 322 port 315 STP 146 VLAN 123, 354 Status screen 82 STP 144 bridge ID 146 bridge priority 148 designated bridge 145 edge port 149 forwarding delay 148 Hello BPDU 145 Hello Time 146, 148 how it works 145 Max Age 146, 148 path cost 144, 149 port priority 149 port role 147 port state 145, 147 root port 145 status 146 terminology 144 vs. loop guard 196, 348 STP Path Cost 145 subnet masking 397 Summary screen 322 Surveillance mode 21, 322 overview 322 Switch DHCP client 43 switch lockout 67 Switch reset 35. 67 Switch Setup screen 92 syslog 296 protocol 296 settings 296 setup 296 severity levels 296 Syslog Setup screen 296 System Info screen 88, 328 system information 88, 328 system reboot 259, 378

# Т

TACACS+ 176 tagged VLAN 121, 352 Tech-Support 262, 380 log enhancement 262, 380 Tech-Support screen 262 temperature indicator 89, 329 Terminal Access Controller Access-Control System Plus 176 terminal emulation software parameters 38 time current 91, 330 daylight saving 91 format 91 Time (RFC-868) 91, 330 time range 165 time server 91, 330 time service protocol 91, 330 format 330 ToS 237 trademarks 406 transceiver connection speed 34 installation 34 removal 35 transceiver MultiSource Agreement (MSA) 33 transceivers 33 Trap Group screen 270, 370 traps destination 270, 369 troubleshooting 81 trunk group 156 Trunk Tagged port 59 trunking 156 trusted ports DHCP snooping 193 tunnel protocol attribute and RADIUS 183 tutorial DHCP snooping 74 tutorials 74 Type of Service 237

## U

untrusted ports DHCP snooping User Information screen SNMP **272**, user name default **44** user profiles UTC (Universal Time Coordinated)

# V

Vendor ID Based VLAN screen 131 Vendor Specific Attribute, see VSA 182 VID 98, 124, 125, 354, 355, 361 number of possible VIDs 122, 352 priority frame 122, 352 VID (VLAN Identifier) 122, 352 View-based Access Control Model (VACM) 373 Virtual Local Area Network 92 **VLAN 92** acceptable frame type 128, 358 and IGMP snooping 171 automatic registration 352 creation 78 ID 121, 352 ingress filtering 128, 358 introduction 92, 121, 352 number of VLANs 124, 354 port number 125, 355 port settings 127, 358 port-based 135 port-based VLAN 133 port-based, isolation 135 port-based, wizard 135 PVID 128, 358 static VLAN 126, 356 status 123, 124, 125, 354, 355 tagged 121, 352 terminology 353 trunking 122, 128, 353, 358 type 93, 123 VLAN (Virtual Local Area Network) 92 VLAN Detail screen 355

VLAN ID 121, 352 VLAN member port 59 VLAN number 95, 96, 98, 361 VLAN Port Setting screen 358 VLAN setting Wizard 58 VLAN Setting screen 250 DHCPv4 248 VLAN Status screen 354 VLAN terminology 353 VLAN trunking 128, 358 VLAN trunking 128, 358 VLAN-unaware devices 70 voice VLAN 128 Voice VLAN Setup screen 129 VSA 182

### W

wall mounting 27 distance above the floor 27 distance between holes 27 wall-mount 20 warranty 406 note 406 Web browser pop-up window 43, 384 Web Configurator getting help 68 home 60 home screen 61 login 43 logout 68 navigating components 61 navigation panel 62 online help 68 usage prerequisite 43 weight 168 Windows OS version check 47 wizard setup 51 WRR (Weighted Round Robin Scheduling) 167

## Ζ

ZDP 47 ZON (Zyxel One Network) 406 ZON Utility 47 compatible OS 47 fields description 51 icon description 50 installation requirements 47 introduction 20 minimum hardware requirements 47 network adapter select 49 password prompt 50 run **48** supported firmware version 48 supported models 48 Switch IP address 43 ZON utility use for troubleshooting 383 ZyNOS (Zyxel Network Operating System) 266, 406 Zyxel AP Configurator (ZAC) 51 Zyxel Discovery Protocol (ZDP) 47